Using FreeHand MX

CONTENTS

Macromedia FreeHand MX is a vector-based drawing application. With FreeHand, you can create vector graphics that can be scaled and printed at any resolution, without losing detail or clarity.

You can use FreeHand to create print and web illustrations such as logos and advertising banners. You can also use FreeHand to turn your artwork into Macromedia Flash animations.

The FreeHand user interface contains a workspace and Tools panel that are consistent with other Macromedia products such as Macromedia Dreamweaver, Fireworks, and Flash, to give you a true integrated print and web solution. In addition, now you can view and test your FreeHand documents in a Macromedia Flash Player window without ever leaving the FreeHand environment.

System requirements

FreeHand runs on both Microsoft Windows and Macintosh operating systems. Their installers are found on separate CDs. To install FreeHand and begin using the application, you will need the following hardware and software:

- For Windows: An Intel Pentium II processor (300 MHz or faster), or the equivalent, running Windows 98SE, Windows ME, Windows 2000, Windows NT version 4 (Service Pack 6), or Windows XP; enough random-access memory (RAM) to meet your operating system's requirements, plus 64 MB of application memory (128 MB recommended); 70 MB of available hard disk space; a CD-ROM drive; a color monitor capable of 1024 x 768 pixel resolution and 16-bit display (thousands of colors, millions of colors recommended); Adobe Type Manager version 4 or later with Type 1 fonts; and a PostScript Level 2–compatible printer or later (recommended).

- For the Macintosh: a Power Macintosh G3 (or faster) computer running Mac OS 9.1 or later, or Mac OS 10.1 or later; enough RAM to meet your operating system's requirements, plus 64 MB of application memory; 70 MB of available hard disk space; a CD-ROM drive; a color monitor capable of 1024 x 768 pixel resolution and 16-bit display (thousands of colors, millions of colors recommended); Adobe Type Manager version 4 or later with Type 1 fonts (Mac OS 9.x); a PostScript Level 2–compatible printer or later (recommended); and QuickTime 6 (Mac OS 9.x).

Installing and starting FreeHand

This section describes how to install FreeHand on your hard disk and start the application.

Before you begin, make sure your computer meets the requirements listed under "System requirements" on page 7. Read the Read Me document on the FreeHand CD for late-breaking information.

To install and start FreeHand in Windows:

1   Disable any virus-protection software.

2   Insert the FreeHand CD into the computer's CD-ROM drive.

3   Follow the onscreen instructions. The FreeHand installer prompts you to enter the serial number found on your registration card.

4   Select Start > Programs > Macromedia FreeHand MX > FreeHand MX to launch FreeHand.

To install and start FreeHand on the Macintosh:

1   Insert the FreeHand CD into the computer's CD-ROM drive.

2   From the Apple menu, select Control Panels > Extensions Manager.

3   Disable virus-protection extensions and restart your computer.

   The CD folder appears on your desktop.

4   Open the FreeHand MX folder.

5   Double-click the FreeHand MX Installer icon to launch the FreeHand installer.

6   Follow the onscreen instructions. The FreeHand installer prompts you to enter the serial number found on your registration card.

   When the installation is complete, the FreeHand folder opens on your desktop.

7   If prompted, restart your computer.

Uninstalling FreeHand

To uninstall FreeHand, you use Add/Remove Programs (Windows) or the installer (Macintosh) to ensure that all FreeHand files are removed from your system.

To uninstall FreeHand in Windows:

1   Select Start > Settings > Control Panel.

2   Double-click Add/Remove Programs.

3   Select Macromedia FreeHand MX from the list of programs that can be removed.

4   Click the Add/Remove button.

5   Follow the onscreen instructions.

   All FreeHand MX program files are removed from your system.

To uninstall FreeHand on the Macintosh:

1 Insert the FreeHand CD into the computer's CD-ROM drive and launch the installer.

2 A pop-up menu prompts you to select an option. Select Uninstall.

3 Follow the onscreen instructions.

> **Note:** If you used custom installation to install FreeHand in a folder other than the default folder, you must specify the same folder when uninstalling.

The installer removes all FreeHand application files from your computer.

Resources for learning FreeHand

FreeHand MX includes a variety of media to help you learn the program quickly and become proficient in creating your own FreeHand illustrations. These resources include *Using FreeHand*, a user's guide that comes in two formats: the help system, and in book form as a PDF file on the application CD.

In addition, Macromedia presents helpful information via the Answers panel. The Answers panel gives you easy access to the latest information on the Macromedia website. On the website, the FreeHand Support Center (www.macromedia.com/support/freehand) offers support and problem-solving information. The Designer & Developer Center (www.macromedia.com/desdev) presents information to help you improve your skills and learn new ones.

FreeHand lessons

If you are new to FreeHand, or if you have used only some of its features, start with the lessons. The lessons introduce you to the main features of FreeHand, letting you practice on isolated examples.

To view the lessons:

1 With a working Internet connection, do one of the following:

- Select Help > Learning FreeHand.

- Select Window > Answers. In the Answers panel, select the Tutorials link.

    A browser window displays the "Learning FreeHand MX" web page.

2 Select one of the lessons in the list.

FreeHand tutorial

The FreeHand tutorial presents a hands-on introduction to the FreeHand workflow by leading you through the creation of a FreeHand illustration. Included in the tutorial are steps involving many features that are new to FreeHand MX. The tutorial assumes that you already understand the topics covered in the FreeHand lessons.

To view the tutorial:

1 With a working Internet connection, do one of the following:

- Select Help > Learning FreeHand.

- Select Window > Answers. In the Answers panel, select the Tutorials link.

    A browser window displays the "Learning FreeHand MX" web page.

2 Select the link to the tutorial.

What's new in FreeHand MX

Whether you design illustrations for print media, the web, or a combination of both, FreeHand MX offers new features that enhance the approachability, creativity, and power of FreeHand.

Standards and interactivity

FreeHand MX has a new user interface that simplifies workflow and organizes the workspace better. The new interface makes FreeHand easier to learn if you already know other Macromedia Studio MX products, including Dreamweaver MX, Flash MX, and Fireworks MX.

Panel grouping/tabs   Panels are now conveniently docked together at the right edge of the application window. You can move, separate, or combine these customizable panel groups. For more information, see "Using panels" on page 15.

Object panel   The Object panel is a context-sensitive panel that lets you view and change properties for selected objects and text. It is extremely useful in performing practically any drawing task. For more information, see "Using the Object panel" on page 107.

Launching and editing Flash   FreeHand can now launch Flash to edit imported Flash movies. For more information, see "Editing imported Flash movies" on page 336.

Launching and editing Fireworks   When you're editing a bitmap file, FreeHand can automatically launch Macromedia Fireworks, letting you use Fireworks bitmap editing tools to modify the image or to make quick optimization changes. Together, the two applications give you a more streamlined workflow for editing and designing graphics. For more information, see "Launching Fireworks to edit imported bitmap images" on page 320 and "Launching Fireworks to optimize bitmap images" on page 321.

Answers panel   The Answers panel helps you work more effectively by giving you quick access to Macromedia website content such as tutorials, lessons, TechNotes, and other useful information. To learn more, see "The Answers panel" on page 21.

Power illustration

Many new features make FreeHand MX an even more powerful illustration tool.

Extrude tool   The new Extrude tool lets you apply 3D extrusion effects to an object. To learn more, see "Extruding objects" on page 205.

Multiple strokes and fills   With FreeHand MX, you can now apply more than one stroke or fill to an object, opening up fascinating new potentials for your illustrations. See "Adding strokes and fills to objects" on page 165.

Live raster effects and transparency   Live raster effects work similarly to some of the image manipulation tools found in photo editing software such as Fireworks. These effects act as properties of the object they are applied to, and do not modify the object itself. For more information, see "Applying live raster effects" on page 198.

Transparency effects allow a fill or stroke (or parts of a fill or stoke) to appear clear or semi-opaque. To learn more, see "Using a Transparency effect attribute" on page 204.

Live vector effects   Live vector effects work similarly to some of the other object manipulation capabilities of FreeHand, except that they act as properties of the object they are applied to, and do not modify the object itself. For more information, see "Applying live vector effects" on page 194.

Blend tool   Blends are now easier to apply. The Blend tool lets you drag a line between two blend shapes to create the blend. See "Using the Blend tool" on page 213.

Calligraphic stroke   This new feature lets you create beautiful calligraphic strokes as part of your vector objects. For more information, see "Using calligraphic stroke attributes" on page 173.

Eraser tool   The new Eraser tool lets you erase parts of vector objects. To learn more, see "Erasing paths" on page 95.

Image alpha channels   FreeHand MX provides full import and display support for the alpha channels of common bitmap image files. See "Working with bitmap images in FreeHand" on page 318.

New gradient fills   Two new gradient fills have been added to FreeHand MX: rectangular and cone gradients. Also, gradient fills now have new options. For more information, see "Using gradient fill attributes" on page 179.

Brush enhancements   The Rounded Corners attribute gives brushed paths a more fluid and natural look as they wrap around corners and sharp angles. To learn about brushes, see "Using brush stroke attributes" on page 169.

Web-related features

Many new and enhanced FreeHand MX features help you plan, mock up, and develop website components. With these additions, FreeHand MX becomes the tool of choice for the beginning stages of web development, and the first step in the Macromedia Studio MX workflow.

Connector tool   The Connector tool lets you draw connector lines that dynamically link objects together. Connector lines automatically adjust when you move connected objects in the Document window. For more information on the Connector tool, see "Dynamically linking objects" on page 102.

Action tool   The Action tool lets you assign Flash actions to an object. For more information, see "Using the Action tool" on page 334.

Output area   You can now print or export an area of the Document window by using the Output Area tool. To learn more, see "Exporting an area of a document" on page 348.

Simplified movie settings   It's now easier to control the settings of a Flash movie inside FreeHand. For more information, see "Using Flash movies" on page 335.

SWF import, placement, and export   Flash SWF files can be directly imported and placed in FreeHand MX, and then exported. See "Editing imported Flash movies" on page 336 and "Exporting FreeHand documents as Flash movies" on page 336.

Ease of use

Finally, many new FreeHand MX features are dedicated to making your workflow easier than ever.

Tools panel changes   The Tools panel has been reorganized to make finding and using your tools easier. To find out more, see "Using the Tools panel" on page 24.

Gradient fill handles   Gradient fill handles increase your control in manipulating gradient fills. See "Using gradient fill attributes" on page 179.

Add page button   Adding a new page to your document is now as easy as clicking the Add Page button at the bottom of the application window. See "Working with pages" on page 44.

Style behavior changes   You can control what types of object attributes a style will apply to. See "Applying styles" on page 302.

CHAPTER 1
FreeHand Basics

To get the most out of working in Macromedia FreeHand MX, it's helpful to familiarize yourself with the FreeHand workspace, which includes the Document window, command menus at the top of your screen, tools and panels for editing and adding objects, and the pasteboard in which you create your artwork.

You can add more commands to the menus by installing software applications called plug-ins, and you can add and rearrange tools in toolbars by customizing your work environment.

About vector graphics and bitmap images

FreeHand is a vector-graphic drawing application. A vector-graphic image is resolution-independent—it can be scaled to any size and printed on any output device at any resolution, without losing detail or clarity. In contrast, bitmap graphics—commonly used in image-editing applications—are composed of pixels. Their display depends on the resolution of the monitor or printer. Bitmap graphics can appear jagged and lose detail when they're scaled onscreen or printed at a low resolution. For more details on vector graphics, see "About vector graphics" on page 69.

Although vector graphics always appear at your computer's maximum screen resolution, you can specify a lower resolution for preparing draft documents. For more information, see Chapter 14, "Printing," on page 375.

The Macromedia Studio MX interface

FreeHand is part of the Macromedia MX product family, so it utilizes the Macromedia MX workspace, an interface that is shared by the other Macromedia MX products. Consistency among products allows users of one product to easily learn and use the others.

The first time you open FreeHand, the workspace consists of the Document window and a set of docked panels. In Windows, the workspace is integrated, so you can dock all panels and toolbars to the single, larger application window. This helps to eliminate the clutter associated with having many panels and toolbars open at the same time.

Panels

Units pop-up menu

Drawing Mode pop-up menu

Add Page button

Go to Page pop-up menu

Page selector buttons

Magnification pop-up menu

The integrated workspace is not supported on the Macintosh. However, panels and toolbars are docked together by default in a configuration that resembles the integrated workspace in Windows.

On all operating systems, FreeHand panels, toolbars, and windows can be rearranged, repositioned, and docked to one another.

For more details about the FreeHand workspace, see the sections that follow.

The Document window

In addition to panels, when you launch FreeHand you'll also see the Document window and the pasteboard—the area that contains the pages of your document.

The Document window contains all your documents' objects. Objects must be placed on a page in order to be printed with the Print command; if they are placed on the pasteboard outside of page boundaries, you can print them using the Output Area feature. For more information, see "Defining an output area" on page 382.

The pasteboard measures up to 222 x 222 inches and can hold 520 letter-sized pages. You can customize the buttons, panels, and toolbars. For more information on panels and toolbars, see "Using panels" on page 15 and "Customizing toolbars" on page 38.

If you modify a document, an asterisk appears next to the document name in the Document window until you save it again. For more information, see "Saving files" on page 341.

Using panels

When you first launch FreeHand, visible panels (excluding the Tools panel) are docked together at the right edge of the application window. You can move, separate, or combine these customizable panel groups. Panels and panel groups can be opened, closed, docked, expanded, and collapsed.

The following panels are grouped together by default:

• The Object and Document panels reside in a panel group called Properties.

• The Swatches, Styles, and Library panels reside in a panel group called Assets.

• The Color Mixer and Tints panels reside in a panel group called Mixer and Tints.

• The Align and Transform panels reside in a panel group called Align and Transform.

• The Find & Replace panel and the Select panel reside in a panel group called Find & Replace and Select.

• The Halftones, Layers, Answers, and Navigation panels are not grouped with other panels by default, but you can group them if you want. With the exception of the Properties and Assets panel groups, when you group panels together, all panel group names appear in the panel group title bar. You can, however, name panel groups anything you like; see "Grouping panels" on page 19.

The Layers panel, the Answers panel, and the Properties, Assets, and Mixer and Tints panel groups appear onscreen by default when you first open FreeHand, although some may be collapsed.

To open a panel:

Select its name from the Window menu.

If a panel was already open, choosing its name from the Window menu closes it or collapses it, depending on whether the panel is docked.

Note: The Find & Replace and Select panels are available in the Edit menu.

To expand or collapse a panel:

Click the panel group name or the expander arrow beside it.

Tip: If a panel is open but collapsed, you can select the panel's name from the Window menu to expand it.

To close a panel:

Click the Close button at the top of a floating panel or floating panel group.

To activate a panel in a panel group:

Click the panel's name or icon.

To move an undocked panel or panel group to another location:

Drag the panel group by its title bar (the area above the panel group name).

Tip: Be careful not to drag a panel group's gripper, or you might inadvertently dock it to another panel group.

To switch between open, floating panel groups (Windows):

Press Control+Tab.

To show or hide all open panels:

Select View > Panels.

To show or hide panels docked to the application window (Windows only):

Click the small arrow that separates the docked panel area from the rest of the application window.

Click to show or hide docked panel area

To return panels to their default positions:

1 Exit FreeHand.

2 Locate the Macromedia/FreeHand/11/English/Settings folder within your user-specific Application Data (Windows) or Application Support (Macintosh) folder.

   Note: The exact location of your user-specific Application Data or Application Support folder varies depending on your operating system. For more information, see your operating system's documentation.

3 Delete the fhprefs.txt (Windows) or Preferences (Macintosh) file.

To define the appearance of panel labels:

1 Display panels preferences by doing one of the following:

• In Windows, press Control+U, then click the Panels tab.

• On the Macintosh, press Command+U, then click the Panels category.

2 From the Label Panel Tabs With pop-up menu, choose to label panels with text only, icon only, or a text and icon combination.

3 Click OK.

Docking panels

You can dock individual panels and panel groups to one another.

In Windows, you can also dock panels to the integrated application window. Panels and panel groups in Windows can be docked on the right side, left side, or both sides of the screen.

To dock a panel or panel group:

Drag the panel or panel group by its gripper to the desired location.

Panel gripper

When a panel or panel group is about to dock to another panel or panel group, a highlight indicates where the panel or panel group will be dropped if you release the mouse button.

In Windows, when a panel or panel group is about to dock with the integrated application window and there are no other panels or panel groups currently docked in that location, an outline indicates the docking position.

To undock a panel or panel group:

Drag the panel or panel group by its gripper to the desired location.

Using a panel's Options menu

Each panel has an Options menu listing a range of choices specific to the active panel.

To open a panel's Options menu:

Click the Options menu control in the upper right corner of the panel group.

Options menu control

Grouping panels

You can group panels with other panels, add them to existing panel groups, or remove them from panel groups.

When you combine panels into a group, the panel group title reflects the names of each of the panels. If a panel group title becomes too long, you can rename it.

To group panels:

1 Open or expand the panel that you want to add to a group.

2 Select Group [*Panel Name*] With from the panel's Options menu, and select a panel or panel group from the pop-up menu.

To remove a panel from a group:

1 Activate the panel you want to remove from the group.

2 Select Group [*Panel Name*] With from the panel's Options menu, and select New Panel Group.

The panel becomes its own panel group.

To rename a panel group:

1 With any panel active in the panel group, select Rename Panel Group from the panel's Options menu.

2 Type a new name.

3 Click anywhere outside the panel group, or press Enter (Windows) or Return (Macintosh).

The Properties panel group

The Properties panel group contains two panels that allow you to display and alter the properties of objects and pages.

The Object panel displays properties for a selected object or objects. The top half of the panel displays a list of properties, such as stroke, fill, and effect, applied to a selected object. The bottom half of the panel is context-sensitive; it displays options for the selected property in the list above it.

The Object panel is used in almost all drawing tasks. For more information about the Object panel, see "Using the Object panel" on page 107; "Applying attributes to strokes" on page 166; "Applying attributes to fills" on page 177; "Displaying type attributes in the Object panel" on page 248; and Chapter 7, "Special Effects," on page 193.

The Document panel displays thumbnail icons for each page in your document. Using the Pointer tool, you can move the thumbnails in the panel to move the corresponding pages on the pasteboard. You can choose from three magnified views. The Document panel also has options for adding, duplicating, and removing pages, plus options to set page size, orientation, bleed, and printer resolution. For more information, see "Using the Document panel" on page 43.

The Answers panel

The Answers panel helps you work more effectively in FreeHand by providing quick access to Macromedia website content such as tutorials, TechNotes, and other useful information.

To get the latest FreeHand information from macromedia.com, with an active Internet connection, click the Update button.

Using toolbars

FreeHand has several toolbars that can either float or be docked along the top, left, and bottom of the Document window. You can customize toolbars; for more information, see "Customizing toolbars" on page 38.

You can display information about each tool as the pointer passes over it (see "Using tooltips" on page 27).

FreeHand has the following toolbars:

- The Tools panel is actually a toolbar. Like other toolbars, it can be docked to the top or bottom of the application window. For more information, see "Using the Tools panel" on page 24.

- The Main toolbar replicates many of the menu commands and lets you create, open, or save documents; import files; find and replace graphics; lock and unlock objects; and display commonly used panels. For more information, see "The Main toolbar" on page 23.

- The Text toolbar contains common text commands and lets you choose a font, font size, font style, leading, and alignment as well as other text-related functions. For more information, see "The Text toolbar" on page 249.

- The Envelope toolbar has tools for applying envelope transformations to objects or groups. For more information, see "Creating perspective" on page 227.

- The Info toolbar gives information on selected objects, depending on the object type and current action. Possible items included in this toolbar are the object type, the pointer position, the change in an object's position, the object's angle, the center of rotation, the radius, and the number of sides the object has.

- The Status toolbar (Windows) appears along the bottom of the Document window. For more information, see "The Status toolbar" on page 25.

- The Xtra Tools toolbar contains plug-in drawing and transformation tools, which can be added and removed from the application. For more information, see "Using and managing Xtras" on page 27.

- The Xtra Operations toolbar contains buttons for applying path operations. For more information, see "Combining paths" on page 127.

To dock and undock toolbars:

Drag the toolbar to the desired location.

An outline appears indicating where the toolbar will be dropped if you release the mouse button.

To show or hide toolbars, do one of the following:

- To show or hide individual toolbars, select Window > Toolbars and select the toolbar name.

- To show or hide all active toolbars, select View > Toolbars.

- To show or hide the Tools panel, select Window > Tools.

The Main toolbar

The Main toolbar contains the basic commands you use when beginning your FreeHand project. You use the Main toolbar to open document files and to manage the appearance of your document. The Main toolbar also provides quick access to many common panels. The following buttons are available on the Main toolbar by default, but you can add other buttons if you want. For more information, see "Customizing toolbars" on page 38.

	Creates a new document		Opens the Align panel
	Opens an existing document		Opens the Transform panel
	Saves the active document		Opens the Library panel
	Imports a file or object		Opens the Object panel
	Prints the active document		Opens the Color Mixer panel
	Locks the selected objects		Opens the Swatches panel
	Unlocks the selected objects		Opens the Layers panel
	Opens the Find & Replace panel		

Using the Tools panel

The Tools panel contains tools that allow you to select, draw, and edit objects; apply color to objects; and create text. It is divided into four sections: Tools, View, Colors, and Snap. You can customize the panel by adding and removing buttons.

Some tools in the Tools panel have a down arrow in the lower right corner. The down arrow indicates the presence of a tool pop-up menu. You can select the other members of a tool pop-up menu by clicking and holding on any tool that has a down arrow, then selecting from the pop-up menu that appears.

Tools

Pen tool
Bezigon tool (B, 8)

Line tool (N)
Arc tool
Spiral tool

Scale tool
Rotate tool
Reflect tool
Skew tool

Perspective tool
3D Rotation tool
Fisheye Lens

Pencil tool (Y)
Variable Stroke Pen tool
Calligraphic Pen tool

Rectangle tool
Polygon tool

Freeform tool (F)
Roughen tool
Bend tool

Extrude tool
Smudge tool
Shadow tool

Blend tool
Mirror tool
Graphic Hose tool
Chart tool

View

Colors

Snap

To select a tool from a tool pop-up menu:

1 In the Tools panel, click and hold on a tool that is part of a tool pop-up menu.

2 Select a tool from the pop-up menu that appears.

To add a tool to the Tools panel, do one of the following:

• Select Window > Toolbars > Customize. Expand the desired category in the Commands list, and drag a tool from the right side of the dialog box into the Tools panel.

• Alt-drag (Windows) or Command-drag (Macintosh) a tool from another toolbar into the Tools panel.

To remove a tool from the Tools panel, do one of the following:

- Select Window > Toolbars > Customize, and drag the desired button from the Tools panel.

- Alt-drag (Windows) or Command-drag (Macintosh) a tool from the Tools panel.

  Once you remove a tool from the Tools panel, you cannot move the tool back onto the panel without using the Customize dialog box. For more information on customizing toolbars, see "Customizing toolbars" on page 38.

The Status toolbar

The Status toolbar appears along the bottom of the Document window. It contains a page addition button and page selector buttons as well as pop-up menus for magnification, page view, drawing mode, and units of measure.

In Windows, the Status toolbar displays messages about the task in progress or the menu command highlighted. To cancel an operation in progress in Windows, you can click the toolbar's Cancel button.

On the Macintosh, the Status toolbar is permanently docked to the Document window; you can't undock it or move it to another location.

Using preferences

FreeHand preferences let you customize your work environment. Settings stored in the Preferences file include the following:

- Number of undo operations

- Path-editing behavior, path fills, and path behavior

- Default line widths and graphic styles

- Text behavior

- Document views and window location

- Active page settings

- Settings for reviewing documents when closing them

- Attributes of imported and exported files

- Settings for embedding graphics in Encapsulated PostScript (EPS) and other Clipboard formats

- Spelling preferences

- Guide and grid colors and color management options

- Panel display options

- Text effects, small text size ("greeked" type), image screen resolution, and objects set to overprint

- Snap sounds (Macintosh only)

To find an explanation of a particular preference option or set of options, refer to the index.

To display preference options:

1 Press Control+U (Windows) or Command+U (Macintosh).

2 In Windows, click a tab; on the Macintosh, click an item in the Category list.

Windows preference tabs and Macintosh preference categories

To restore all preferences to their default settings:

1 Press Control+U (Windows) or Command+U (Macintosh).

The Preferences dialog box appears.

2 Click Defaults at the bottom of the Preferences dialog box, and click OK.

Using tooltips

Tooltips give you information about a tool name or toolbar button. In FreeHand, tooltips appear by default; you can turn them off if you want.

To display a tooltip:

Pause the pointer over a button on a toolbar.

To turn off tooltips:

1 Display panels preferences by doing one of the following:

- In Windows, press Control+U, then click the Panels tab.

- On the Macintosh, press Command+U, then click the Panels category.

2 Deselect Show ToolTips and click OK.

Using and managing Xtras

Xtras are plug-in software extensions that expand FreeHand capabilities. FreeHand Xtras are developed by Macromedia and third-party companies.

Xtras with similar features are grouped in submenus. A third-party Xtra may appear in the Xtras menu, the Xtra Tools toolbar, the Xtra Operations toolbar, or a custom panel, depending on its design and the customizations made within the user interface.

Xtras included with FreeHand are automatically installed with FreeHand. You can install additional Xtras and remove Xtras.

To install an Xtra:

1 Drag the Xtra file into the Xtras folder, which is located in your FreeHand MX application folder.

Note: On some operating systems, this folder may be located in the English subfolder within the FreeHand MX application folder.

2 Restart FreeHand.

To remove an Xtra:

Drag the Xtra file out of the Xtras folder. (See the previous procedure for folder location.)

To use an Xtra, do one of the following:

- Select the Xtra from the Xtras menu.

- Select Window > Toolbars > Xtra Tools to display the toolbar, and click the Xtra.

- Select Window > Toolbars > Xtra Operations to display the toolbar, and click the Xtra.

Setting the document view

You can set your document view to help you work more efficiently. You can use multiple views to see several pages or documents at once, and you can create custom views.

Commands in the View menu let you choose different ways to view and preview your work. You can set preferences to determine the view and page placement when opening a document.

To set document view and placement preferences:

1 Display document preferences by doing one of the following:

• In Windows, press Control+U, then click the Document tab.

• On the Macintosh, press Command+U, then click the Document category.

2 Select an option to define how documents will appear when opened:

Restore View When Opening Document opens documents at the same magnification as when they were last saved.

Remember Window Size and Location opens documents in the same window size and at the same location as the last saved document.

3 Click OK.

For more information on preferences, see "Using preferences" on page 25.

Anti-aliasing artwork

Anti-aliasing removes jagged edges in onscreen artwork, so it appears smooth even when magnified. Vector objects and text are anti-aliased by default in all drawing modes. You can turn this option off if you want.

Note: On the Macintosh, anti-aliasing is available only if you're running Mac OS X or later.

To turn off anti-aliasing:

1 Display redraw preferences by doing one of the following:

• In Windows, press Control+U, then click the Redraw tab.

• On the Macintosh, press Command+U, then click the Redraw category.

2 Deselect Enable Anti-Aliasing and click OK.

Optimizing document redrawing

You can choose how to view a document onscreen using drawing modes. Drawing modes don't affect object data or print quality. You can also set preferences to control screen redrawing.

The fast drawing modes, Fast Preview and Fast Keyline, optimize redrawing by reducing blend steps to 10 and greeking (dimming) text for onscreen point sizes of 50 and below.

To choose a drawing mode:

Select an option from the Drawing Mode pop-up menu in the Status toolbar (Windows) or at the bottom of the Document window (Macintosh):

Preview displays the document as it will print. (You can't preview custom, PostScript, or textured strokes and fills.)

Fast Preview displays blends with reduced steps and greeked (dimmed) text.

Keyline displays only a black hairline stroke, no fill for objects, and X-boxes for EPS images and bitmap images.

Fast Keyline displays blends with reduced steps and greeked (dimmed) text.

From left to right: Preview, Fast Preview, Keyline, Fast Keyline

To switch between Preview mode and Keyline mode:

Select View > Keyline.

This command is a toggle. A checkmark beside Keyline indicates that the document is in one of the Keyline modes. When no checkmark is displayed, the document is in one of the Preview modes.

To switch between fast modes and other modes:

Select View > Fast Mode or press Control+Shift+K (Windows) or Command+Shift+K (Macintosh).

These commands toggle between fast modes and other modes. A checkmark beside Fast Mode indicates the document is either in Fast Preview or Fast Keyline mode.

To set how scrolling affects redrawing:

1 Display redraw preferences by doing one of the following:

- In Windows, press Control+U, then click the Redraw tab.

- On the Macintosh, press Command+U, then click the Redraw category.

2 Select Redraw While Scrolling to redraw the document when you click a scroll arrow or scroll bar.

   When this option is deselected, the document is redrawn when scrolling stops.

3 Click OK.

To enable object previews while dragging:

1 Display object preferences by doing one of the following:

- In Windows, press Control+U, then click the Object tab.

- On the Macintosh, press Command+U, then click the Object category.

2 Deselect the Alt-Drag Copies Paths option (Windows) or the Option-Drag Copies Paths option (Macintosh), if it is selected.

3 Click OK.

To preview an object while dragging it:

1 Press and hold down Alt (Windows) or Option (Macintosh).

2 Drag the object.

   Note: Before dragging the object, ensure that the Alt-Drag Copies Paths option (Windows) or the Option-Drag Copies Paths option (Macintosh) is deselected in object preferences. See the previous procedure.

To set the maximum number of objects to preview while dragging:

1 Display redraw preferences by doing one of the following:

- In Windows, press Control+U, then click the Redraw tab.

- On the Macintosh, press Command+U, then click the Redraw category.

2 Enter a value in the Preview Drag text box.

   Note: Previewing a large number of objects can slow redrawing.

3 Click OK.

To drag an object without previewing it:

Drag the object within the Document window.

The object's path displays the object's movement, similar to the way in which objects appear in Keyline mode.

Magnifying and reducing the view

You can zoom in or out to magnify or reduce your view using tools, menu commands, or keyboard shortcuts. Using the Zoom tool, you can create custom views based on the applied magnification. Using the View menu or the document's Magnification pop-up menu, you can select magnifications ranging from 6% to 6400%, depending on the menu you use.

In Windows, you can use the right mouse button to magnify a selected area. You specify this behavior through preferences; see "Using the right mouse button (Windows)" on page 33.

To enlarge or reduce a page view using the Zoom tool:

1 Click the Zoom tool.

2 Do one of the following:

• To enlarge the page, click the page.

• To enlarge a selected area, drag the selection.

• To reduce the page view, hold down Alt (Windows) or Option (Macintosh) and click the page.

• To reduce a selected area, Alt-drag (Windows) or Option-drag (Macintosh) the selection.

To enlarge or reduce a page using menu commands, do one of the following:

• Select an increment from the Magnification pop-up menu in the Status toolbar (Windows) or at the bottom of the Document window (Macintosh), or enter a value into the text box. You can also enter a value followed by **x**, up to 256x.

Magnification pop-up menu

• Select View > Magnification to select an increment from 25% to 800%.

• In Windows, right-click in the workspace to display a context menu, then select View and select an increment between 6% and 6400%.

To enlarge or reduce a page using keyboard shortcuts:

1 Click the Zoom tool.

2 Do one of the following:

• To reduce the page view to the next increment, hold down Alt (Windows) or Option (Macintosh) and click the page.

• To zoom out to the lowest magnification, hold down Shift+Alt (Windows) or Control+Option (Macintosh) and click the page.

• To zoom in to the highest magnification, hold down Shift (Windows) or Control (Macintosh) and click the page.

To fit the view to a selection or page:

Select an option from the View menu, or from the Magnification pop-up menu in the Status bar (Windows) or at the bottom of the Document window (Macintosh):

Fit to Page fits the active page inside the Document window.

Fit Selection fits all selected objects inside the Document window.

Fit All fits all pages inside the Document window.

Displaying multiple document views

To see a document at different views or magnifications simultaneously, you can use multiple views and display up to eight windows of the same document at one time.

To open an additional document view:

1 Select Window > New Window.

2 Change the view and magnification of the new window.

To close document views, do one of the following:

• Click the window's Close button (Windows) or close box (Macintosh).

• To close all document views, press Control+Shift+F4 (Windows) or hold down Option and click the close box (Macintosh).

Naming and saving custom views

You can name and save the current view's magnification percentage, drawing mode, and scroll bar positions to recall later.

To save settings with a custom view name:

1 Adjust view elements using the Magnification pop-up menu, Drawing Mode pop-up menu, and scroll bars, as desired.

2 Select View > Custom > New.

3 Name the view and click OK.

To recall a saved view, do one of the following:

• Select the view name from the Magnification pop-up menu.

• Select View > Custom, and select the view from the pop-up menu.

To define, name, and save a view using the Zoom tool:

1 Click the Zoom tool.

2 Shift-drag to define the new view.

The New View dialog box appears after the new view is set.

3 Name the new view and click OK.

To edit a custom view:

1 Adjust view elements to redefine the view using the Magnification pop-up menu, Drawing Mode pop-up menu, and scroll bars.

2 Select View > Custom > Edit.

3 In the Edit Views dialog box, select a custom view name and click Redefine.

Tip: To change the name of a custom view, double-click the custom view name and type a new name.

4 Click OK.

To delete a custom view:

1 Select View > Custom > Edit.

2 Select the view to be deleted.

3 Click Delete; then click OK.

To switch from the current to the previous view:

Select View > Custom > Previous.

Note: You can switch to the previous custom view only if you have created at least two custom views.

Using the right mouse button (Windows)

In Windows, you can choose commands from context menus as you work. By clicking the right mouse button, you can display context-specific commands for panels and objects, including paths, text blocks, bitmap images, EPS paths, groups, and blends.

You can also use the right mouse button to magnify an area of your document.

To display a context menu, do one of the following:

• Right-click an object to display a context menu with object-specific commands.

- Select multiple objects by pressing Shift as you select the objects or by dragging a bounding box around the objects. Right-click the selection to display common commands.

- Right-click a page, color box, style, or foreground or background layer.

  This approach works in the Document panel, Swatches panel, Layers panel, Styles panel, and Tints panel, as well as for any color swatch, color box, or blank area of the document.

To use the right mouse button to magnify an area of your document:

1 Display general preferences by doing one of the following:

- In Windows, press Control+U, then click the General tab.

- On the Macintosh, press Command+U, then click the General category.

2 Select Right Mouse Button Magnification, and click OK.

   Note: Selecting this option disables Windows context menus.

Printing a shortcut quick-reference card

You can print a shortcut quick-reference card and save a custom card.

To print a shortcut quick-reference card:

1 Select Edit > Keyboard Shortcuts.

2 In the Keyboard Shortcuts dialog box, click Print.

3 In the dialog box that appears, click Print again.

A system Print dialog box appears. Set any desired options and click the appropriate button to send the card to your printer.

To save a custom keyboard shortcut card:

1 Select Edit > Keyboard Shortcuts.

2 In the Keyboard Shortcuts dialog box, click Print.

3 In the dialog box that appears, click Save As.

4 Navigate to a location to save the shortcut card, and enter a filename in the File Name text box.

5 Click Save.

FreeHand produces a text file that can be opened in another application (such as a word processor), where you can format and reorder the text to create your own custom shortcut card. For example, you might want to place the text in a table or sort it by shortcuts, commands, or descriptions.

Customizing your environment

FreeHand lets you customize many aspects of its work environment. You can add and remove keyboard shortcuts, use shortcuts from other applications, rearrange toolbars, and change toolbar buttons.

Customizing shortcuts

To change current keyboard shortcuts or to assign shortcuts to commands that have no shortcuts, you use the Shortcuts tab in the Customize dialog box (Windows) or the Customize Shortcuts dialog box (Macintosh). Although you can assign shortcuts to the Repeat Xtra command, you cannot assign shortcuts to other Xtras.

In addition to the default FreeHand shortcut group, FreeHand provides the default shortcut groups for FreeHand 8, FreeHand 9, and many other applications, including Adobe Illustrator, QuarkXPress, Adobe PageMaker (Macintosh), Adobe Photoshop (Macintosh), and Macromedia Director (Macintosh). You can also copy custom shortcut groups from another user's computer or from another location on your hard disk.

To view and choose from available shortcut groups:

1 Select Edit > Keyboard Shortcuts.

The Customize dialog box (Windows) or the Customize Keyboard Shortcuts dialog box (Macintosh) appears.

Shortcuts tab in Customize dialog box (Windows)

Customize Keyboard Shortcuts dialog box (Macintosh)

2 Select a shortcut group from the Keyboard Shortcuts Setting pop-up menu.

To copy a customized shortcut group from one computer to another:

1 Select the Shortcuts file, located in the Keyboard folder within the Macromedia/FreeHand/11/ English/Settings folder in your user-specific Application Data (Windows) or Application Support (Macintosh) folder.

Note: The location of your user-specific Application Data or Application Support folder varies depending on your operating system. Refer to your operating system's documentation for information on locating this folder.

2 Copy the file to the same location within a user folder on another computer.

The new group's name appears in the Keyboard Shortcuts Setting pop-up menu. (Windows adds the extension .set to the shortcut group file, but the extension does not appear in the Keyboard Shortcuts Setting menu.)

To assign a custom shortcut:

1 Select Edit > Keyboard Shortcuts.

The Customize dialog box (Windows) or the Customize Keyboard Shortcuts dialog box (Macintosh) appears.

2 Do one of the following to create a custom shortcut:

• Select an application from the Keyboard Shortcuts Setting menu.

• To keep all default FreeHand shortcuts intact and create your own shortcut group, click the Plus (+) button under Keyboard Shortcuts Setting. Navigate to a location, name the file, and click Save.

3 In the Commands list, click the plus (+) sign (Windows) or triangle (Macintosh) to expand the categories.

The Commands list replicates all FreeHand menus, with some additional features. If the command to which you want to assign a shortcut is not in a FreeHand menu, expand the Tools/Commands category in the Commands list.

4 Click the name of the command to which you want to assign a new shortcut.

The command description appears under Description. The Current Shortcut Keys text box displays any shortcuts already assigned to the command. A command can have more than one shortcut, but only one appears in the menu.

5 Click in the Press New Shortcut Key text box, then press the key or keys that make up the new shortcut sequence.

The new shortcut appears in the Press New Shortcut Key text box. Any shortcuts already assigned to the command or keyboard sequence are listed under Currently Assigned To.

6 Select how to assign the shortcut:

• Select Go to Conflict on Assign to highlight in the Command list the command for a previously assigned keyboard shortcut.

• Click Assign to assign the new shortcut to the specified command and disable any previous assignment for the shortcut.

7 Repeat steps 4 through 6 to assign additional shortcuts.

8 Click Close to confirm the new shortcut assignments, or click Reset to revert to the previous shortcuts without saving the new shortcuts.

To remove a shortcut:

1 Select Edit > Keyboard Shortcuts.

2 Expand the Commands list to locate and select the desired command.

3 Select the shortcut you want to delete under Current Shortcut Keys.

4 Click Remove.

5 Click Close or select a new shortcut group to confirm the removal.

Customizing toolbars

To customize the form, location, and contents of a toolbar, you can use the Customize dialog box (Windows) or the Customize Toolbars dialog box (Macintosh). You can also drag toolbar buttons.

Note: Disabled buttons cannot be moved or deleted.

To customize toolbars using the Customize command:

1 Select Window > Toolbars > Customize. (Alternatively, in Windows you can select Edit > Keyboard Shortcuts and click the Toolbars tab.)

Toolbars tab in the Customize dialog box (Windows)

Customize Toolbars dialog box (Macintosh)

2 Do one of the following to select the command you want to add:

- Scroll through the Commands list to find the command whose button you want to place on a toolbar. If necessary, click the plus (+) sign (Windows) or the triangle (Macintosh) to expand categories.

- If the command is not in a FreeHand menu, expand the Tools/Commands category.

- Click a menu or menu command to highlight the associated buttons.

- Click a button to highlight the associated menu command.

  The Commands list replicates all FreeHand menus, with some additional features.

3 Drag the button from the Customize Toolbars dialog box to the desired location on a toolbar.

If necessary, existing buttons move to make room for the new button.

To remove a button from a toolbar, do one of the following:

- Select Window > Toolbars > Customize, and drag the button off the toolbar.

- Hold down Alt (Windows) or Command (Macintosh), and drag the button off the toolbar.

Note: You cannot undo this procedure once you drag the button off the toolbar, but you can put a button back using the Customize command. For more information, see the previous procedure.

Dragging a button off the toolbar (left), and the result (right)

To customize toolbars by dragging tool buttons:

To move any button from one toolbar to another, hold down Alt (Windows) or Command (Macintosh), and drag the button to the desired location on the other toolbar.

To duplicate a button for placement on more than one toolbar:

Hold down Alt+Control (Windows) or Option+Command (Macintosh), and drag the button to the second location.

To move a docked toolbar onto the pasteboard:

Drag the gray area of a docked toolbar onto the pasteboard.

A highlight indicates where the toolbar will be dropped if you release the toolbar at that location. The toolbar becomes a resizable floating toolbar when dropped beyond the toolbar area.

To dock a floating toolbar onto the top, bottom, or side toolbar area:

Drag the gray area of the floating toolbar onto the top, bottom, or side toolbar area.

A highlight indicates where the toolbar will be dropped if you release the toolbar at that location. The floating toolbar becomes a regular toolbar when dropped in the area surrounding the pasteboard.

CHAPTER 2
Setting Up Your Document

When you begin your Macromedia FreeHand MX project, you can choose among various document settings to best meet your design and final output requirements. You use the Document panel to set page options such as page size and orientation, bleed value, and final output resolution. You can also use the Document panel to define custom page sizes. You can create templates to use as defaults for creating new documents. You can also create master pages to create a consistent look throughout a document.

To aid in aligning and placing objects in your documents, you can set up guides, grids, and page rulers. You can also set the unit of measure for your document.

If you open or import a document that uses fonts not installed on your system, FreeHand allows you to replace the missing fonts.

In Windows, you can quickly begin a project and simplify your workflow using FreeHand wizards, which are interactive screens that guide you through and simplify a variety of tasks.

Using the Document panel

The Document panel displays a miniature representation of the pasteboard, with thumbnail icons for each page in your document. You can use the Document panel to add and remove pages or set page attributes, such as size, orientation, and bleed, as well as to set document attributes such as target printer resolution. By dragging thumbnails of pages in the Document panel, you can move the corresponding pages on the pasteboard.

To display the Document panel, do one of the following:

- Select Window > Document.

- Click the Document tab in the Properties panel group if it is visible.

- Click the Document panel button in the Main toolbar.

   Note: The Document panel button does not appear by default when you open FreeHand. To add the button to your Main toolbar, see "Customizing toolbars" on page 38.

Working with pages

You can set page options—including page size, page orientation, and bleed value—using the Document panel or the Add Pages dialog box. You can also quickly add pages to a document using the Add Page button.

To set page options:

1 Select Window > Document to display the Document panel if it isn't already open.

Page size pop-up menu

Page orientation

Page thumbnail views

2 Select a page size from the Page Size pop-up menu.

3 Click one of the page orientation buttons to the right of the Page Size pop-up menu to select a page orientation: portrait (tall) or landscape (wide).

4 Enter a desired bleed value in the Bleed text box. The paper dimensions must be larger than the page size you specify. To set the dimensions, select File > Print. For more information on bleeds, see "Printing" on page 375.

5 Click a page magnification button to enlarge or reduce the size of the page thumbnails.

When magnification is set to the middle or highest level, some of the pages in the document may not be visible in the Document panel's pasteboard window.

6 Select a value from the Printer Resolution pop-up menu. For more information on printer resolution, see "Printing" on page 375.

7 To move pages on the pasteboard, drag a thumbnail to a new location in the Document panel preview window.

8 To scroll the pasteboard view, hold down the Spacebar while dragging the pasteboard.

To add pages to a document using the Document panel:

1 Click the Document panel Options menu control, and select Add Pages.

2 Set options in the Add Pages dialog box.

3 Click OK.

To add pages to a document from the Document window, do one of the following:

• Click the Add Page button at the bottom of the Document window.

• Select the Page tool in the Tools panel, and Alt-drag (Windows) or Option-drag (Macintosh) the page.

Selecting pages

To change a page's attributes, you must first select the page. You can do this directly in your document, or in the Document panel.

You can also set preferences that let you select a page in the Document window using a tool in the Tools panel.

To select a page, do one of the following:

• Click the Page tool in the Tools panel and click a single page on the pasteboard.

• In the Document panel, click a page thumbnail.

• Select a page number from the Go to Page pop-up menu in the Status toolbar (Windows) or at the bottom of the Document window (Macintosh), or enter a value in the text box.

- Click a page selector button in the Status toolbar (Windows) or at the bottom of the Document window (Macintosh).

- Click the page in the Document window with any tool. For this to work with all tools, the Using Tools Sets the Active Page option must be selected; see the following procedure.

To set how pages become active:

1 Display document preferences by doing one of the following:

- In Windows, press Control+U, then click the Document tab.

- On the Macintosh, press Command+U, then click the Document category.

2 Select one or both of the following options:

Changing View Sets the Active Page lets you select a page in the Document panel or in the Document window using the scroll bars. When this option is selected, you can activate a new page by scrolling through the Document window. The active page appears in the Status toolbar (Windows) or at the bottom of the Document window (Macintosh), and it is highlighted in the Document panel.

Using Tools Sets the Active Page lets you use any tool to select a page. When this option is selected, you can activate a new page by using any tool on the page in the Document window.

3 Click OK.

Duplicating, removing, and moving pages

To duplicate, remove, or move pages, you use either the Document panel or the Page tool.

To duplicate a page:

1 Select the page (see "Selecting pages" on page 45).

2 Do one of the following:

- Click the Document panel Options menu control and select Duplicate.

- Using the Page tool, Alt-drag (Windows) or Option-drag (Macintosh) the page in the workspace.

To remove a page:

1 Do one of the following:

- Select the page in the pasteboard preview of the Document panel. Then click the Document panel Options menu control and select Remove.

- Using the Page tool, select the page in the workspace, then press Delete.

2 If the selected page contains objects, click OK at the prompt.

Note: To remove a page, you must have more than one page on the pasteboard.

To move a page and its contents, do one of the following:

- Using the Page tool, select the page and drag it to the desired location on the pasteboard.

- In the Document panel, select the page and drag it to the desired location.

To move a page without moving its contents:

1 Using the Page tool, select the page.

2 Start dragging the page, then hold down Control (Windows) or Command (Macintosh) and continue dragging the page on the pasteboard.

Modifying, resizing, and rotating pages

You can modify page attributes, as well as resize and rotate pages, using the Page tool.

You cannot modify, resize, or rotate a child of a master page; these types of changes must be made to the master page.

To modify a page:

1 Using the Page tool, Alt-double-click (Windows) or Option-double-click (Macintosh) the page to open the Modify Page dialog box.

2 Do any of the following:

- Select a new page size from the Page Size pop-up menu. To create a custom size, select Custom from the pop-up menu and enter the dimensions in the text boxes.

- Select a new page orientation.

- Enter a new bleed size in the text box.

- If a master page is available, select a master page from the Make Child of Master Page pop-up menu.

3 Click OK.

To snap a page to the grid while resizing it:

1 Verify that View > Grid > Snap to Grid is selected.

   For more information, see "Using the grid" on page 54.

2 Click the Page tool in the Tools panel.

3 Click the page you want to resize to display its selection handles.

4 Drag a corner, top, or side handle. To resize the page proportionately, hold down Shift while you drag.

To rotate a page:

1 Click the Page tool in the Tools panel.

2 Click the page to display its selection handles.

3 Position the pointer outside the page and close to a selection handle. The pointer changes to the Rotate pointer.

4 Drag to change the page orientation.

   Note: Rotating a page does not rotate the objects on the page.

Defining custom page sizes

You can add custom page sizes to a document using the Edit Page Sizes dialog box. Custom page sizes are based on the document's current unit of measure. Custom pages cannot be changed; to edit a custom page definition, you must delete and re-create it.

Custom pages are retained within the FreeHand document. To make a custom page definition available to newly created FreeHand documents, you add the custom page definition to a FreeHand template. For more information, see "Using templates" on page 60.

To add a custom page size:

1 Select Window > Document to display the Document panel if it isn't already open.

2 In the Document panel, select Edit from the Page Size pop-up menu to the left of the page orientation buttons.

The Edit Page Sizes dialog box appears.

3 Click New.

4 Enter a name for the new custom page in the Page Size text box.

5 Enter the page dimensions in the X and Y text boxes. Values are in the document's current units of measure. For more information, see "Setting units of measure" on page 49.

6 Click Close.

To delete a custom page size:

1 In the Document panel, select Edit from the Page Size pop-up menu.

2 In the Edit Page Sizes dialog box, select the custom page size you want to delete.

3 Click Delete.

Deleting a custom page size in the Edit Page Sizes dialog box does not affect custom pages in your document. Their page type changes to Custom in the Document panel.

To apply a custom page size to a selected page:

Select the custom page size from the Document panel's Page Size pop-up menu.

To create a new page using a custom page size:

1 Click the Document panel Options menu control and select Add Pages.

2 In the Add Pages dialog box, enter the number of pages to be added.

3 Select the custom page from the Page Size pop-up menu.

4 Click OK.

Setting units of measure

FreeHand offers precision and flexibility for entering numeric values and displaying the rulers and grid:

- You can choose from points, picas, inches, decimal inches, millimeters, kyus, centimeters, or pixels to display in the rulers, panels, and dialog boxes.

- You can override the default unit of measure in numeric text boxes. If you override the default unit of measure, FreeHand automatically converts the value to the default unit of measure. For example, entering **125m** in a text box yields 125 millimeters instead of 125 points; the 125-millimeter value is automatically converted to 354.3307 points.

- You can enter mathematical equations and combine units of measure in numeric text boxes to have FreeHand automatically calculate values for you.

- You can define custom units of measure equivalent to other units of measure, including meters, feet, miles, ciceros, and didots. For more information, see "Using the rulers" on page 52.

To set the unit of measure for an entire document:

1 Click the Units pop-up menu in the Status toolbar (Windows) or in the bottom of the Document window (Macintosh).

2 Select a unit of measure.

   This setting affects almost all numeric text boxes except the text-related settings based on points. For example, if the Units pop-up menu is set to inches, entering **12** in a font size text box yields 12-point type regardless of the unit of measure.

To set a unit of measure other than the default in a numeric text box:

1 Enter a numeric value followed by the unit—**i** for inches, **p** for picas, **pt** for points, **m** for millimeters, **c** for centimeters, and **x** for pixels.

   For example, enter **7p** for 7 picas.

2 Press Enter (Windows) or Return (Macintosh).

To specify a value using mathematical functions:

1 Enter numeric values and create an equation using any of the following mathematical symbols:

   + (addition)

   – (subtraction)

   * (multiplication)

   / (division)

   Multiplication and division operations are evaluated before addition and subtraction if you combine these operations.

   You can combine different units in an equation. For example, if the default unit of measure in the Units menu is set to points, entering **4*50-49**, **71+80**, or **2i + p7** in a text box yields 151 points. If you enter an invalid equation or unit, FreeHand tries to resolve it or enters 0.

2 Press Enter (Windows) or Return (Macintosh).

Working with master pages

Master pages allow you to easily apply consistent page layouts in a document. You can define page attributes on a master page, as well as place text and graphics on it, and then apply these attributes to some or all of the pages in your document. You can create more than one master page in a document.

Note: You can also use templates to create documents with predefined page layouts. For more information, see "Using templates" on page 60.

You can create a new master page or convert a current document page to a master page. When you create a new master page, it takes on the page size, orientation, and bleed settings of the current page in the document; you can then change these settings if you wish. When you convert a document page to a master page, the elements on the document page are placed on the master page.

You can manage master pages in the same way you manage graphic symbols, using the Library panel. You group, duplicate, rename, and delete master pages, and you can hide or show them in the Library panel. For more information on the Library panel, see "Using the Library panel" on page 297.

You can export master pages to use them with other documents, and import master pages from other documents for use with the current document. Information about master pages is also included in a document report. For more information, see "Printing" on page 375.

When working with master pages, keep in mind the following parameters:

• When you apply a master page to a child page, the elements on the master page are placed on the bottom of each layer in the child page.

• You can bleed objects off of a master page onto the pasteboard. When master pages with bleeds are applied to child pages, the imaging on the child page is controlled by the bleed rectangle.

Master page's bleed rectangle as seen on its child page

Master page and child page

• Selecting a master page from the Master Page pop-up menu in the Document panel makes the current page (or range of pages) a child (or children) of the master page. Selecting None makes the current page (or range of pages) an ordinary page (or pages), disassociated from the master page.

To create a new master page:

1 Do one of the following:

- Select Window > Document to display the Document panel if it's not already displayed. Then click the Document panel Options menu control and select New Master Page.

- Select Window > Library to display the Library panel if it's not already displayed. Then click the Library panel Options menu control and select New Master Page.

  The new master page opens in the master page window and uses the current page's settings for size, orientation, and bleed. If the current page is a child of another master page, then the new master page uses the settings from that master page. These settings can be changed within the Document panel.

2 Place elements such as text or graphics on the master page.

3 When you have completed the master page layout, close the master page window. The attributes are saved with the master page symbol in the library.

To convert a page to a new master page:

1 Select the page (see "Selecting pages" on page 45).

2 Click the Document panel Options menu control and select Convert to Master Page.

   Note: To convert a child page to a master page, you must first release it. For more information, see the following procedures.

To apply a master page to a document page:

1 Select the page or pages with the Page tool.

2 Do one of the following:

- In the Document panel, select a master page from the Master Page pop-up menu.

  Note: In a multipage document, the selected page is the only page assigned to the master page. If multiple pages are selected with the Page tool, they all become children of the master page.

- Drag a master page icon from the Library panel and drop it onto a selected document page.

To add a child page to a document, do one of the following:

- Click the Document panel Options menu control and select Add Pages. Select the Make Child of Master Page option and select a master page from the pop-up menu, then click OK.

- Select a child page and select Duplicate from the Document panel Options menu.

- Using the Page tool, Alt-drag (Windows) or Option-drag (Macintosh) a child page to an empty location on the pasteboard.

To edit a master page:

1 Do one of the following:

- Double-click the icon of the master page in the Library panel.

- Select a child page and click Edit in the Document panel.

2 Modify the master page as needed.

3 Close the master page window to end the editing session.

To release a child page:

1 Select a page or pages using the Page tool.

> *Note:* The current page must be a child page.

2 Click the Document panel Options menu control and select Release Child Page.

The selected page or pages are no longer based on a master page. Any objects from the master page are pasted onto the selected page or pages. One group of objects is created for each layer that contained objects.

To show or hide master pages in the Library panel:

Click the Library panel Options menu control and select Show Master Pages.

This command toggles between showing and hiding master pages. A check mark before the menu item indicates that master pages are visible (the default).

To import a master page:

1 Click the Library panel Options menu control and select Import.

2 In the dialog box that appears, navigate to locate the folder from which to import the master page.

3 Click the filename, and click Open.

> *Note:* In Mac OS X, click Choose.

4 Select the master page from the Import Symbols dialog box (Shift-click to select multiple pages), and click Import.

The lower pane of the Library panel displays the imported master page.

To export a master page:

1 Click the Library panel Options menu control and select Export.

2 Select the master pages you want to export, and click Export.

3 In the dialog box that appears, navigate to locate the folder to which to export the symbol.

4 Enter a filename for the master page, and click Save.

Using the rulers

Rulers help you accurately place and measure objects in your document. They appear at the left and top of the Document window.

The rulers adjust as you scroll and zoom in the file. The large tick marks indicate the units of measure (such as points), and the small tick marks indicate the increment (such as 16 points).

Page rulers use the document's current units of measure, set in the Units pop-up menu in the Status bar (Windows) or at the bottom of the Document window (Macintosh). You can define custom units of measure equivalent to meters, feet, yards, miles, nautical miles, kilometers, ciceros, and didots. You define custom units on a per-document basis.

> *Note:* To make custom units available to newly created FreeHand documents, you can add the custom units to a FreeHand template. For more information, see "Creating a new default template" on page 61.

To show or hide page rulers:

Select View > Page Rulers > Show.

This command toggles between showing and hiding the rulers. A check mark indicates that the rulers are visible.

To change the page ruler's zero point:

Drag the zero-point marker from the upper left corner of the Document window to a new location on the pasteboard.

Zero-point marker

Note: Zero points can be defined for each individual page in a document.

To reset the page rulers:

Double-click the zero-point marker.

To define custom units of measure:

1 Select View > Page Rulers > Edit.

2 In the Edit Units dialog box, create new custom units by typing a new name or accepting the default name.

3 Enter numeric values in the text boxes and use the pop-up menus to select the units upon which to base the custom units of measure.

4 Click Accept.

5 To add more custom units, click the Plus (+) button and perform steps 2-4 for each unit.

6 Click Close when you are finished adding or removing custom units of measure.

To delete custom units of measure:

1 Select View > Page Rulers > Edit to open the Edit Units dialog box.

2 Select the units of measure you want to delete from the Units pop-up menu.

3 Click the Minus (–) button.

4 In the alert dialog box, click OK. Then click Close.

Using the grid and guides

For alignment aids, you can display nonprinting lines as guides or a grid. You can change the color of these lines.

To change the color of the grid or guides:

1 Display colors preferences by doing one of the following:

- In Windows, press Control+U, then click the Colors tab.

- On the Macintosh, press Command+U, then click the Colors category.

2 To change the color of the guides or grid, click the respective Guide Color or Grid Color box and select a new color.

3 Click OK.

Using the grid

The grid is a nonprinting background of horizontal and vertical dotted lines. You can use the grid to align objects precisely, and you can force objects to snap to grid intersections or positions relative to their original position within a grid cell.

**To show or hide the grid:**

Select View > Grid > Show.

This command toggles between showing and hiding the grid. A check mark indicates that the grid is visible.

To turn snapping to the grid on or off:

Select View > Grid > Snap to Grid.

This command toggles between turning snapping to the grid on and off. A check mark indicates that snapping to the grid is on.

To set grid options:

1 Select View > Grid > Edit.

2 Enter a grid size in the units of measure specified for the current document. (For more information on setting units of measure, see "Defining custom page sizes" on page 48.)

3 Choose the snapping behavior:

- To force objects to snap to the same relative position within the destination grid cell, select Relative Grid.

- To force objects to snap to precise grid intersections, deselect Relative Grid.

4 Click OK.

Using guides

Guides are nonprinting lines that help you align and position objects. Guides are blue by default, but you can change their color if desired (see "Using the grid and guides" on page 54). You can set guides where you want them using the page rulers or the Edit Guides command. You can add, modify, and delete guides as needed. You can also lock guides in place. Guides can only exist on pages; you cannot drag them to the pasteboard.

By default, the Document window does not scroll when you drag a guide. However, you can set preferences to make this happen. (For more information on setting preferences, see "Using preferences" on page 25.) You can also change how close objects can be to a guide before snapping to it, using the Snap Distance preference. For more information, see "Selecting objects" on page 109.

You can convert paths to guide objects and lock guides using the Layers panel; for more information, see "Using layers" on page 289.

Note: Guides that reside on a master page can be modified or deleted only from the master page and not from associated child pages.

To show or hide guides, do one of the following:

* Select View > Guides > Show.

   This command toggles between showing and hiding the guides. A check mark indicates that the guides are visible.

* Click the check mark column beside the Guides layer in the Layers panel.

To add a guide by dragging:

1 If the page rulers aren't visible, select View > Page Rulers > Show to display them.

2 Drag from the top ruler onto the page to set horizontal guides; drag from the left ruler onto the page to set vertical guides.

   Note: When dragging a guide from a ruler, make sure to release the mouse button while the pointer is over the page. Otherwise, the guide will be deleted.

To delete a guide:

Drag the guide off the page.

To add guides precisely:

1   Do one of the following:

- Select View > Guides > Edit.

- Double-click an existing guide.

2   Click Add.

3   Select Horizontal or Vertical.

4   Choose an Add By option to add guides:

- Select Count and enter a value to add a precise number of guides.

- Select Increment and enter a value to add guides at set intervals.

5   Enter the first and last position of the guides.

6   Set the page range.

7   Click Add.

8   Repeat steps 2 through 7 to add additional horizontal or vertical guides.

9   Click OK.

To turn guide snapping on or off:

Select View > Guides > Snap to Guides.

This command toggles between snapping and not snapping. A check mark by the menu item indicates that snapping behavior is active. Snap to Guides is active by default.

The pointer displays a horizontal or vertical triangle when dragging objects near a corresponding guide, indicating that the object will snap to the guide at that location if released.

To lock or unlock guides, do one of the following:

- Select View > Guides > Lock.

  This command toggles between locking and unlocking the guides. A check mark by the menu item indicates that the guides are locked. Guides are unlocked by default.

- Click the padlock icon beside the Guides layer in the Layers panel.

To edit, release, or delete guides:

1 Do one of the following:

- Select View > Guides > Edit.

- Double-click an existing guide.

2 Select the guide you want to modify.

To modify more than one guide at a time, Control-click (Windows) or Command-click (Macintosh). Shift-click to select contiguous guides.

3 Do one of the following:

- To edit a guide's position, click Edit. In the Guide Position dialog box, enter a new location for the guide and click OK.

- To release the guide or guides, click Release. Releasing a guide converts it into an object.

- To delete the guide or guides, click Remove (Windows) or Delete (Macintosh).

4 Click OK.

To set whether the Document window scrolls when a guide is dragged:

1 Display general preferences by doing one of the following:

- In Windows, press Control+U, then click the General tab.

- On the Macintosh, press Command+U, then click the General category.

2 Do one of the following:

- To make the window scroll when a vertical or horizontal guide is dragged beyond the edges of the Document window, select Dragging a Guide Scrolls the Window.

- To keep the window from scrolling when a guide is dragged, deselect Dragging a Guide Scrolls the Window.

3 Click OK.

Creating and opening documents

When you create a new document, it is based on the default document template. To learn more about templates, see "Using templates" on page 60.

You can open a multipage document, make changes to it, and then save the document. For easy access, the four most recently saved documents appear in the File > Open Recent menu. When you quit FreeHand, you have a chance to review any unsaved documents.

You can set document preferences to determine the view and page placement that a document will have when it's opened. For more information on setting preferences, see "Using preferences" on page 25.

In addition to opening FreeHand documents, FreeHand can open files of many other types, including Adobe Illustrator files, versions 1.1 through 9.

FreeHand allows you to have as many documents open at a time as you like. The only limitation is your system's own memory capacity.

To create a new document, do one of the following:

- Select File > New.
- Click the New button in the Main toolbar.

To open an existing document:

1 Select File > Open or click the Open button in the Main toolbar.

2 Locate the file to open, and click Open.

To switch between open documents:

In the Window menu, select the name of the document to display.

To close a file and quit FreeHand:

1 Select File > Exit (Windows) or File > Quit (Macintosh).

   Note: In Mac OS X, select FreeHand › Quit FreeHand.

2 If you have not yet saved or named the file, an alert dialog box appears. To save the file, click Review, and then click Yes (Windows) or Save (Macintosh).

3 Enter a name in the Name text box (if needed), and click Save.

For more information on saving files, see "Saving files" on page 341.

To set preferences that affect how FreeHand handles documents:

1 Display document preferences by doing one of the following:

- In Windows, press Control+U, then click the Document tab.

- On the Macintosh, press Command+U, then click the Document category.

2 Do any of the following:

- To open a document at the same magnification as when it was last saved, select Restore View When Opening Document.

- To open a document in the same window size and at the same location as the last saved document, select Remember Window Size and Location.

- To base new documents on a different template, select a template from the New Document Template pop-up menu, or click the Ellipsis (…) button (Windows) or the Select button (Macintosh) and locate another template file. For more information on using templates, see "Using templates" on page 60.

- To review and save each open document when quitting the application, select Always Review Unsaved Documents upon Exit (Windows) or Always Review Unsaved Documents upon Quit (Macintosh).

- To locate broken links to graphics, select Search for Missing Links (Macintosh only).

- To restore your default preferences, Click Defaults.

3 Click OK.

Opening documents from previous versions of FreeHand

FreeHand MX can open documents created in FreeHand 8 and later versions.

Because some of the FreeHand features change between versions, some illustration attributes may change or be omitted when an illustration is converted. After converting a document from an earlier version, make sure FreeHand displays and prints it properly before you delete the original document.

To convert a file from a previous version of FreeHand:

Open the file in FreeHand MX.

The converted file's name becomes *Filename*.FH11 (Windows) or *Filename* (Converted) (Macintosh).

Using templates

To work more efficiently and avoid design inconsistencies, you can create templates for documents that share common design elements and production settings. You can then use these templates as defaults for creating new documents.

You can also use master pages to apply page layouts to individual pages. For more information, see "Working with master pages" on page 50.

A template's settings and attributes are defaults for creating other documents. To create new documents with the same objects, settings, colors, and object and paragraph styles as those of an existing document, you can save the existing document as a template.

A template file saves the following elements of a FreeHand document:

- Guides
- Layer information
- Graphic styles
- Text styles
- Symbols and master pages
- All objects
- Custom brushes
- Custom colors
- Custom page sizes
- Custom units of measure

When you open a template, an untitled copy of the template document appears. You use the untitled copy to create a new template or replace an existing template. You can also designate a template as the default for all new documents.

To save a document as a template:

1 Select File > Save As.

2 Enter a name for your template file in the Save Document dialog box (Windows) or Save dialog box (Macintosh).

3 Select FreeHand Template from the Save as Type pop-up menu (Windows) or from the Format pop-up menu (Macintosh).

4 Select a destination and click Save. In Windows, the extension .ft11 is added to the filename.

To edit a FreeHand template:

1 Open the template, make changes, and then select File > Save As.

2 Save the newly revised document as a template with the same name and location.

3 FreeHand prompts you to replace the original template file. Click Yes (Windows) or Replace (Macintosh).

The edited template replaces the old one.

To convert any FreeHand file into a template without opening it (Macintosh):

1 Select the FreeHand file in the Finder.

2 Select File > Get Info or File > Show Info and then select Stationery Pad.

   To convert a template into a regular FreeHand document, deselect Stationery Pad.

To change the default template:

1 Display document preferences by doing one of the following:

- In Windows, press Control+U, then click the Document tab.

- On the Macintosh, press Command+U, then click the Document category.

2 Do one of the following:

- Select a template from the New Document Template pop-up menu.

- Click the Ellipsis (…) button (Windows) or the Select button (Macintosh) and locate another template file.

**3** Click OK.

Creating a new default template

Using the default template, you can apply document-level defaults to control settings in documents as a whole. You can apply object-level defaults to the default template to control settings for selected objects.

To create a new default template:

1 Select File > New.

2 Modify the document.

   For example, you can change the page size, default colors in the color list, default font size, and magnification, and save these with the template.

3 Select File > Save As.

4 Select FreeHand Template from the Save as Type pop-up menu (Windows) or from the Format pop-up menu (Macintosh).

5 Name the file and save it in the Macromedia/FreeHand/11/English/Settings folder within your user-specific Application Data (Windows) or Application Support (Macintosh) folder. In Windows, the extension .ft11 is added to the filename.

The location of your user-specific Application Data or Application Support folder can vary depending upon your operating system. For information on how to locate this folder, see your operating system's documentation.

Tip: A quick way to locate your user-specific folder is to go to the Document tab or category in the Preferences dialog box, click the Ellipsis (...) button (Windows) or the Select button (Macintosh) beside New Document Template, and examine the path to the current default document template.

Linking and embedding

You can set preferences to determine whether to link or embed a bitmap, SWF, or EPS graphic when you import it into a FreeHand document. An embedded graphic is included in the document; a linked file remains independent of the file, resulting in a smaller FreeHand document.

Embedding is useful for transporting an illustration without breaking the link, but it results in a larger file and increases the memory needed to display the document.

Note: Do not embed a DCS EPS 1.0 file in a FreeHand document. A DCS 1.0 file is actually five separate files: a low-resolution, composite preview and a separate file for each process (CMYK) color. If you try to embed the file, only the low-resolution file is embedded.

When you link to a graphic, FreeHand displays a preview of the graphic in the document. When you print or export a linked graphic, FreeHand requires that the link be maintained. If you move or rename linked graphics, you may have to relink them to display or print your document. Linked graphics are easier to update after they are modified, because the graphics update automatically when the document opens. However, storing linked images on a network server can slow FreeHand performance.

To link a graphic:

1 Display import preferences by doing one of the following:

• In Windows, press Control+U, then click the Import tab.

• On the Macintosh, press Command+U, then click the Import category.

2 Deselect the Embed Images and EPS upon Import option and the Convert Editable EPS When Imported option.

3 Click OK.

4 Select File > Import.

5 Navigate to the graphic you want to import.

6 Double-click the filename.

The import pointer appears.

Import pointer

7 Position the import pointer where you want the graphic or text block's upper left corner to appear.

8 Place the graphic by doing one of the following:

• Click to place the graphic at its default size.

• To resize an image while importing, drag the import pointer to create a marquee. Release the mouse button when the marquee is the correct size.

To always embed graphics:

1 Display import preferences by doing one of the following:

• In Windows, press Control+U, then click the Import tab.

• On the Macintosh, press Command+U, then click the Import category.

2 Select the Embed Images and EPS upon Import option.

3 Deselect the Convert Editable EPS when Imported option.

4 Click OK.

Managing links

When linking or embedding a graphic, FreeHand records the graphic's filename and location. When you open, export, or print the illustration containing a link, FreeHand looks for the linked graphic by its filename. If the source graphic is not in its original folder, FreeHand looks for it in the same folder as the FreeHand document.

When moving a document to another computer or to a storage device for transport, follow these guidelines:

• Save the linked graphics in the same folder as the document or embed all the graphics in the document.

• When preparing a document to send to a service bureau, use the Collect for Output command to gather all needed components, including linked graphic files. For more information, see "Printing" on page 375.

• Use the Search for Missing Links feature (Macintosh). For more information, see "Updating and fixing broken links upon opening a document" on page 65.

To update a link to a graphic after you have opened the document:

1 Do one of the following:

- Select Edit > Links to display the Links dialog box.

- In the Object panel, click the Links button when the graphic is selected in the document.

  The Links dialog box appears, listing all imported graphic files. The file information for files with broken links appears in italics. The Kind column lists the type of image (such as TIFF, SWF, EPS, or grayscale). The Size column displays the size of the file. The Page column lists the page number of the document on which the upper left corner of the image appears.

2 Do any of the following:

- To view information on a linked graphic, such as name, location, last modified date, kind, size, and a thumbnail of the graphic, select the file in the list and click Info. Click OK when you're finished viewing the information.

- To update or reestablish a link, select the file with the broken link from the list and click Change. Then navigate to the renamed or moved file and click Open.

- To embed an image, select the file in the Links dialog box, and click Embed.

To extract an embedded graphic from a document and create a new link to an external graphic file:

1 Do one of the following:

- Select Edit > Links. Select the graphic in the list and click Extract.

- With the graphic selected in the document, click the Links button in the Object panel and then click Extract.

2 In the Extract Import dialog box, select the folder you want to extract to.

3 Accept the default name or enter a new name in the File Name text box.

4 Click Save.

5 If you're saving over an existing file, a dialog box appears asking if you want to replace the existing file. Click Yes to replace the file, or click No and navigate to a new location.

6 Click OK.

Updating and fixing broken links upon opening a document

If you try to open a document with a broken link to a graphic, you'll be prompted to locate the link.

To locate a missing link:

1 Select File > Open.

2 Navigate to locate the file to open. Click Open.

3 In the Locate File dialog box, navigate to locate the missing file, and select it.

 Note: Select Search the Current Folder for Missing Links to have FreeHand look in this folder if any other broken links are encountered while the file is being opened. Click Ignore or Ignore All to prevent a graphic (or graphics) from being relinked.

4 Click Open.

 The document is updated with the new link.

5 Save the document.

To set preferences for searching for missing links (Macintosh):

1 Press Command+U, then click the Document category.

2 Select Search for Missing Links and click the Select button to search a specified folder and its subfolder for missing links.

 FreeHand searches up to 10 subfolders deep for a missing link; if FreeHand finds the graphic, the application automatically relinks the placed graphic to the new location.

3 Click Select, then click OK.

Handling font substitution

If you open or import a file that uses fonts not installed on your system, you can choose to replace the missing fonts or substitute fonts installed on your system. You may also have to reapply or substitute fonts if you transfer a document between Windows and Macintosh platforms, if the original fonts are not available on the other platform, or if the fonts have different names. You can use Macromedia Fontographer to create compatible versions of fonts for both Windows and the Macintosh; for more information on Macromedia products, go to the Macromedia website at www.macromedia.com.

Replacing fonts strips all manual kerning applied to the fonts. Substituting fonts temporarily substitutes fonts when the illustration is opened.

Replacing missing fonts

If you open or import a file containing fonts that are not installed on your system, the Missing Fonts dialog box prompts you to replace the missing fonts. Any missing fonts not replaced will display and print in the default replacement font, Arial (Windows) or Courier (Macintosh); however, the font assignment in the document remains the same.

To replace missing fonts:

1 Do one of the following:

- Select File > New to open a new file. Then select File > Import to import a file.

- Select File > Open and open a file.

  The Missing Fonts dialog box appears.

2 Highlight a font in the list, or click Select All to select all missing fonts.

3 Click Replace to open the Replace Font dialog box. Select the font name and style with which to replace the specified font or fonts, then click Change.

4 Do one of the following:

- Click OK to open the document with the new fonts.

  If you didn't click Replace to replace missing fonts prior to clicking OK, the missing fonts are temporarily displayed and printed in system default fonts.

- Click Cancel to cancel opening the document.

Automatic font substitution

If you use the Adobe Type Manager (ATM) font substitution feature, ATM temporarily substitutes fonts when the illustration is opened, and the Missing Fonts dialog box does not appear.

ATM automatically applies each missing font's metrics and weight to a multiple master font and marks the font name with a diamond in the font menu. Line breaks and word spacing are preserved, but the subtleties of the letterforms may be lost.

If you are concerned about typography, open the ATM control panel and deselect Enable Font Substitution (Macintosh only).

Sending mail (Windows)

If your Windows system includes an MAPI32-compliant electronic mail system, you can create a new outgoing mail message with the active FreeHand document or all open documents attached.

To send an e-mail message with an attached FreeHand document:

1 Select File > Send.

2 Do one of the following:

• To attach the active document to your e-mail message, select the filename.

• To attach all currently open documents to your e-mail message, select All Open Documents.

   The first time you send mail, a window appears asking you to set up a profile. See your e-mail application's documentation for more information.

3 Add any additional message.

4 To add the e-mail addresses, type an address in the text box or click To.

5 Click Send.

   The documents are attached in their current state. If the documents are unnamed, they are attached with the default names.

Using AppleScript to automate FreeHand (Macintosh)

On the Macintosh, you can automate some FreeHand functions, including document manipulation, printing, report generation, and the Find and Replace function, using AppleScript and the AppleScript Script Editor (available from Apple).

To use AppleScript capabilities in FreeHand, you must have AppleScript and the AppleScript Script Editor installed on your computer. You write scripts using the AppleScript Script Editor and run them either from the Script Editor or by saving a script as an application and launching it from the desktop or Apple menu.

To get more information on AppleScript commands used by FreeHand:

1 Launch the AppleScript Script Editor.

2 Follow the instructions in the AppleScript Read Me file to select FreeHand MX as the dictionary. The AppleScript Read Me is located in the ReadMes folder in the FreeHand MX application folder.

For more information on the AppleScript Script Editor or other AppleScript commands, see the AppleScript Read Me or the *AppleScript Handbook* by Danny Goodman, Random House Electronic Publishing.

Working with wizards (Windows)

In Windows, you can quickly begin a project and simplify your workflow using FreeHand wizards. Wizards are interactive screens that guide you through and simplify a variety of tasks.

To use a wizard:

1   Select Help > Wizards.

2   Select a topic:

Welcome lets you create a new document, open the previous document, select and open a document from a list, open a template, or launch FreeHand Help. This screen appears when you launch FreeHand.

Setup creates a document based on an illustration style, freehand or technical. Select colors, color mode, unit of measure, page size, and page orientation.

Screen-based creates a document optimized for creating graphics, for either the Internet or multimedia/image editing. Select colors and set the size and orientation for onscreen designs.

Stationery creates common business documents: letterhead, envelopes, and business cards. Select colors and a standard paper size. You also can browse through various layout ideas.

Publication creates multipage documents. Select page size, number of pages, page orientation, colors, unit of measure, and styles.

3   Follow the onscreen instructions.

Note: Some wizard settings let you add more than one preset color palette to the swatches.

CHAPTER 3
Drawing

Macromedia FreeHand MX gives you a wide range of options for drawing. You can drag to create simple objects, such as rectangles, ellipses, and lines. You can also drag to create more complex shapes, including spirals, stars, and polygons. Most drawing tools let you set options. For example, you can change the number of sides on a polygon or the direction in which a spiral winds.

You can create paths by placing points with the Pen or Bezigon tools, or by drawing a freeform shape with the Pencil tool. You can change the type of points and edit them to adjust the shape of the path segments that join them. FreeHand also lets you edit paths by removing or adding points, combining paths, and dragging path segments into new shapes.

You can use other tools to create specialty objects. For example, the Chart tool lets you add charts to your drawings. The Connector tool lets you create connector lines that dynamically adjust as you reposition objects within your drawing. The Graphic Hose tool lets you draw using a picture as your "paintbrush."

About vector graphics

Paths connected by points are the basic elements of FreeHand objects. A path consists of at least two points, each connecting one or more line segments, either straight or curved.

FreeHand generates lines and curves, called paths, which describe graphics according to their mathematical characteristics. Graphics constructed this way are much smaller in file size than bitmap graphics. Vector graphics are also resolution-independent—they appear crisp and smooth onscreen or when printed regardless of the monitor or printer resolution.

In contrast, bitmap images consist of a matrix of pixels whose display depends on the resolution of your monitor and printer. Bitmap images appear granulated when enlarged.

Vector image (top) and bitmap image (bottom)

FreeHand is a vector drawing program, but you can work with bitmap images in several ways. You can *rasterize* FreeHand objects, which means to convert them to bitmap images within your document. For more information, see "Converting vector graphics to bitmap images" on page 326. You can also export an entire FreeHand document or selected objects to a bitmap file format. For more information, see "Exporting bitmap images" on page 352.

You can import or copy a bitmap image into a FreeHand drawing. For example, you can import a photograph of a rose, an image that would be difficult to create using vector graphics, to enhance a drawing. (For more information, see Chapter 10, "Using Imported Artwork," on page 309.) Macromedia FreeHand MX can import a wide variety of vector and bitmap graphic formats.

You can also trace a bitmap image in FreeHand. The Trace tool creates paths that follow the outlines of a bitmap image. For example, you can import a photograph of a cow, and then trace the cow's outline or just the cow's spots. For more information, see "Tracing bitmaps" on page 323.

Path and point characteristics

Paths and points have the following basic characteristics:

- A path can be *open* with unconnected end points, or *closed* with the same beginning and ending point.

Examples of open (top) and closed (bottom) paths

- Each path can have up to 32,000 points, which lets you import complex files from other sources. However, using more points increases file size and slows redrawing and printing.

- Paths can be outlined by one or more strokes of varying widths and filled with color, gradients, or patterns. Paths can also be filled with vector images, bitmap images, or tiled fills.

Fill
Stroke

By default, an open path doesn't have a fill, but you can change this behavior. For more information, see "Setting path and point display preferences" on page 73.

- Paths have either clockwise or counterclockwise direction. The Rectangle, Polygon, and Ellipse tools draw in a clockwise direction. With the Line tool, the direction in which you draw sets the path direction. With the Pen and Bezigon tools, the order in which you place points sets the path direction.

Ending point

Beginning point

Beginning and ending point

The path direction affects path operations (see "Changing a path's direction" on page 95) and blending.

- Different types of points anchor path segments and let you edit lines and curves in different ways by adjusting their handles.

Corner point   Connector point   Curve point

FreeHand places a *corner* point, which is displayed as a square, when you draw a straight path segment. A corner point's handles can be adjusted independently. When you first select a corner point, its handles are retracted.

FreeHand places a *curve* point, which is displayed as a circle, when you draw a curved path segment. A curved point's handles move in tandem. When you first select a curve point, its handles are extended. When unselected, curve points display as squares.

Connector points, which are displayed as triangles, let you make a smooth transition between a straight path segment and a curved one. The position of adjacent points limits how much you can adjust a connector point's handles and whether its handles are initially extended or retracted. When unselected, connector points display as squares.

Setting path and point display preferences

You can set your preferences to change the way FreeHand displays paths and points. This can make it easier to select and edit a path or point, particularly in a complex drawing.

You can also change the way fills are displayed for a new open path.

To set the display preferences for selected paths and points:

1 Display general preferences by doing one of the following:

- In Windows, press Control+U, then click the General tab.
- On the Macintosh, press Command+U, then click the General category.

2 Select one or more options:

Smaller Handles displays smaller points and handles.

Show Solid Points displays points as a solid shape. Deselect this option to display points as an outline.

3 Click OK.

To set the display preferences for a fill in an open path:

1 Display object preferences by doing one of the following:

- In Windows, press Control+U, then click the Object tab.

- On the Macintosh, press Command+U, then click the Object category.

2 Select Show Fill for New Open Paths if you want an open path's fill to be displayed. This option applies only to paths created after you have set this preference.

3 Click OK.

Drawing rectangles, ellipses, and lines

Rectangles, ellipses, and lines are the basic FreeHand shapes. You can draw basic shapes by dragging with one of these tools. You can also precisely adjust the size and position of rectangles, and adjust the curve of rectangle corners.

Line
Rectangle
Ellipse

Rectangles and ellipses are drawn as grouped objects. If you ungroup a rectangle or ellipse, FreeHand converts it to a path, and you can no longer edit it as a rectangle or ellipse.

To draw a rectangle, ellipse, or line:

1 In the Tools panel, select the Ellipse tool, or select the Rectangle or Line tool from its pop-up menu.

2 Drag to define the object, and then release the mouse button to end the path.

To draw a rectangle, ellipse, or line from its center:

1 In the Tools panel, select the Ellipse tool, or select the Rectangle or Line tool from its pop-up menu.

2 Hold down Alt (Windows) or Option (Macintosh) as you drag the respective tool.

Drawing rectangles with curved corners

You can precisely edit the curvature of rectangle corners by using the Object panel. The corners of a rectangle can be uniform, or you can edit corners individually by unlocking them in the Object panel. Locked corners edit uniformly, even if some of the remaining corners are unlocked.

You can also edit corners manually by using the subselect tool to drag radius handles of a rectangle.

To draw rectangles with curved corners:

1 In the Tools panel, if the Rectangle tool is not showing, select it from its pop-up menu.

2 Double-click the Rectangle tool.

3 In the Rectangle Tool dialog box, enter a value or use the slider to adjust the corner radius, from 0 for a standard 90° corner to 100 for extremely curved corners.

4 Click OK.

5 Draw the rectangle.

To adjust the corners of a selected rectangle uniformly:

1 In the Tools panel, click the Subselect tool.

2 Select the rectangle.

3 Drag a radius handle.

To adjust the corners of a selected rectangle independently:

1 In the Tools panel, click the Subselect tool.

2 Select the rectangle.

3 In the Object panel, deselect Uniform.

4 Drag a radius handle.

Constraining a basic shape as you draw

You can constrain how a tool draws a basic shape. When constrained, the Rectangle tool draws a square, the Ellipse tool draws a circle, and the Line tool draws at increments of 45°.

You can change the constrain angle. When the constrain angle is 0°, holding down the Shift key constrains objects to 0°, 45°, 90°, and so on. Changing the constrain angle shifts these angles by the specified amount. A constrain angle of 10°, for example, changes the angles to 10°, 55°, 100°, and so on. If you change the constrain angle, a rectangle, line, or ellipse that you draw will be tilted to the value you specified.

To constrain a shape as you draw, do one of the following:

• To constrain a shape, hold down Shift as you drag the pointer.

• To constrain a shape as you draw from the center, hold down Alt (Windows) or Option (Macintosh) and Shift-drag the pointer.

To set the constrain angle:

1 Select File > Document Settings > Constrain.

2 Enter a value in the Angle text box, or use the pop-up angle dial to set the angle.

3 Click OK.

Repositioning a basic shape as you draw

You can move a rectangle, line, ellipse, polygon, or star as you draw.

To reposition a basic shape while drawing, do one of the following:

- Hold down the Spacebar.

- (Windows only) Hold down the right mouse button.

Drawing polygons and stars

You can use the Polygon tool to draw polygons and stars. When you draw a polygon, you create a closed path. The Polygon tool draws from the center.

To set Polygon tool options:

1 In the Tools panel, if the Polygon tool is not showing, select it from its pop-up menu.

2 Double-click the Polygon tool.

3 In the Polygon Tool dialog box, select Polygon or Star for the shape.

4 Set the number of sides by dragging the slider or entering a value from 3 to 360. Values above 20 will create a nearly round object.

5 For a star, set the angle of the star points. Select Automatic to draw a preset star shape, or Manual to set a shape using the Acute/Obtuse slider.

The preview window displays the setting results.

6 Click OK.

Automatic (left), Acute (center), and Obtuse (right)

To draw a polygon or star:

1 In the Tools panel, select the Polygon tool from its pop-up menu.

2 Drag to draw a polygon or star.

3 To modify the polygon or star as you draw, use any of the following keys:

• Press Shift to constrain the angles of the polygon.

• Press Alt (Windows) or Option (Macintosh) to draw from the center regardless of the selected drawing option.

To edit a polygon or star:

1 In the Tools panel, click the Subselect tool.

2 Select the polygon or star.

3 Do either of the following:

• Drag a diamond-shaped handle to uniformly edit the vertices, or "peaks," of the polygon or star.

• Drag a circular handle to uniformly edit the midpoints, or "valleys," of the polygon or star.

Midpoint

Vertex

4 To constrain the vertices or midpoints to the original angle of the polygon or star, press Shift as you drag.

Drawing spirals and arcs

With the Spiral and Arc tools, you can easily draw spirals and arcs. Options let you customize the way each tool works.

To set Spiral tool options:

1 In the Tools panel, if the Spiral tool is not showing, select it from its pop-up menu.

2 Double-click the Spiral tool.

3 In the Spiral dialog box, select a Spiral Type option:

• Click the left button to create a spiral with a concentric, evenly spaced radius.

• Click the right button to create an expanding-radius spiral that opens up farther with each rotation. In the Expansion text box, enter a value or drag the slider to adjust the expansion rate.

4 Select a Draw By option:

Rotations specifies the number of rotations in the spiral, regardless of its size. Set the number by entering a value in the Number of Rotations text box or by adjusting the slider.

Increments adds more rotations as the spiral grows bigger. Set the spacing between each rotation by entering a value in the Increment Width text box or by adjusting the slider. For expanding spirals, enter a value in the Starting Radius text box.

5 Select a Draw From option:

Center lets you click to set the center point of the spiral and drag to place the end point.

Edge lets you click to place the end point of a spiral and drag to place the center point.

Corner lets you click to place one end point of a spiral and drag to place the other end point.

6 Click a Direction button to specify whether a spiral turns clockwise or counterclockwise. This does not change the *path* direction of a spiral.

7 Click OK.

To draw a spiral:

1 In the Tools panel, select the Spiral tool from its pop-up menu.

2 Drag to draw a spiral.

3 To modify the spiral as you draw, use any of the following keys:

• Press Shift to constrain the placement of the final point.

• Press Alt (Windows) or Option (Macintosh) to draw from the center regardless of the selected drawing option.

To set Arc tool options:

1 In the Tools panel, if the Arc tool is not showing, select it from its pop-up menu.

2 Double-click the Arc tool.

3 In the Arc dialog box, select from the following options:

Create Open Arc lets you draw only the arc curve. Deselect this option to draw the arc as a quarter pie shape.

Create Flipped Arc lets you flip the orientation of the arc.

Create Concave Arc lets you draw the arc with an outer corner.

Concave (left), Open (center), and Flipped (right)

4 Click OK.

To draw an arc:

1 In the Tools panel, select the Arc tool from its pop-up menu.

2 Drag to draw an arc.

3 To modify the arc as you draw, press any of the following keys, alone or in combination, after you begin drawing the arc:

• Press Shift to constrain the arc.

• Press Alt (Windows) or Option (Macintosh) to draw a flipped arc.

• Press Control (Windows) or Command (Macintosh) to draw a closed arc.

• (Windows only) Press Control and hold down the right mouse button as you draw to create a concave arc.

• (Macintosh only) Press Control to draw a concave arc.

Drawing freeform paths

With the Pencil, Variable Stroke Pen, and Calligraphic Pen tools, you can draw freeform paths that follow the direction of your hand movements.

Drawing with the Pencil tool

The Pencil tool draws a simple line as you drag.

To set Pencil tool options:

1   In the Tools panel, if the Pencil tool is not showing, select it from its pop-up menu.

2   Double-click the Pencil tool.

3   In the Pencil Tool dialog box, select tool options:

- Enter a value from 1 to 10 in the Precision text box, or adjust the slider. Choose a high value to follow minor variations as you draw. Choose a low value to smooth minor variations as you draw.

- Select Draw Dotted Line to draw paths faster by displaying a dotted line as you draw. The final path is still solid.

4   Click OK.

5   Use the stroke and fill color selectors in the Tools panel to set color attributes for the path.

To draw a path with the Pencil tool:

1   In the Tools panel, select the Pencil tool from its pop-up menu.

2   Drag to draw a path. To draw a straight line, hold down Alt (Windows) or Option (Macintosh) as you drag.

To continue a selected path with the Pencil tool:

Position the Pencil tool over a path's end point; a solid plus (+) sign indicates that drawing will continue the path.

Drawing with the Variable Stroke Pen tool

The Variable Stroke Pen tool draws a path that resembles a brush stroke. You can use keyboard commands or a pressure-sensitive tablet to vary the width of the path as you draw.

To set Variable Stroke Pen tool options:

1   In the Tools panel, if the Variable Stroke Pen tool is not showing, select it from its pop-up menu.

2   Double-click the Variable Stroke Pen tool.

3   In the Variable Stroke Pen dialog box, select tool options:

- Enter a value from 1 to 10 in the Precision text box, or adjust the slider. Choose a high value to follow minor variations as you draw. Choose a low value to smooth minor variations as you draw.

- Select Draw Dotted Line to draw paths faster by displaying a dotted line as you draw. The final path is still solid.

- Select Auto Remove Overlap to remove unnecessary path segments and create a composite path.

Original (left) and Auto Remove Overlap applied (right)

Note: Using the Auto Remove Overlap option may slow the redrawing of an image. You can also remove any overlap by selecting the path and choosing Modify › Alter Path › Remove Overlap or clicking the Remove Overlap button on the Xtra Operations toolbar.

- For Width, set the minimum and maximum possible stroke widths, measured from the centerline, between 1 and 72 points.

4 Click OK.

5 Use the stroke and fill color selectors in the Tools panel to set color attributes for the path.

To draw a path with the Variable Stroke Pen tool:

1 In the Tools panel, select the Variable Stroke Pen tool from its pop-up menu.

2 Drag to draw a path.

3 To draw a straight line, hold down Alt (Windows) or Option (Macintosh).

Drawing with the Calligraphic Pen tool

The Calligraphic Pen tool draws a path that resembles a calligraphy stroke. You can use keyboard commands or a pressure-sensitive tablet to vary the width of the path as you draw.

To set Calligraphic Pen tool options:

1 In the Tools panel, if the Calligraphic Pen tool is not showing, select it from its pop-up menu.

2 Double-click the Calligraphic Pen tool.

3 In the Calligraphic Pen dialog box, select tool options:

- Enter a value from 1 to 10 in the Precision text box, or adjust the slider. Choose a high value to follow minor variations as you draw. Choose a low value to smooth minor variations as you draw.

- Select Draw Dotted Line to draw paths faster by displaying a dotted line as you draw. The final path is still solid.

- Select Auto Remove Overlap to remove unnecessary path segments and create a composite path.

Original (left) and Auto Remove Overlap applied (right)

Note: Using the Auto Remove Overlap option may slow the redrawing of an image. You can also remove any overlap by selecting the path and choosing Modify › Alter Path › Remove Overlap or clicking the Remove Overlap button on the Xtra Operations toolbar.

- Select Fixed to set calligraphic paths to a constant width, or click Variable to specify a path width between 1 and 72 points.

- Set the angle of the Calligraphic Pen by entering a value or dragging the Angle dial from 0° to 359°. The actual width of a stroke at a given location on the path depends on the direction in which you drag.

4 Click OK.

5 Use the stroke and fill color selectors in the Tools panel to set color attributes for the path. Select no stroke and a basic fill to most closely resemble a real calligraphy pen.

To draw a path with the Calligraphic Pen tool:

1 In the Tools panel, select the Calligraphic Pen tool from its pop-up menu.

2 Drag to draw a path.

3 To alter the path as you draw, do any of the following:

- Hold down Alt (Windows) or Option (Macintosh) to draw a straight line.

- To decrease the path width, press the Left Arrow key (Windows) or Left Bracket key (Macintosh).

- To increase path width, press the Right Arrow key (Windows) or the Right Bracket key (Macintosh).

- If you're using a pressure-sensitive tablet, the width of the path segments increase or decrease according to the amount of pressure applied.

To continue a selected path with the Calligraphic Pen tool:

Position the Pencil tool over a path's end point; a solid plus (+) sign indicates that drawing will continue the path.

Drawing with the Pen tool and Bezigon tool

You can use the Pen tool and Bezigon tool to draw by placing points to define a path. These tools differ in the way they place points. As you move the Pen or Bezigon pointer (cursor), it changes to show what action will result if you click at the current location.

- The Pen tool lets you adjust a point's handles, and therefore the curvature of a path, as you draw. Click to place a point, then drag to adjust the handles. Use the Pen tool to create a path with curved segments. After you place the first point, the Pen tool shows a "rubberband" preview of what the path will look like when you click to place the next point.

- The Bezigon tool sets point locations. Click to place a point, then continue dragging to move that point. Use the Bezigon tool to create a path with straight segments.

Drawing with the Pen tool

Drawing with the Bezigon tool

To draw with the Pen tool:

1 In the Tools panel, select the Pen tool from its pop-up menu.

2 Do any of the following:

- Click to place a corner point.

- Drag to place a curve point and extend its handles. Press Control (Windows) or Command (Macintosh) as you drag to move the curve point to a new location.

- Hold down Alt and right-click (Windows) or Control-click (Macintosh) to place a connector point.

    Dragging as you place a connector point extends the point's handle. This handle affects the curve of the next path segment.

3 To finish the path, do one of the following:

- Double-click the last point or press Tab to create an open path.

- Click the first point to create a closed path.

To draw with the Bezigon tool:

1 In the Tools panel, select the Bezigon tool from its pop-up menu.

2 Do one of the following:

- Click to place a corner point.

- To place a curve point, hold down Alt (Windows) or Option (Macintosh) as you click.

- To reposition a point and the point handles simultaneously, hold down Control (Windows) or Command (Macintosh) and drag the point to its new location.

- To place a connector point that connects a straight segment to a curved path: In Windows, hold down Alt and use the right mouse button to drag; on the Macintosh, Control-drag.

3 To finish the path, do one of the following:

- Double-click the last point or press Tab to create an open path.

- Click the first point to create a closed path.

To constrain path segments:

Hold down Shift as you place a point.

To continue a selected path:

1 In the Tools panel, click the Subselect tool.

2 Select an end point on the path you want to continue.

3 In the Tools panel, select the Pen tool or Bezigon tool from their pop-up menu. You can continue a Pen path with the Bezigon tool and vice versa.

4 Click or drag to draw additional segments.

To continue an unselected path:

1 In the Tools panel, select the Pen tool or Bezigon tool from their pop-up menu. You can continue a Pen path with the Bezigon tool and vice versa.

2 Move the pointer over an end point of the path you want to continue.

3 Alt-drag (Windows) or Option-drag (Macintosh) to extend the path.

4 Click or drag to draw additional segments.

To close a selected open path, do one of the following:

• Use the Pointer or Subselect tool to drag one end point over the other end point.

• Select Window > Object. In the Object panel, select Closed to automatically connect the end points of the path with a new path segment.

• (Windows only) Right-click the path and select Path > Closed from the context menu.

To open a selected closed path, do one of the following:

• Select Window > Object. In the Object panel, deselect Closed to remove the last path segment from the path.

• (Windows only) Right-click the path and select Path > Open from the context menu.

Editing paths

You can easily edit paths using various tools and techniques. Once you've drawn a path, you can add or delete points, reposition points, or redirect the path.

You can edit paths using the Pen, Bezigon, Pointer, and Subselect tools. You can reshape paths using the Freeform tool, split paths with the Knife tool, or erase parts of paths with the Eraser tool. You can also apply Xtras to simplify paths by reducing the number of points.

You can also control path display and behavior using the Object panel.

Adding and deleting path segments and points

Deleting one or more segments from a path leaves one or more open paths.

To delete a path segment or point:

1 In the Tools panel, click the Subselect tool.

2 Click the path to select it.

3 Click a point or path segment to select it. Shift-click to select additional segments or points.

4 Press Delete.

To manually add points to a selected path:

1 In the Tools panel, select the Pen tool from its pop-up menu.

2 Click the path to place a new corner point.

To automatically add points to a selected path:

Select Window > Toolbars > Xtra Operations. Click the Add Points button on the Xtra Operations toolbar, or select Xtras > Distort > Add Points.

A point is added halfway between every pair of points on a path.

Reshaping a path

Using the Pointer and Subselect tools, you can reshape a path by moving points and path segments. You can also adjust the points on a path by dragging with the Pointer tool or by using the Object panel.

You can also modify a path by using the Freeform tool; see "Editing a path with the Freeform tool" on page 90.

To move points on a selected path:

1 Do one of the following:

- If you are selecting points on an ungrouped path, click the Pointer tool in the Tools panel.

- If you are selecting points on a path that is part of a group, click the Subselect tool in the Tools panel.

2 Click a point to select it.

3 Shift-click to select additional points.

4 Drag any of the selected points to move all of the selected points to the new location.

To adjust a point's handles:

1 Do one of the following:

- If you are selecting points on an ungrouped path, click the Pointer tool in the Tools panel.

- If you are selecting points on a path that is part of a group, click the Subselect tool in the Tools panel.

2 Select the path.

3 Click a point to display its handles. The adjacent handles of the points on either side of the selected point are also displayed.

4 Drag a handle to adjust the curve.

Moving a handle closer to its point decreases the amount of curvature. Moving it away from the point increases the curve.

Dragging a corner point's handle to curve a straight path segment

Dragging a curve point's handle to reverse a path segment's curve

Dragging a connector point's handle to increase a path segment's curvature

The farther you drag a handle from a corner, curve, or connector point, the more pronounced the curve becomes.

To adjust points using the Object panel:

1 Select Window > Object to display the Object panel.

Path information in the Object panel

2 Select the path and then the points you want to adjust. The Object panel displays several options for the selected points.

If you select more than one point, the Point location text boxes are hidden.

Point information in Object panel

3 Do one of the following:

- Click a Point Type button to change the type of the selected point.

- Click a Handles button to retract the selected point's handles.

- Select Automatic to extend the point handles and adjacent path segments to best conform to the existing path. This option may move curve point handles from their original position, but does not add handles to corner or connector points.

- Change a point's location by editing the values in the Point Location X and Y text boxes. Values are in the default unit of measure, as measured from the page's zero point.

Editing a path with the Freeform tool

The Freeform tool lets you modify a path by pushing, pulling, or reshaping. The Freeform tool automatically adds points, deletes points, or changes point types as you modify the paths.

The Freeform tool has two modes of operation:

- **Push/Pull** mode lets you adjust a selected path by *pushing* the pointer across a path segment or by *pulling* the segment directly. Pulling is similar to dragging a segment using the Subselect tool. Pushing reshapes only that part of the path that the pointer touches.

- **Reshape** mode is similar to pushing, except that the effect weakens as you drag the pointer. Reshaping is a powerful tool for creating naturalistic shapes, such as tentacles or tree branches.

Push (left) and Reshape (right)

To set Freeform tool Push/Pull options:

1 In the Tools panel, if the Freeform tool is not showing, select it from its pop-up menu.

2 Double-click the Freeform tool.

3 In the Freeform Tool dialog box, select Push/Pull.

4 Select the Push Settings options:

- Set the pointer size in pixels by entering a value from 1 to 1000 in the Size box or by adjusting the slider.

- Set the tool precision by entering a value from 1 to 10 in the Precision box or by adjusting the slider. Lower numbers mean lower precision and fewer points added to the path.

5 Select the Pull Settings options.

6 Select a Bend option from the pop-up menu:

By Length specifies the length of the segment that will be affected, from 1 to 1000 pixels.

Between Points affects all of a path segment between its end points. A small *s* beside the pull pointer shows when this option is active.

7 If you are using a pressure-sensitive drawing tablet, set the Pressure options:

Size activates the tablet's pressure-sensitive size adjustment capability.

Length activates the tablet's pressure-sensitive length adjustment capability.

8 Click OK.

To push or pull a selected path:

1 In the Tools panel, if the Freeform tool is not showing, select it from its pop-up menu.

2 You can adjust the path two ways:

• Click on the path and drag to pull the path. A small *s* beside the pointer indicates that you are in Pull mode.

Pulling a path segment between points (top) and pulling a path of a specified length (bottom)

• Click beside the path and drag to push the path. A circular pointer indicates that you are in Push mode. The pointer's size depends on the Freeform tool size setting.

Push set at 50 (left) and curve after being pushed (right)

3 While dragging with the Freeform tool in Push/Pull mode, you can use the following keys to modify the operation:

• Hold down Shift to constrain the pointer movement.

• To switch temporarily between the By Length and Between Points options, hold down Alt (Windows) or Option (Macintosh), and then drag with the pull pointer. Holding down these modifier keys after you start dragging clones the path.

• To increase the width of the push pointer, press the Right Arrow or Right Bracket (]) key. To decrease the width, press the Left Arrow or Left Bracket ([) key.

To set Freeform tool Reshape options:

1 In the Tools panel, if the Freeform tool is not showing, select it from its pop-up menu.

2 Double-click the Freeform tool.

3 In the Freeform Tool dialog box, select Reshape.

4 Select the Settings options:

• Set the pointer size in pixels by entering a value from 1 to 1000 in the Size box or by adjusting the slider.

• Set the strength of the pointer, or how strongly it will distort a path, by entering a value from 1 to 100 percent in the Strength box or by adjusting the slider.

• Set the tool precision by entering a value from 1 to 10 in the Precision box or by adjusting the slider. Lower numbers mean lower precision and fewer points added to the path.

5 If you are using a pressure-sensitive drawing tablet, set the Pressure options:

• Select Size to activate the tablet's pressure-sensitive size adjustment capability.

• Select Length to activate the tablet's pressure-sensitive length adjustment capability.

6 Click OK.

To reshape a selected path:

1 In the Tools panel, if the Freeform tool is not showing, select it from its pop-up menu.

2 Double-click the Freeform tool.

3 In the Freeform Tool dialog box, select Reshape Area.

4 Click OK.

5 Position the pointer near the path and press the mouse button.

The pointer changes to the reshaping pointer.

Note: The inner circle of the reshaping pointer represents the strength setting.

6 Drag the pointer across the path to reshape the path.

7 While dragging with the Freeform tool in Reshape mode, you can use the following keys to modify the operation:

• Hold down Shift to constrain the pointer movement.

• To increase the width of the reshaping pointer, press the Right Arrow or Right Bracket (]) key. To decrease the width, press the Left Arrow or Left Bracket ([) key.

• To increase the strength of the reshaping pointer, press the Up Arrow key. To decrease the strength, press the Down Arrow key.

Splitting paths

You can manually split paths and create open or closed paths by using the Knife tool or the Split command.

To set the Knife tool options:

1 In the Tools panel, double-click the Knife tool.

2 Select options in the Knife Tool dialog box:

- Select Freehand to make a freehand cut or Straight to make a straight cut. If you are using the Freehand operation, you can hold down Alt (Windows) or Option (Macintosh) as you drag to cut a straight line. Hold down Shift to constrain it.

- Enter a value from 0 to 72 points in the Width text box, or set the width with the slider. A width of 0 gives a single, thin cut. Higher values make two cuts spaced according to the Width value.

- Select Close Cut Paths to close the resulting paths and to display the stroke and fill of the original path. Deselect the option to keep the resulting paths open and to display only the stroke.

  Note: If you have selected the Show Fill for New Open Paths preference, the resulting paths still display the original path's fill, regardless of the Knife tool settings.

- Select Tight Fit to make a cut that closely follows the path of your hand movements.

  If the Smoother Editing general preference is deselected, new points resulting from a cut path may not be visible.

To split a selected path with the Knife tool:

Drag the Knife tool across the path.

To split paths using the Split command:

1 Select one or more paths.

2 Select one or more points on each path. The path will be split at each point you select.

3 Select Modify > Split.

Erasing paths

You can erase parts of selected paths by using the Eraser tool.

To set the Eraser tool options:

1   In the Tools panel, double-click the Eraser tool.

2   Enter a value from 0 to 72 points in the Min text box, or set the minimum width with the slider.

3   Enter a value from 0 to 72 points in the Max text box, or set the maximum width with the slider.

To erase a selected path with the Eraser tool:

1   In the Tools panel, click the Eraser tool.

2   Drag the Eraser tool across the path.

• To decrease the eraser width, press the Left Arrow key.

• To increase the eraser width, use the Right Arrow key.

• If you're using a pressure-sensitive tablet, the width of the path segments increase or decrease according to the amount of pressure applied.

Simplifying paths

Using many points on a path increases the file size and can slow the process of redrawing the screen and printing. Simplifying a path generally makes editing, displaying, and printing easier, and is useful for objects created with the Trace tool or the Pencil tool.

To selectively simplify paths in an entire document, you can use the Edit > Find and Replace > Graphics command to select paths containing more than a specified number of points. For more information on this command, see "Making global changes" on page 124.

You can also change the flatness setting to improve printing speed on printers with little memory. For more information, see "Printing" on page 375.

To simplify a selected path:

1   Select Modify > Alter Path > Simplify.

2   Enter a value in the Amount text box or adjust the slider. The higher the value, the more points FreeHand removes from the path.

3   Click Apply to preview the result. You can change the result and preview it as many times as you want.

4   Click Cancel to cancel the operation or click OK to accept the results.

Changing a path's direction

The path direction affects which handle adjusts a given path segment, which path end an arrowhead is attached to, and how text is attached to a path. Direction also affects blending paths, composite paths, and brush strokes.

To reverse the direction of a selected path:

Select Modify > Alter Path > Reverse Direction.

Overlapping fills

Closed paths have one of two directions: clockwise or counterclockwise. When a clockwise path meets a counterclockwise path, these paths yield a transparent, overlapping section in a composite path. When two closed paths of the same direction overlap, these paths yield a filled, overlapping section. If your composite path's overlapping fill does not behave as expected, try correcting its direction, or subselect one path and reverse its direction.

To apply Correct Direction to a selected composite path, do one of the following:

- Select Modify > Alter Path > Correct Direction.

- Select Xtras > Cleanup > Correct Direction.

- Click the Correct Direction button on the Xtra Operations toolbar.

Creating charts and pictographs

Using the Chart tool, you can create charts to visually display numeric data. You create a chart by entering data and choosing display options. You can later edit the data and change the display options to update the chart.

A FreeHand chart is a grouped series of objects that acts much like any other group—you can enlarge, scale, rotate, and move it, and you can also edit individual chart elements. Once you ungroup a chart, however, it becomes a graphic and you can no longer edit the data, even if you regroup the chart.

Pictographs are graphics that replace the standard chart bars or lines with an image. For example, you can represent a monetary value with a stack of coins or a library value with stack of books.

Charts are created in grayscale. You can color them using various techniques.

To create a chart:

1 In the Tools panel, select the Chart tool from its pop-up menu.

2 Drag the pointer to set the initial size of the chart.

   The Chart dialog box appears with the insertion point in the data entry text box. The active cell is outlined in black.

   To change the active cell, click a different cell or use the arrow keys.

3 Do one of the following to add data to the selected cell:

- Type in the text box above the chart cells. To undo the last change, click the Undo button.

- Click Import to import tab-delimited text from another application, such as Microsoft Excel.

4 To create labels and legends, leave the top left cell empty. Enter data across the first row for the chart legend and in the left column for the labels.

   Labels appear across the bottom of the graph and the legend appears at its right side. Type quotation marks around number labels to have them read as numbers instead of data.

5 To transpose the rows and columns and their data, click the Transpose button.

6 To adjust column width, drag the triangle above the line separating two columns.

7 To set the data precision, enter a Decimal Precision value for the number of decimal places to which the data will be rounded. Select Thousands Separator to punctuate values of one thousand or greater.

8 Continue entering data as needed, repeating steps 3 through 7.

Note: The Chart tool plots empty cells as values of 0.

9 When you have finished entering data, click Apply to create the chart, or click OK to create the chart and close the dialog box.

10 Click the style button at the top of the dialog box to specify the chart type. For more information, see "Setting the chart type and options" on page 98.

To edit data in a chart:

1 Select the chart in your document.

2 In the Tools panel, if the Chart tool is not showing, select it from its pop-up menu.

3 Double-click the Chart tool.

4 In the Chart dialog box, select a cell or drag to select multiple cells.

5 To edit data in the worksheet, select any of the following options:

Cut removes data from highlighted cells.

Copy copies data from highlighted cells.

Paste pastes copied or cut data into cells starting with the cell currently highlighted.

6 To switch the data categories and groupings:

• Click Transpose to change the columns to rows and the rows to columns.

• If you're creating a scatter chart, click Switch XY to reverse the x axis and y axis.

7 When you have finished editing data, click Apply to preview your changes without closing the Chart dialog box, or click OK to apply the changes and close the dialog box.

To edit the appearance of chart elements:

1 In the Tools panel, click the Subselect tool.

2 Click a chart element to select it.

3 Select Edit > Select > Superselect or press the Tilde (~) key to select all of the elements in that series.

4 Edit the selection as desired. You can apply most of the same changes and transformations to the selected elements as you can to any other FreeHand object, such as coloring, scaling, or rotating.

You can add perspective to the entire chart, but not to individual elements. For more information, see "Creating perspective" on page 227.

To color selected chart elements:

Select a stroke or fill color from the pop-up color boxes in the Tools panel. You can also use Find and Replace Graphics feature to change colors in a chart; for more information, see "Making global changes" on page 124.

Setting the chart type and options

You can select different chart types and options, and preview how the data will be presented, either as you create the chart or afterwards. Options vary according to the chart type.

To choose a chart type for a selected chart:

1 In the Tools panel, if the Chart tool is not showing, select it from its pop-up menu.

2 Double-click the Chart tool.

3 In the Chart dialog box, click the Chart Type button to display the chart type options.

4 Select a chart type:

   Grouped Column compares data using bars. Each bar represents one cell of data.

   Stacked Column compares the progress of data. Each bar represents a row of data.

   Line shows the trend of data over a period of time. Each line represents a column of data.

   Pie displays data in a circular graph with wedges. Each cell of data represents a single wedge. Each row of data produces a Pie chart.

   Area displays filled areas representing the progress of data over time. Each area represents a column of data in the worksheet. Each column's value is added to the previous column's total.

   Scatter plots data as paired sets of coordinates to identify trends in data. Each coordinate represents a row of data containing two cells.

5 To preview your chart using the selected chart type, click Apply.

To specify chart options:

1 In the Chart dialog box, click the Chart Type button to display the chart type options.

2 Select a chart type using the buttons and then select options for that type:

- For Grouped Column and Stacked Column graphs, specify a column width to adjust the space of each column. Values greater than 100 overlap columns.

- For a Grouped Column graph, specify a cluster width to adjust the space for each group of columns. Values greater than 100 overlap columns.

- For a Pie chart, specify the separation between pie pieces, from none (0) to 50.

- For Line and Scatter graphs, select the type of data markers: None, Square, Diamond, Triangle, or Circle.

3 Select Data Numbers in Chart to display the data values next to the graph or chart points.

This option is not available for Area graphs.

4 Select Drop Shadow to add a drop shadow behind and to the right of the chart.

This option is not available for Line and Scatter charts.

5 Select Legends Across Top to display legends across the top of the chart, instead of along its side.

6 Click Apply to preview your changes without closing the Chart dialog box, or click OK to apply the changes and close the dialog box.

Adding gridlines to charts

All of the graphs except the Pie chart let you display gridlines along the x axis or y axis.

To add gridlines:

1 Select the chart.

2 In the Tools panel, if the Chart tool is not showing, select it from its pop-up menu.

3 Double-click the Chart tool.

4 In the Chart dialog box, click the Chart Type button.

5 Select an Axis Display option to set where the vertical axis of the chart appears—to the right, to the left, or on both sides of the chart.

6 For Gridlines, select X Axis to extend gridlines from left to right along the x axis, Y Axis to extend gridlines from top to bottom along the y axis, or select both options to create a grid behind the chart.

7 Click Apply to preview your changes without closing the Chart dialog box, or click OK to apply the changes and close the dialog box.

Displaying axis values

You can display values along the axes of a chart to control how the numerical data is presented. If an axis has no numerical values, the options in the Chart Type dialog box are dimmed. The axis value options are not available for a Pie chart.

To display axis values:

1   Select the chart.

2   In the Tools panel, if the Chart tool is not showing, select it from its pop-up menu.

3   Double-click the Chart tool.

4   In the Chart Type dialog box, click the X Axis or Y Axis button to display the Axis Options dialog box.

5   Select an Axis Values option:

Calculate from Data lets you calculate axis values from the data entered in the worksheet.

Manual lets you enter your own Minimum, Maximum, and Between values. The Between value determines how many steps will be displayed between each whole number. For example, if the axis values range from 1 to 10, a Between value of 1 will display 1, 2, 3, and so on. A Between value of 2 will display 2, 4, 6, and so on.

To have the axis start with a high number and end with a lower number, enter a negative number in the Between box.

6   Select Tick Marks options.

Major tick marks correspond to numbers or category labels on the axis. They can be displayed across, inside, or outside the axis. Minor tick marks are evenly spaced between major marks. The value in the Count text box determines how many minor tick marks appear between each major mark. They can also be displayed across, inside, or outside the axis.

7   For Axis Value Labels, enter a prefix to add a label before a value (such as $ for $125), and enter a suffix to add a label after a value (such as % for 5%).

8   Click OK.

9   Repeat steps 4 through 8 to set options for the other axis.

10 Click Apply to preview your changes without closing the Chart dialog box, or click OK to apply the changes and close the dialog box.

Adding pictographs to charts

Pictographs represent data visually, according to the type of data shown. For example, instead of a simple bar to represent a dollar amount, you can add a pictograph of a dollar sign or a stack of coins.

To create a pictograph:

1 Select and copy the FreeHand graphic you'd like to use.

2 Use the Subselect tool to select a column in the series to which you'll apply the pictograph.

3 Select Xtras > Chart > Pictograph.

4 In the Pictograph dialog box, click Paste In to display the copied object in the preview window.

5 To copy the selection in the preview window to the Clipboard, click Copy Out.

6 Choose how to fill the columns:

• Select Repeating to fill the columns with repeating copies of the object. Partial objects are used to represent incremental values.

• Deselect Repeating to fill the column with one scaled object.

7 Click OK.

To remove a pictograph from your chart:

Select the column from which you want to remove the pictograph, and select
Xtras > Chart > Remove Pictograph.

Dynamically linking objects

You can use the Connector tool to draw connector lines that dynamically link objects together. Connector lines automatically adjust when you move connected objects in the document window. Use connector lines for tasks such as drawing call-out lines for labels, building organizational charts, or creating basic flowcharts. You can use the Object panel to edit the start symbol, end symbol, and other stroke attributes of connector lines. For more information, see "Applying attributes to strokes" on page 166.

To draw a connector line between two objects:

1 In the Tools panel, click the Connector tool.

2 Move the Connector tool over the start object. The mouse pointer changes to indicate that there is an object from which a connector line can start.

3 Move the pointer near the top, bottom, left, or right of an object to start the connector line from that side of the object.

4 Drag to the top, bottom, left, or right of the target object to end the connector line on that side of the object.

To move the end point of a connector line using the Connector tool:

Drag the end point to an object or to an empty space in the Document window.

To reverse the direction of a connector line:

1 Select the connector line.

2 Select Modify > Alter Path > Reverse Direction.

To manually reshape a connector line:

1 In the Tools panel, click the Connector tool.

2 Select the connector line to display its handles.

3 Drag a handle to reshape the connector line.

Drawing with the Graphic Hose tool

For quick illustration, you can use the Graphic Hose tool to "spray" frequently used objects on your document page.

Objects in hose (left) and spraying result

The Graphic Hose dialog box lets you store up to 10 images (including bitmaps, groups, blends, text, envelopes, and symbols) in each hose. When you paint with the hose, the images are applied in an order based on the options you choose.

FreeHand comes with a collection of predefined hoses. You can edit these hoses or create your own.

To select a graphic hose:

1 In the Tools panel, if the Graphic Hose tool is not showing, select it from its pop-up menu.

2 Double-click the Graphic Hose tool.

3 Select Hose to display the hose sets.

4 Select a hose from the pop-up menu to activate it and display a preview of the first object in the set. You can use the Contents pop-up menu to preview the other objects in the set.

5 To preview individual objects contained in the hose, select an option from the Contents pop-up menu.

To draw with the Graphic Hose tool:

1 In the Tools panel, select the Graphic Hose tool from its pop-up menu.

2 Drag the tool, controlling the spray as follows:

• Increase or decrease the speed and direction of dragging to control how objects are placed. Dragging faster spaces the objects farther apart.

• Use the Left and Right Arrow keys to increase or decrease the spacing between objects as you spray them.

• Use the Up and Down Arrow keys to increase or decrease the scale factor as you spray objects.

• Click to place individual objects with the hose.

Importing a graphic hose

Additional graphic hoses are located on the FreeHand MX installation CD in the Graphic Hoses folder in the Assets folder. Other hoses might be available from other artists or third-party developers.

Note: Import hoses only from a trusted source.

To import a graphic hose:

1 Navigate to the location of the graphic hose file you want to import.

2 Copy the hose files to the Macromedia/FreeHand/11/English/Xtras folder within your user-specific Application Data (Windows) or Application Support (Macintosh) folder.

Note: The location of your user-specific Application Data or Application Support folder can vary depending upon your operating system. For information on how to locate this folder, see your operating system's documentation.

Creating a graphic hose

In a graphic hose, you can include up to 10 objects. These objects can be from your current FreeHand document or from other documents. You can also use symbols as elements in a hose. By using symbols, you can modify the symbol element to update all objects created by the graphic hose automatically.

For more information, see "Using the Library panel" on page 297.

To create a graphic hose:

1 In the Tools panel, if the Graphic Hose tool is not showing, select it from its pop-up menu.

2 Double-click the Graphic Hose tool.

3 Choose a method to create a new set:

• Select New from the Sets pop-up menu to add a new set.

• Select Rename or Duplicate from the pop-up menu to base the new set on an existing one.

4 In the dialog box that appears, name the new set and click Save to add it to the list.

Note: Hoses are stored in the Macromedia/FreeHand/11/English/Graphic Hose folder within your user-specific Application Data (Windows) or Application Support (Macintosh) folder. The location of your user-specific Application Data or Application Support folder can vary depending upon your operating system. For information on how to locate this folder, see your operating system's documentation.

5 In your document, select artwork to include in the hose.

6 Select Edit > Copy.

7 In the Graphic Hose dialog box, click Paste In. The artwork appears in the preview window as an object in the Contents pop-up menu.

Each new object you add to a hose is assigned the name Object-1, Object-2, and so on. You can select an object name from the Contents pop-up menu to preview it.

Note: Avoid placing too many memory-intensive objects such as lenses, EPS images, and TIFF images in a hose. In general, spraying a great number of these objects increases file size.

8 Repeat steps 5 through 7 as needed to complete the hose.

To delete a hose:

Locate and delete the FreeHand file for the hose in the Macromedia/FreeHand/11/English/ Graphic Hose folder within your user-specific Application Data (Windows) or Application Support (Macintosh) folder.

Note: The location of your user-specific Application Data or Application Support folder can vary depending upon your operating system. For information on how to locate this folder, see your operating system's documentation.

To restore the default hoses:

1 Navigate to the Graphic Hoses folder in the Installer/Support folder on the FreeHand MX installation CD.

2 Copy any or all of the default hose files to the Graphic Hoses folder in the Macromedia/ FreeHand/11/English/Graphic Hose folder within your user-specific Application Data (Windows) or Application Support (Macintosh) folder.

Note: The location of your user-specific Application Data or Application Support folder can vary depending upon your operating system. For information on how to locate this folder, see your operating system's documentation.

Setting graphic hose options

You can set options for painting with the graphic hose, including the order of objects, spacing, scale, and rotation of objects.

To set graphic hose options:

1 In the Tools panel, if the Graphic Hose tool is not showing, select it from its pop-up menu.

2 Double-click the Graphic Hose tool.

3 In the Graphic Hose dialog box, click Options.

4 Select an order in which objects in the set are applied:

Loop applies objects in numeric order.

Back and Forth first applies objects in forward order, then applies them in reverse order, and continues alternating as you paint.

Random applies objects in random order.

5 Select a spacing between objects:

Grid spaces objects in rows and columns with the size you set in the Grid text box.

Variable spaces objects from Tight (0) to Loose (200).

Random spaces objects in no set order from 0 to 200. Use the slider or enter a value to set the deviation.

6 Select how to scale objects:

Uniform scales objects progressively from 1% to 200%.

Random scales objects randomly from 1% to 200% (greatest deviation).

7 Select how to rotate the sprayed objects:

• Select Uniform to set a specific angle for all objects.

• Select Incremental to apply rotations that change in specific increments from one object to the next.

• Select Random to rotate the objects randomly.

• Specify the angle or drag the angle dial to control the rotation.

8 Drag the Graphic Hose tool on the page to apply the hose artwork.

CHAPTER 4
Working with Objects

Macromedia FreeHand MX lets you manipulate objects in a number of ways. You can group objects to treat them as a single unit and nest groups within a group. You can move objects using the mouse or keyboard or by specifying a precise location. You can align objects to each other or align them to the page. You can also transform objects by rotating, scaling, skewing, and reflecting. In addition, you can alter, combine, inset, and expand paths, as well as create a clipping path, or mask, that exposes only part of an object behind it.

FreeHand provides enhanced cut-and-paste functions that let you control how objects are copied to and from your drawings. You can also clone or duplicate objects.

You can make global selections or replacements within a drawing by searching for graphics with particular attributes, such as stroke width or shape.

Using the Object panel

The Object panel is a context-sensitive panel that lets you view and change properties for selected objects and text. Each kind of object has different properties.

The Object panel is part of the Properties panel group, which is open in FreeHand by default. To show or hide the Object panel, select Window > Object.

The top portion of the Object panel displays the Properties list, a hierarchical list that contains the properties applied to a selected object. The attributes of a selected property appear on the bottom half of the Object panel. The contents of the attributes section change depending on the property selected in the Properties list.

Above the Properties list are buttons that allow you to add and delete properties such as fills, strokes, and effects. You can add more than one fill, stroke, and effect to an object. By dragging properties in the list, you can rearrange the order in which properties are applied to a selected object.

Properties for an object with multiple strokes and fills

Most changes you make to an object's attributes are immediately applied in the Document window. For some attributes, however, changes are not applied until you click outside the attribute-editing boxes, or press Enter (Windows) or Return (Macintosh).

When no items are selected in the Document window, the Object panel displays the default attributes for new objects that you create.

Object panel displaying default attributes

The Object panel is used in almost all drawing tasks in FreeHand. For more information about this panel, see the following documentation:

- "Applying attributes to strokes" on page 166
- "Applying attributes to fills" on page 177
- "Displaying type attributes in the Object panel" on page 248
- Chapter 7, "Special Effects," on page 193

Selecting objects

You can select objects with the Pointer, Subselect, and Lasso tools, or by using keyboard shortcuts or menu commands.

The Pointer, Subselect, and Lasso tools let you select objects or points by clicking. The Pointer and Subselect tools also let you select objects or points by dragging a rectangular selection marquee. The Lasso tool lets you select objects and points by dragging a free-form selection marquee.

By default, the selection marquee must completely enclose an object or point to select it. You can change this behavior so that dragging the selection marquee over any part of an object's edge selects the object.

You can also change the distance at which the Pointer tool selects an object.

To prevent an object from being selected or changed, you can hide it. You can also lock an object, which prevents it from being changed but allows it to be selected.

To set Pointer, Subselect, and Lasso tool options:

1 Double-click the tool in the Tools panel.

2 In the tool's dialog box, do one of the following:

• Deselect Contact Sensitive if you want to select only objects and points that are completely enclosed by the selection marquee. Points that lie within the selection area will still be selected.

• Select Contact Sensitive if you want to select objects or groups that are only partially enclosed by the selection marquee.

Note: The Pointer and Subselect tools use the same Contact Sensitive setting.

To specify how closely you must click to an object to select it:

1 Display general preferences by doing one of the following:

• In Windows, press Control+U, then click the General tab.

• On the Macintosh, press Command+U, then click the General category.

2 Enter a value from 1 to 5 pixels in the Pick Distance text box and click OK.

To select an object using the Pointer tool, do one of the following:

• Using the Pointer tool, click the object. If the object has no fill, click its path to select it.

• If you are using a tool other than the Pointer tool, hold down Control (Windows) or Command (Macintosh) to temporarily use the Pointer, and then click the object.

To select an object or point using the Subselect tool, do one of the following:

• Using the Subselect tool, click the object, path, or point. This selects only the object, path, or point you click, even if it is contained in a group.

• If you are using the Pointer tool, hold down Alt (Windows) or Option (Macintosh) to temporarily use the Subselect tool, and then click the object, path, or point.

• If you are using a tool other than the Pointer tool, hold down Control+Alt (Windows) or Command+Option (Macintosh) to temporarily use the Subselect tool, and then click the object, path, or point.

To select an object using the Lasso tool:

Drag the Lasso tool to define a selection marquee around the object or points you want to select.

To add an object to a selection:

Hold down Shift as you select an object or point.

To select all objects on the active page, do one of the following:

- Select Edit > Select > All.
- Press Control+A (Windows) or Command+A (Macintosh).

To select all objects in a document, do one of the following:

- Select Edit > Select > All in Document.
- Press Control+Shift+A (Windows) or Command+Shift+A (Macintosh).

To deselect all objects in a document:

Select Edit > Select > None or press Tab.

To select all objects except the current selection:

Select Edit > Select > Invert Selection.

To delete a selection without storing it on the Clipboard:

Select Edit > Clear or press Delete.

Selecting complex objects

Objects within a composite path, group, blend, extrusion, or clipping path act as a group. You can select individual objects, path segments, or points within that group so that you can edit them individually.

Note: You can select only the points and path of the original object on which an extrusion is based; you can't select individual paths or points in the extrusion itself. However, you can release an extrusion and then select these items. For more information, see "Extruding objects" on page 205.

To select an object within a composite path, group, blend, extrusion, or clipping path:

1 Click the Subselect tool.

2 Click the object.

3 To select a path segment or point on a selected object, click the segment or point. To select additional path segments or points, hold down Shift as you click with the Subselect tool.

To select an object underneath another object within a composite path, group, blend, or paste inside:

1 Click the Subselect tool.

2 Hold down Control and Alt-right-click (Windows), or hold down Control and Option-click (Macintosh) the object. This selects the top object in the stack. Continue clicking to cycle through the objects beneath the first one.

Note: This procedure is used when a filled object covers the objects beneath it. To select from a group of unfilled objects, click the object's stroke using the Subselect tool.

Hiding objects

You can hide objects to prevent them from being modified. You can select View > Show All to redisplay hidden objects. Hidden objects will automatically redisplay when you close and re-open a file.

Hidden objects appear in printed documents unless they reside on a nonprinting layer or a background layer. For more information about nonprinting and background layers, see "Using layers" on page 289.

To hide selected objects:

1 Select the objects you want to hide.

2 Select View > Hide Selection.

To show all hidden objects:

Select View > Show All.

Note: Show All does not show hidden layers.

Locking objects

Locked objects cannot be edited. However, you can set preferences to allow fill attributes and text in locked objects to be edited.

To lock a selected object:

Select Modify > Lock to lock the object, or click the Lock button in the Main toolbar.

The Lock button is dimmed, and the Unlock button is now available.

To unlock a selected object, do one of the following:

• Select Modify > Unlock. The command is dimmed if the selection is not locked.

• Click the Unlock button in the Main toolbar.

 The Unlock button is dimmed, and the Lock button is now available.

To allow changing of fill and stroke attributes of locked objects:

1 Display object preferences by doing one of the following:

• In Windows, press Control+U, then click the Object tab.

• On the Macintosh, press Command+U, then click the Object category.

2 Select Edit Locked Objects to allow the stroke and fill attributes of locked objects, including text within a locked text block, to be modified.

3 Click OK.

Note: Deselecting Edit Locked Objects prevents any changes.

Moving objects

You can move selected objects directly by dragging them in the Document window or by using the arrow keys. When moving an object with the arrow keys, you can specify the distance it moves each time you press an arrow key.

You can also move selected objects numerically by entering values in the Object panel or the Transform panel. When you move an object numerically using the Object panel, the values you enter define the coordinates of the object relative to the page's zero-point marker. For information about resetting or moving the zero-point marker, see "Using the rulers" on page 52. When you move an object numerically using the Transform panel, the values you enter define the distance to move the object relative to its current position.

For information about moving objects while drawing them, see "Repositioning a basic shape as you draw" on page 77.

To move a selected object directly in the workspace, do one of the following:

• Drag the selection to a new location. Press Control (Windows) or Command (Macintosh) to switch to the Pointer tool if another tool is selected.

• Move the selection by pressing the corresponding arrow key or by pressing Shift and an arrow key.

To specify the distance an object moves when you press an arrow key:

1 Select File > Document Settings > Cursor Distance.

2 Enter a value in the Arrow Key Distance text box. Values are in the document's current units of measure. In points, the value can range from 1 to 864. For more information about units of measure, see "Setting units of measure" on page 49.

3 To specify the distance a selected object moves when you press Shift and an arrow key, enter a value in the Shift+Arrow Key Distance text box. This value can also range from 1 to 864 points.

To move selected objects using the Transform panel:

1 Do one of the following to display the Transform panel if it's not already displayed:

• Select Modify > Transform > Move.

• Select Window > Transform, and click the Move button.

2 Enter a positive value in the X text box to move the object to the right or a negative value to move it to the left.

3 Enter a positive value in the Y text box to move the selection up or a negative value to move it down.

For more information on using this panel, see "Using the Transform panel" on page 137.

To move selected objects using the Object panel:

1 Select Window > Object to display the Object panel if it's not already displayed.

2 Select the object name in the Properties list of the Object panel if it's not already selected.

3 In the bottom half of the panel, enter a positive value in the X text box to move the object to the right or a negative value to move it to the left.

4 Enter a positive value in the Y text box to move the selection up or a negative value to move it down.

For more information on using this panel, see "Using the Object panel" on page 107.

Snapping to points and other objects

When you move objects and points, you can "snap" them to the points or paths of other objects, provided this feature is turned on. How close an object or point must be to another object before it snaps is determined by the Snap Distance setting in FreeHand preferences.

To snap a selected object or point to a point:

1 Do one of the following:

- Click the Snap to Point button in the Tools panel if it's not already selected.

- Select View > Snap to Point if it's not already enabled. (A check mark beside this command means it's enabled.)

    Note: Snap to Point is a toggle; selecting it when it's already enabled turns it off.

2 Using the Pointer tool, drag the selected object near or onto the target point. When the tool is within the snap distance, the pointer changes.

3 Release the mouse button to drop the object in the desired location.

To snap a selected object or point to a path:

1 Do one of the following:

• Click the Snap to Object button in the Tools panel, if it's not already selected.

• Select View > Snap to Object, if it's not already enabled. (A check mark beside it means it's enabled.)

   Note: Snap to Object is a toggle; choosing it when it's already enabled turns it off.

2 Using the Pointer tool, drag the selected object near or onto the target path. When you get within the snap distance, the pointer changes.

3 Release the mouse button to drop the object in the desired location.

To change the snap distance:

1 Display general preferences by doing one of the following:

• In Windows, press Control+U, then click the General tab.

• On the Macintosh, press Command+U, then click the General category.

2 Enter a setting in the Snap Distance box. This setting determines the distance at which one object will snap to another object.

3 Click OK.

Aligning and distributing objects

You can align or distribute objects or points relative to other objects, other points, or the current page. Aligning moves objects so that they lie on a straight line along one edge or their centers. Distributing spaces objects evenly by one edge or their centers, or by evenly spacing the distance between them. Points are aligned or distributed by their position, since they don't have an edge.

You can lock an object so that it does not move during alignment. Other objects will align relative to the locked one.

You can also use blends or power duplicating to evenly space identical objects across a page. For more information, see "Blending composite paths and groups" on page 216 and "Power-duplicating" on page 145.

To align or distribute selected objects or points:

1 Select Window > Align to display the Align panel.

Click edge to align objects to top, bottom, left, or right.

Horizontal options

Vertical options

Click in a square to align vertically and horizontally.

The three rectangles in the preview illustrate the current alignment settings; when you select a distribution option, a fourth rectangle appears.

2 Do one of the following:

- In the preview window, click to set alignment options. For example, click the left edge to align objects by their left edges.

- Select alignment or distribution options using the pop-up menus.

- Select Align to Page to align or distribute objects relative to the current page dimensions.

3 Click Apply.

Copying objects

You can copy objects between FreeHand documents or between FreeHand and other applications—such as Adobe Illustrator, Photoshop, and Microsoft Word—by copying and pasting with the Clipboard or by dragging.

Pasted graphics appear in the center of the screen in the FreeHand document.

Setting copy and paste preferences

FreeHand can copy objects to or paste objects from the Clipboard in a number of formats. When copying to the Clipboard, FreeHand copies the selection using all the formats specified in export preferences. When pasting from the Clipboard, FreeHand uses the format that retains the most information about the object.

You can override the default format by using the Copy Special or Paste Special commands.

You can change the list of copy formats available to FreeHand by changing the export preferences. In Windows only, you can change the list of paste formats available by changing the import preferences.

You can choose from the following formats for FreeHand copy operations:

- FreeHand
- RTF
- AI/EPS (Windows)
- EMF (Windows)
- Metafile (Windows)
- Bitmap (Windows)
- Device independent bitmap (Windows)
- Adobe Illustrator (Macintosh)
- ASCII (Macintosh)
- PICT (Macintosh)

You can also choose the color space you want for the copied selection. In Windows, this choice is only available if you have selected AI/EPS. You can select one of the following color conversion options:

- CMYK
- RGB
- CMYK and RGB
- Photoshop 4/5 pixels (Windows)
- Photoshop 4/5 paths (Windows)
- Photoshop 4/5 (Macintosh)

In Windows only, you can choose from the following formats for FreeHand paste operations:

- FreeHand
- LRG
- PNG
- AI/EPS
- RTF
- EMF
- Metafile
- Bitmap
- Device independent bitmap

To set copy format preferences:

1 Display export preferences by doing one of the following:

• In Windows, press Control+U, then click the Export tab.

• On the Macintosh, press Command+U, then click the Export category.

2 In the Clipboard Copy Formats list (Windows) or Clipboard Output Formats (Macintosh), select the formats you want FreeHand to use when copying to the Clipboard. Deselected formats are not available for copying.

3 In the Convert Colors To list, select the color space you want for the copied selection.

4 Click OK.

To set paste format preferences (Windows only):

1 Press Control+U, then click the Import tab.

2 In the Clipboard Paste Formats list, select the formats you want FreeHand to choose from when pasting from the Clipboard. Deselected formats are not available for pasting.

3 Click OK.

Copying objects within a FreeHand document

You can create copies of an object within a FreeHand document by copying and pasting with the Clipboard, dragging, cloning, or duplicating.

Copying by dragging can be disabled in FreeHand preferences.

Cloning places a copy of the object on top of the original. Duplicating places a copy of the object at a specified place near the original. You can also use *power-duplicating* to repeat an object transformation as you make copies; see "Power-duplicating" on page 145.

To copy a selected object within a FreeHand document:

1 Do one of the following to copy the object:

• Select Edit > Copy.

• Select Edit > Special > Copy Special and select a format in the Copy Special dialog box.

2 Do one of the following to paste the object:

• Select Edit > Paste.

• Select Edit > Special > Paste Special and select a format in the Paste Special dialog box.

To copy an object by dragging within a FreeHand document:

1 Using the Pointer tool, select the object and continue holding down the mouse button until the cross-hair pointer appears.

2 Hold down Alt (Windows) or Option (Macintosh) as you drag the object.

To disable copying when Alt-dragging (Windows) or Option-dragging (Macintosh):

1 Display object preferences by doing one of the following:

- In Windows, press Control+U, then click the Object tab.

- On the Macintosh, press Command+U, then click the Object category.

2 Deselect Alt-Drag Copies Paths (Windows) or Option-Drag Copies Paths (Macintosh), and click OK.

To clone or duplicate a selected object, do one of the following:

- To duplicate the object, select Edit > Duplicate. A copy of the object appears offset from the original.

- To clone an object, select Edit > Clone. A copy of the object appears on top of the original.

Copying objects between FreeHand documents

You can copy objects between FreeHand documents by copying and pasting using the Clipboard or by dragging.

When you copy objects between FreeHand documents, your preferences determine which layer the copy will appear on. If the Remember Layer Info option is off, the object will be copied to the active drawing layer. If Remember Layer Info is on, the object will be placed on a layer with the same name as the source layer. If no layer with that name exists in the document, FreeHand will create one. For more information about layers, see "Using layers" on page 289.

Note: If the document to which you are copying objects has the same layer names but uses a different stacking order than the source document, copied objects might be stacked differently than they were in the original document.

To copy a selected object to another FreeHand document:

1 Do one of the following to copy the object:

- Select Edit > Copy.

- Select Edit > Special > Copy Special and select a format in the Copy Special dialog box.

2 Open the document to which you want to paste the object.

3 Do one of the following to paste the object:

- Select Edit > Paste.

- Select Edit > Special > Paste Special and select a format in the Paste Special dialog box.

To copy an object by dragging between FreeHand documents:

1 Open both the source and destination documents.

2 Do one of the following:

- On Windows, select Window > Tile Vertically or Window > Tile Horizontally to show both documents.

- On the Macintosh, resize and reposition each document's window so that you can see both at the same time.

3 Drag the object from the source document to the location you want in the destination document. A copy of the object remains in the source document.

Copying objects between applications

You can copy objects between a FreeHand document and a document in another application by copying and pasting with the Clipboard or, in some cases, by dragging.

When you copy to or paste from the Clipboard, FreeHand normally chooses the best format from the available ones you set in preferences. Using the Copy Special command, you can force FreeHand to convert the selection on the Clipboard to a specific file format.

You can copy objects by dragging them between FreeHand and other applications that support the Apple Drag Manager (Macintosh) or OLE Drag and Drop (Windows). Some of these applications include Netscape Navigator (Macintosh), Macromedia Fireworks, Photoshop, and Illustrator. See your operating system instructions for the correct dragging procedure.

To copy from FreeHand and paste into another application:

1 In FreeHand, select the object.

2 Do one of the following:

- Select Edit > Copy to copy the selection according to the Clipboard Copy Formats preferences.

- Select Edit > Special > Copy Special and select a format in the Copy Special dialog box.

3 Make active the application into which you'll paste the selection. Select Edit > Paste or the equivalent command for that application.

To copy from another application and paste into FreeHand:

1 In the application you want to copy from, select an object and then select Edit > Copy or the equivalent command for that application.

2 Make the FreeHand document active.

3 Do one of the following:

- Select Edit > Paste to paste the selection according to the Clipboard Paste Formats preferences.

- Select Edit > Special > Paste Special and select a format in the Paste Special dialog box.

Grouping objects

Grouping two or more objects constrains their positions and stacking order relative to one another, so you can manipulate them as a single object. Grouping objects on different layers moves these objects to the current drawing layer but retains their relative stacking order.

You can ungroup objects to edit them individually. When ungrouping objects, you can return them to their original layers.

Objects within a group retain their original stroke and fill attributes. You can modify these attributes by subselecting objects within the group and making changes in the Object panel. You can also modify the attributes of the group as a single object, which applies the attributes to the group as a whole; this approach does not alter the original attributes of the individual objects.

Ungrouped, selected (left) and Grouped, selected (right)

Note: Attributes applied to a group as a whole are lost when you ungroup the objects.

To group selected objects:

Select Modify > Group.

To ungroup a selected group:

Select Modify > Ungroup.

To automatically return objects to their original layers when ungrouping:

1   Display general preferences by doing one of the following:

• In Windows, press Control+U, then click the General tab.

• On the Macintosh, press Command+U, then click the General category.

2   Select Remember Layer Info and click OK.

Selecting grouped objects

You can work with individual objects within a group by subselecting only the objects you want to modify. You can also remove one or more objects from a group. You cannot move individual objects within a group to other layers or group them with other groups.

Group (left); selecting object within group (right)

To select an object within a group:

1 Do one of the following:

- Click the Subselect tool and click the object to select it.

- Using the Pointer tool, hold down Alt (Windows) or Option (Macintosh) and click the object to select it.

2 To add objects to the subselection, press Shift as you subselect.

To select an object behind another object in a group:

1 Click the Pointer tool.

2 Do one of the following:

- In Windows, hold down Control+Alt and right-click to cycle through selected objects.

- On the Macintosh, hold down Control+Option and click to cycle through selected objects.

To deselect a subselected object:

Press Tab or click outside the group.

To select the group containing a subselected object:

Select Edit > Select > Superselect.

To subselect all objects within a group:

With the group selected in the Document window, double-click the Contents property in the Properties list of the Object panel.

Working with nested objects

Nested objects are objects in groups within larger groups. You can manipulate them just as you would any other group.

To nest an object or group within an existing group:

1 Select an object or group that you want to nest.

2 Hold down Shift as you select the group into which you want to nest the selection.

3 Select Modify > Group.

You can apply the Group command up to 20 times in succession to nest objects within a group, or to combine groups within a larger group. Multiple nested groups can significantly increase printing time and complexity.

Note: The actual nesting limit is 28, but certain objects such as inline graphics (see Chapter 8, "Using Type," on page 233) and paste insides might contain nested objects and therefore may account for more than one nest level.

To subselect an object within a nested group:

1 Do one of the following:

- With the Pointer tool selected, hold down Alt (Windows) or Option (Macintosh) and click an object within the nested group.

- Click the Subselect tool and click an object.

2 To add objects to the subselection, press Shift as you subselect.

Arranging objects

You can change the stacking order of objects by using the Arrange commands or by cutting and pasting. (The stacking order may not be obvious if the objects do not overlap.) You can integrate an object into a group or clipping path by pasting the object behind or in front of another object within a group or a clipping path. For more information on clipping paths, see "Working with clipping paths" on page 132.

Using the Paste Behind and Paste In Front commands, you can quickly move an object to a specific place in the stacking order.

The Arrange and Paste in Front/Behind commands apply only to selections on the same layer. For more information on rearranging objects by changing their layering, see "Using layers" on page 289.

To change the stacking order of objects:

1 Using the Pointer tool, select the object to rearrange.

2 Select Modify > Arrange and select from the following commands:

   Move Forward moves an object forward in a stack.

   Bring to Front moves an object to the top of a stack.

   Move Backward moves an object backward in a stack.

   Send to Back moves an object to the bottom of a stack.

To paste an object in front of or behind another object:

1 Using the Pointer tool, select the object that you want to paste.

2 Select Edit > Cut or Edit > Copy.

3 Select the object in front of or behind which you'll paste the selection.

4 Do one of the following:

- Select Edit > Special > Paste in Front to paste the cut/copied object in front of the selected object.

- Select Edit > Special > Paste Behind to paste the cut/copied object behind the selected object.

Adding names and notes to objects

You can name an object or add a note to it by using the Navigation panel. You can also use the Navigation panel to check object names and notes. Names and notes can be exported as annotations when you export a FreeHand drawing to PDF format. For more information, see "Exporting PDF files" on page 358.

You can also add URL links to objects and text. For information, see "Attaching URLs to objects and text" on page 327.

To add a name or note to a selected object:

1   Select Window > Navigation.

2   In the Navigation panel, type a name for the object in the Name text box. Names can be up to 26 characters long.

3   Type a note in the Note text box. Notes can be up to 254 characters long.

Names and notes are applied when you type them. You don't need to press Enter or close the Navigation panel to apply your changes.

To review a selected object's name or note:

Select Window > Navigation.

The object's name and note are displayed in the Navigation panel.

Making global changes

You can quickly make global changes to your artwork—including rotating and scaling multiple objects—using the Find & Replace and Select panel group. You can search for and replace objects by name or by characteristics. The Find & Replace and Select panel group contains two panels: Find & Replace, and Select.

The Find & Replace panel lets you rotate and scale objects relative to each object's center. These operations aren't available when you use the transformation tools alone.

To make changes to layers using the Find & Replace and Select panel group, make sure the layers are not locked or hidden. For more information, see "Using layers" on page 289.

You can find and replace type attributes too; for more information, see "Adding, duplicating, and removing styles" on page 303. To find and replace text, you use the Find Text dialog box; for more information, see "Finding and replacing text" on page 247.

Selecting objects globally

To quickly change objects, you can select objects based on certain attributes. The attributes are color, style, same as selection, size, fill type, stroke type, stroke width, font, text effect, object name, object type, path shape, halftone, and overprint.

For information on selecting type attributes (paragraph styles, text effects, and fonts), see "Adding, duplicating, and removing styles" on page 303.

For information on printing attributes, see Chapter 14, "Printing," on page 375.

To select objects by attributes:

1 Select Edit > Find and Replace > Graphics, or click the Graphics button in the Main toolbar.

2 Click the Select tab.

3 Use the Attribute pop-up menu to choose what to select:

Color selects objects with the specified color.

Style selects objects with a specified style name.

Same as Selection selects objects with matching strokes or fills.

Fill Type selects objects with a designated fill type.

Stroke Type selects objects with a designated stroke type.

Stroke Width selects objects with a specified range of stroke width values.

Font selects a font and its style. (If the size is required, set the minimum and maximum. Leave blank to search for all.)

Text effect selects all text blocks that have any effect or a specific effect.

Object Name selects objects with a specified name assigned to them in the Navigation panel.

Object Type selects objects of a specific type. Object types include paths, polygons, composite paths, clipping paths, groups, blends, ovals, rectangles, text blocks, bitmaps, EPS files, envelopes, extrusions, connector lines, and instances.

Path Shape selects all paths of a designated shape after a path has been copied and Paste In has been clicked. It also searches for the fill and stroke specific to that shape.

Halftone selects objects with custom halftones.

Overprint selects all objects that have overprint turned on.

4 Select Document, Page, or Selection from the Search In pop-up menu to specify what to search.

Finding and replacing graphics

The Find & Replace panel lets you search for and automatically change attributes including color, stroke width, transformations, path shapes, and blend steps. The feature lets you modify every occurrence of a specific attribute, including all occurrences of the attribute in hidden objects.

You can replace a selection or object in a page or document. The stroke width, simplify, rotate, scale, and blend steps attributes can be calculated mathematically.

For more information on searching for printing attributes (halftones and overprinting), see Chapter 14, "Printing," on page 375. For more information on replacing colors, see "Making global color changes" on page 163.

To find and replace graphics:

1. Select Edit > Find and Replace > Graphics or click the Graphics button in the Main toolbar.

2. Under Change In, select Page, Document, or Selection to specify the search.

3. Select a category from the Attribute pop-up menu:

   Color lets you select a color to change. Specify the colors using the From and To pop-up menus, or drag a color from the Color Mixer or Swatches panels onto the color boxes beside the pop-up menus. Select Include Tints to search for tints of the From color. For more information on color, see "Using Strokes and Fills" on page 165.

   Stroke Width lets you find strokes within the width range you specify using the Min and Max pop-up menus. For example, to search for widths from 2 to 8 points, you would enter **2 points** in the Min text box and **8 points** in the Max text box. To search for a specific width, enter the width in the Min text box and leave the Max text box empty.

   Font lets you search for a specific font and size.

   Remove lets you search for and remove invisible objects, overprinting, custom halftones, or contents.

   Path Shape lets you search for all paths of a designated shape, fill, and stroke. To specify the path to search for, copy the path and click Paste In to the right of the From box. Do the same in the To box for the path you want to replace the original path.

   If you select Path Shape, you can select Transform to Fit Original to keep the original object's dimensions for the new object.

   Simplify lets you specify the number of points a path must contain; for Allowable Change, enter a value or drag the slider to set the replacement number of points.

   Rotate lets you set the rotation angle to rotate objects around their individual center points.

   Scale lets you enter a scale factor to scale objects. To scale objects proportionally, enter the same percentage in both the X and Y text boxes.

   Blend Steps lets you enter the number of steps to search for. In the pop-up menu, select Resample At to resample at the current printer output resolution.

4. Click Change.

Combining paths

You can create new paths by joining or combining paths. Some of these operations produce *composite paths*, which consist of individual paths joined together that act as one path.

When you combine paths using the Join command, the selected paths are simply joined as a single composite path. When you combine paths using the Union, Divide, Intersect, Punch, or Crop command, the result might be a composite path or a single path depending on the position of the originals and the path operation you use.

You can specify whether path operations other than Join consume the original paths by setting object preferences. Hold down Shift as you select a path operation to retain the original paths, without resetting the defaults.

To set retention options for original paths:

1 Display object preferences by doing one of the following:

• In Windows, press Control+U, then click the Object tab.

• On the Macintosh, press Command+U, then click the Object category.

2 Do one of the following:

• Select Path Operations Consume Original Paths to delete the original paths when a path operation is applied.

• Deselect this option to keep the original paths.

Creating composite paths by joining

Joining two or more closed paths creates a composite path, which acts as a single path. A composite path assumes the stroke and fill attributes of the backmost path. Path direction also affects the appearance of composite paths.

You can specify whether open paths must be touching to be joined.

For information on blending composite paths, see "Blending composite paths and groups" on page 216.

To control whether nontouching open paths are joined:

1 Display object preferences by doing one of the following:

• In Windows, press Control+U, then click the Object tab.

• On the Macintosh, press Command+U, then click the Object category.

2 Do one of the following:

• Select Join Non-Touching Paths to connect the paths if the end points are within the snap distance set on the General tab or category of the Preferences dialog box.

• Deselect Join Non-Touching Paths to join the paths only if they touch.

3 Click OK.

To create a composite path by joining:

1 Select two or more paths.

If the two paths are open, their distance and preferences control whether they are joined.

2 Select Modify > Join.

To adjust the transparent sections of a composite path:

1 Select a composite path.

2 Select Window > Object to display the Object panel if it's not already displayed.

3 Do one of the following:

• Select Even/Odd Fill to make overlapping subpaths of a composite path alternate between filled and transparent.

• Deselect Even/Odd Fill to make overlapping subpaths filled or transparent based on their path direction. For more information on path direction, see "Path and point characteristics" on page 71.

Overlapping paths running in the same direction are filled; overlapping paths running in opposite directions (counterclockwise and clockwise) are transparent.

4 If the composite path's overlapping fill does not appear as expected, select a subpath and do one of the following:

• Select Modify > Alter Path > Correct Direction.

Original (left) and Correct Direction applied (right)

• Select Modify > Alter Path > Reverse Direction.

• Select Window > Toolbars > Xtra Operations to display the Xtra Operations toolbar if it's not already displayed, and click either the Correct Direction button or the Reverse Direction button.

Note: If you're exporting composite paths to applications that don't support even/odd fills, apply the Correct Direction command, deselect Even/Odd Fill, and then export the path. Alternatively, select Modify › Alter Path › Remove Overlap to reconstruct a composite path with an even/odd fill as separate, nonoverlapping paths.

Using the Union command

Union combines two or more closed paths into a single path, enclosing the entire area of the original paths. If the selected path does not touch the other paths, the result is a composite path.

To apply the Union command to selected paths, do one of the following:

• Select Modify > Combine > Union.

• Select Window > Toolbars > Xtra Operations to display the Xtra Operations toolbar if it's not already displayed, and click the Union button. (For more information on working with Xtras, see "Using and managing Xtras" on page 27.)

• Select Xtras > Path Operations > Union.

Using the Divide command

Divide cuts selected paths into sections defined by the areas of overlap. Use open paths, closed paths, or a combination. Stroke and fill attributes of the topmost path are applied to the areas common to all selected paths.

To apply the Divide command to selected paths, do one of the following:

- Select Modify > Combine > Divide.
- Select Window > Toolbars > Xtra Operations to display the Xtra Operations toolbar if it's not already displayed, and click the Divide button. (For more information on working with Xtras, see "Using and managing Xtras" on page 27.)
- Select Xtras > Path Operations > Divide.

Using the Intersect command

Intersect creates a new path of the area common to all selected, closed paths, with the stroke and fill attributes of the farthest back object. If selected paths don't overlap, the command deletes the selection, unless the Path Operations Consume Original Paths preference is turned off. (See "Combining paths" on page 127.)

To apply the Intersect command to selected paths, do one of the following:

- Select Modify > Combine > Intersect.
- Select Window > Toolbars > Xtra Operations to display the Xtra Operations toolbar if it's not already displayed, and click the Intersect button. (For more information on working with Xtras, see "Using and managing Xtras" on page 27.)
- Select Xtras > Path Operations > Intersect.

Using the Punch command

Punch removes parts of selected, closed paths below the topmost, closed path. The front selected path is deleted as its shape punches a hole. Where a hole is fully enclosed within a path, a punched path becomes a composite path. Stroke and fill attributes remain unchanged.

To apply the Punch command to selected paths, do one of the following:

- Select Modify > Combine > Punch.
- Select Window > Toolbars > Xtra Operations to display the Xtra Operations toolbar if it's not already displayed, and click the Punch button. (For more information on working with Xtras, see "Using and managing Xtras" on page 27.)
- Select Xtras > Path Operations > Punch.

Using the Crop command

Crop uses the topmost path as a cookie cutter to trim selected, extending paths below the top path. Stroke and fill attributes remain unchanged.

Note: The Crop command operates only on vector objects. To crop a bitmap image, you must use the Crop tool. For information, see "Cropping a bitmap image" on page 326.

To apply the Crop command to selected paths, do one of the following:

- Select Modify > Combine > Crop.

- Select Window > Toolbars > Xtra Operations to display the Xtra Operations toolbar if it's not already displayed, and click the Crop button. (For more information on working with Xtras, see "Using and managing Xtras" on page 27.)

- Select Xtras > Path Operations > Crop.

Working with clipping paths

You can fill a closed path with other objects: vector graphics, text, or bitmap images. These paths are called clipping paths, and the items they contain are called contents or paste insides. Contents that extend beyond the clipping path are hidden, not deleted, and you can edit, move, and transform them.

Note: You can use a composite path as a clipping path only if you create the composite path before pasting objects inside.

When transforming a clipping path, you can choose whether the transformation affects the contents.

To create a clipping path:

1 Select one or more objects to use as the contents.

2 Position the objects the way you want them to appear as the contents in the clipping path.

3 Select Edit > Cut.

4 Select a closed path to use as the clipping path.

5 Select Edit > Paste Contents.

6 Select the Contents property in the Properties list of the Object panel.

When a clipping path's contents are selected, a paste contents handle appears on top of the contents in the workspace. By dragging this handle, you can reposition the contents.

Paste contents handle

7 Repeat the steps above to add additional contents to the clipping path.

To set transformation options for a selected clipping path:

1 Do one of the following:

- Select Modify > Transform > Move.

- Select Window > Transform, and click the Move button.

2 In the Transform panel, do one of the following:

- Select Contents if you want transformations applied to the clipping path to apply to the contents.

- Deselect Contents if you don't want transformations applied to the clipping path to apply to the contents.

To edit the contents of a selected clipping path:

1 Select the clipping path.

2 Subselect the contents you want to edit. To select all of the clipping path's contents, double-click the paste contents handle or double-click the Contents property in the Object panel Properties list.

3 Edit the contents.

To remove contents from a clipping path:

1 Select the clipping path.

2 Select Edit > Cut Contents.

Expanding a path

You can expand the stroke of a path to change a path into an object. For example, a simple path with only two points will become a closed, rectangular path with four points after you expand it.

When you expand an open path, the result is a filled, closed path. When you expand a closed path, the result is a composite path.

Expanding a stroke lets you edit its shape and add additional fills, such as gradient, lens effects, textures, and tiles.

To expand the stroke of a selected path using menu commands or Xtras:

1 Do one of the following:

• Select Modify > Alter Path > Expand Stroke.

• Select Windows > Toolbars > Xtra Operations to display the Xtra Operations toolbar if it's not already displayed, and click the Expand Stroke button.

• Select Xtras > Path Operations > Expand Stroke.

2 In the Expand Stroke dialog box, enter a value in the Width text box or adjust the width using the slider.

3 Adjust the Cap, Join, and Miter Limit settings. For more information on these attributes, see "Applying attributes to strokes" on page 166.

4 Click OK.

You can also expand the stroke of a path using live effects. For more information, see Chapter 7, "Special Effects," on page 193.

Insetting a path

Inset Path expands or contracts one or more closed paths by a specified amount and creates additional paths that follow the original path's outline. You can specify the number of additional paths as well as their location and spacing.

To create an inset path of a selected path:

1 Do one of the following:

- Select Xtras > Path Operations > Inset Path.

- Select Modify > Alter Path > Inset Path.

- Select Windows > Toolbars > Xtra Operations to display the Xtra Operations toolbar if it's not already displayed, and click the Inset Path button.

2 In the Inset Path dialog box, enter the number of paths to create in the Steps text box. A value of 1 replaces the selected object; a larger value creates the specified number of paths. Inset paths are created as grouped objects.

3 For steps greater than 1, select the spacing for the inset paths:

Uniform spaces the inset paths evenly.

Farther creates more space between the paths closer to the original and less space between paths farther away.

Nearer creates less space between the paths nearer to the original and more space between paths farther away.

4 Enter an inset value in the units of measurement for your drawing, or adjust the inset using the slider. Positive numbers place the new objects inside the original. Negative numbers place the new objects outside the original.

5 Adjust the Join and Miter Limit settings. For more information on these attributes, see "Applying attributes to strokes" on page 166.

6 Click OK.

Transforming objects

You can transform objects or points by rotating, scaling, skewing, reflecting, and moving them. You can make transformations using the transformation tools, the Transform panel, or an object's transform handles.

You can also apply transformations to objects as editable effects. After a transform effect has been applied, it is always live, so you can modify the scale and skew percentage, rotation angle, and move distance at any time. For more information on applying transformations as live effects, see "Using a Transform effect attribute" on page 197.

Note: Extruded objects are rotated differently than other objects. For more information, see "Extruding objects" on page 205.

Using the transformation tools

The transformation tool pop-up menu in the Tools panel consists of the following:

- The Scale tool enlarges or reduces objects.
- The Rotate tool applies two-dimensional rotations.
- The Reflect tool flips an object.
- The Skew tool slants an object along a specified axis.

To transform a selected object using the transformation tools:

1 Click or select a transformation tool in the Tools panel.

2 Place the pointer at the spot that will be the center of transformation on an object.

3 Drag to transform the object:

- Drag farther away from the point of transformation for greater control over the transformation.
- Shift-drag to constrain the transformation to 45° increments relative to the current constrain angle (File > Document Settings > Constrain).

Using the Transform panel

You can use the Transform panel to apply precise transformations and to display information on transformed objects. When you move, rotate, scale, skew, or reflect an object, the Transform panel displays the move distance, rotation angle, scale percentage, skew percentage, and reflection axis, respectively. For all transformations except moving an object, transformations are applied in relation to a set point on or around the object, called the center point. The Center X and Y Coordinate text boxes indicate the location of an object's center point after each transformation.

To learn how to move objects using the Transform panel, see "Moving objects" on page 112. To transform objects pasted inside a clipping path or group, see the procedures in "Transforming objects freely" on page 142.

To set an object's center point manually:

1 Click the Pointer tool in the Tools panel.

2 Double-click the object.

The object's transform handles and center point appear.

3 Drag the center point to the new location.

4 To reset a center point, deselect and then reselect the object, or hold down Shift and click the center point.

To rotate a selected object:

1 Do one of the following:

- In the Tools panel, if the Rotate tool is not showing, select it from its pop-up menu; then double-click it.

- Select Modify > Transform > Rotate.

- Select Window > Transform, and click the Rotate button in the Transform panel.

2 Select one or more of the following options:

Contents rotates the contents of a clipping path with the rest of the path.

Fills rotates gradient and tiled fills with the rest of the object.

3 In the Rotation Angle text box, enter a positive value to rotate the selection counterclockwise around its center. Enter a negative value to rotate the selection clockwise around its center.

4 Enter a value in the Copies text box. A value of 0 rotates only the selected object. Higher values create the specified number of copies, each of which is progressively rotated.

5 Set the object's center manually or by entering values in the X and Y text boxes in the Transform panel.

6 Click the Rotate button.

To scale a selected object:

1 Do one of the following:

- In the Tools panel, if the Scale tool is not showing, select it from its pop-up menu; then double-click it.

- Select Modify > Transform > Scale.

- Select Window > Transform, and click the Scale button in the Transform panel.

2 Select any of the following options:

Contents scales the contents of a clipping path with the rest of the path.

Fills scales a tiled fill with the rest of the object.

Strokes scales the object's stroke with the rest of the object.

Note: To transform stroke widths in grouped objects to show perspective, select the Transform as Unit option in the Object panel (Window > Object).

3 For horizontal scaling, enter a positive value in the X text box to enlarge the selection or enter a negative value to reduce it.

To adjust horizontal and vertical scaling separately, deselect Uniform.

4 For vertical scaling, enter a positive value in the Y text box to enlarge the selection or enter a negative value to reduce it.

5 Enter a value in the Copies text box. A value of 0 scales only the selected object. Higher values create the specified number of copies, each of which is progressively scaled.

6 Set the object's center manually or by entering values in the X and Y text boxes in the Transform panel.

7 Click the Scale button.

To skew a selected object:

1 Do one of the following:

- In the Tools panel, if the Skew tool is not showing, select it from its pop-up menu; then double-click it.

- Select Modify > Transform > Skew.

- Select Window > Transform, and click the Skew button in the Transform panel.

2 Select any of the following options:

Contents skews the contents of a clipping path with the rest of the path.

Fills skews a tiled fill with the rest of the object.

3 Enter a positive value in the H text box to skew the selection to the right, or enter a negative value to skew it to the left.

4 Enter a positive value in the V text box to skew the selection up, or enter a negative value to skew it down.

5 Enter a value in the Copies text box. A value of 0 skews only the selected object. Higher values create the specified number of copies, each of which is progressively skewed.

6 Set the object's center manually or by entering values in the X and Y text boxes in the Transform panel.

7 Click the Skew button.

To reflect a selected object:

1 Do one of the following:

- In the Tools panel, if the Reflect tool is not showing, select it from its pop-up menu; then double-click it.

- Select Modify > Transform > Reflect.

- Select Window > Transform, and click the Reflect button in the Transform panel.

2 Select any of the following options:

Contents reflects the contents of a clipping path with the rest of the path.

Fills reflects a tiled fill with the rest of the object.

3 Enter a value from 0 to 90° in the Reflect Axis text box to flip the selection horizontally. Enter a value from 90º to 180° in the Reflect Axis text box to flip the selection vertically.

4 Enter 0 or 1 in the Copies text box. Entering a higher number causes multiple copies of the object to be stacked on top of each other.

5 Set the object's center manually or by entering values in the X and Y text boxes in the Transform panel.

6 Click the Reflect button.

Transforming objects freely

You can use transform handles to freely transform objects, including text blocks, and to combine a series of transformations. You can also use transform handles to transform an object within a group or a paste inside, or to transform a point within a selected path.

If transform handles don't appear when you double-click an object, you can display them using FreeHand preferences.

Note: Extruded objects are rotated differently than other objects. For more information, see "Extruding objects" on page 205.

To display transform handles:

1 Display general preferences by doing one of the following:

• In Windows, press Control+U, then click the General tab.

• On the Macintosh, press Command+U, then click the General category.

2 Select Double-Click Enables Transform Handles, and click OK.

To transform freely:

1 Using the Pointer tool, double-click the object you want to transform.

Eight transform handles appear around the selection, and a circle appears at the selection's center point. To disable the transform handles, double-click away from the selection.

Moving the Pointer tool over and around the selection changes the pointer (cursor) to indicate which transformation function is available.

2 Drag the handles to transform the selection, as follows:

• To move the selection, position the pointer over the object within the selection rectangle, and drag the object to a new position. Do not drag the center point.

• To set the center of rotation, drag the center point to a new location.

• To rotate the selection, position the pointer just outside a transform handle and drag.

Shift-drag to rotate in 45° increments.

- To scale the selection, position the pointer on a transform handle, and drag.

  Shift-drag or drag a corner handle to resize proportionally.

- To skew the selection, position the pointer on the dotted outline between the transform handles and drag.

  Shift-drag to constrain the skew horizontally or vertically.

3 To copy the selection as you transform it, click and hold a handle, hold down Alt (Windows) or Option (Macintosh), and drag the handle. A plus (+) sign next to the pointer indicates copying.

To transform an object within a group or inside a clipping path:

1 Click the Pointer tool.

2 Double-click the group or clipping path to activate the transform handles, and drag to transform it.

3 Hold down Alt (Windows) or Option (Macintosh) to subselect the object you want to transform. The object's transform handles will be activated.

4 Press Tilde (~) to superselect objects in the group or clipping path without moving the center point.

To transform selected points within a path:

1 Double-click a point to activate transform handles for the entire selection, and drag to transform it.

2 Press Tilde (~) to activate transform handles for the entire path without moving the center point.

Power-duplicating

Power-duplicating is the process of repeating a transformation (move, scale, skew, reflect, rotate) on successive duplicates of the object. You can use power-duplication with more than one transformation. For example, you can move, scale, and skew a duplicate, and those transformations will be applied to successive duplicates.

Moving (left); moving and scaling (center); and moving, scaling, and rotating

Note: You cannot combine scaling and skewing during power-duplication.

To power-duplicate a selected object:

1 Select Edit > Duplicate.

2 Transform the object.

3 Without deselecting the object, select Edit > Duplicate.

4 To create additional copies, repeat step 3.

Undoing actions

Using the Edit > Undo and Redo commands, you can undo or redo up to 100 actions, depending on the memory available to your system. You can undo an action after you've saved a file, but not after you've closed and reopened it.

You can also undo any number of actions by reverting to the last saved version of the file.

To undo or redo an action, do one of the following:

• Select Edit > Undo [*action name*] to undo an action. If the Undo command is dimmed, you cannot undo the action.

• Select Edit > Redo [*action name*] to redo the action.

To set the number of undo levels:

1 Display general preferences by doing one of the following:

- In Windows, press Control+U, then click the General tab.

- On the Macintosh, press Command+U, then click the General category.

2 Enter a value between 1 and 100 in the Undo's text box. Setting the level to more than 10 uses additional computer memory.

3 Click OK. For this change to take effect, you must close and reopen the document or open a new document.

To revert to the last saved version of your file:

Select File > Revert, and then click Revert in the warning box. You cannot undo this action.

Changing default attributes

When no objects are selected in the workspace, the document's default attributes are displayed in the Object panel. Default attributes are defined by the currently selected style in the Styles panel. You can modify these attributes in the Object panel, and all new objects that you subsequently create will use the modified attributes, unless you select a different style before creating the objects. (For more information about styles, see "Using styles" on page 301.)

Modifying the attributes for an object does not change the default attributes for the document. You can change this behavior in FreeHand preferences, so that each time you modify an object's attributes, the default attributes are changed.

To change default attributes:

1 Select Edit > Select > None or press Tab to deselect all objects in your document.

2 Select Window > Object to display the Object panel if it's not already displayed.

3 Make your changes to the default attributes.

For information about editing attributes in the Object panel, see "Using the Object panel" on page 107.

To change default attributes by editing a selected object:

1 Display object preferences by doing one of the following:

- In Windows, press Control+U, then click the Object tab.

- On the Macintosh, press Command+U, then click the Object category.

2 Select the Changing Object Changes Defaults option to have changes to an object modify the default attributes.

3 Click OK.

In Macromedia FreeHand MX you can apply colors to objects using various techniques, and using colors from various color models. Whether for print, onscreen, or both, you can add, remove, name, and edit colors. FreeHand makes global color changes to a selection easy, without affecting the colors of unselected objects. You also can import and export color palettes and settings for use in other applications or FreeHand drawings.

Applying color to objects

You can apply colors to strokes and fills by dragging color swatches from the Color Mixer, Tints, or Swatches panels. You can apply colors to selected objects by using the Object panel or the pop-up color palettes in the Tools panel.

You can also apply colors by using the Eyedropper tool to drag colors from other objects in the active document.

The stroke and fill color boxes on the Tools panel open a color palette that by default displays a list of web-ready colors (called color cubes). You can change the palette's display to show the color list from the Swatches panel.

Stroke (upper) and fill (lower) color boxes in the Tools panel

For information on applying color to text, see "Applying color to text and text blocks" on page 269.

To apply color to a selected object, do one of the following:

• In the Swatches panel, drag a swatch to the Fill, Stroke, or Both color selector at the upper left of the Swatches panel.

• In the Swatches panel, click the Fill, Stroke, or Both selector at the upper left of the Swatches panel, and then select a color name in the list.

• In the Object panel, select the stroke or fill to which you want to apply a color, and then select a color from the Swatches panel. For more information on adding strokes and fills using the Object panel, see Chapter 6, "Using Strokes and Fills," on page 165.

• Click the stroke or fill color box in the Tools panel and select a color from the pop-up color palette.

To apply color to an unselected object:

Drag a color swatch from the color box in the Color Mixer, Tints, or Swatches panel onto the object's stroke or fill.

To change how color is applied to an unselected object:

1 Drag a color swatch from the color box in the Color Mixer, Tints, or Swatches panel over the object.

2 Before you release the mouse button, do one of the following:

• Hold down Shift as you release the mouse button to apply the color only to the object's fill.

• Hold down Control-Shift (Windows) or Command (Macintosh) as you release the mouse button to apply the color only to the object's stroke.

To apply color using the Eyedropper tool:

1 In the Tools panel, click the Eyedropper tool.

2 Position the pointer over the color that you want to apply.

3 Drag the color to the object to which you'll apply the color.

To change the display of the pop-up color palettes:

1 In the Tools panel, click the stroke or fill color box to display the color palette.

2 Click the palette's Options menu control and select Swatches or Color Cubes.

Spot and process colors

Spot and process colors correspond to the two main ink types used in commercial printing.

A *process color* is printed by combining the four standard CMYK process inks: cyan, magenta, yellow, and black. By blending these inks in varying proportions, the printer can reproduce most colors.

A *spot* (or custom) color is a special premixed ink that is used with, or instead of, CMYK process inks. A spot color requires its own plate on the press.

The difference between the two types of color is that process colors are printed as four-color separations, corresponding to the four process inks. Spot colors do not need to be separated, since a spot color is printed on a single plate.

FreeHand comes with several color libraries that you can import in whole or in part into your drawings. For more information, see "Editing colors" on page 161.

Color spaces

Color spaces are methods for defining colors in a computer application. Each color space has different benefits and drawbacks depending on whether you plan to present a drawing online or in print. The color space you choose also becomes important when you import or export artwork.

In FreeHand, you can define colors using four methods:

- CMYK color components represent the process inks used in four-color printing.

- RGB (red, green, and blue) is used for onscreen display, including web and multimedia design. RGB values range from 0 to 255 for each color.

- HLS (hue, lightness, and saturation) color mode produces RGB colors. This system is useful for picking different colors with similar values (for example, highly saturated colors of different hues).

- The System Color Picker (Windows) and the Apple Color Picker (Macintosh) display the colors installed in the operating system. The System Color Picker lets you choose from 48 basic Windows colors. The Apple Color Picker lets you define colors as CMYK, RGB, HLS, HSV (hue, saturation, value); you can choose from the 60-color Crayon picker or the 216-color Web HTML picker.

Using the Color Mixer panel

Use the Color Mixer panel to define colors, to adjust hue, lightness, and saturation, and to select colors from the System Color dialog box. Controls in the Color Mixer panel let you choose from four color modes and add colors to the color list in the Swatches panel.

Original   New

Add to Swatches panel

Change attribute color

Both the Color Mixer panel and the Tints panel use the same color box to display a color as you edit it. The color box displays the original color on the left and the new color on the right. You can change this display to a single color box setting by using FreeHand preferences. The single color box shows only the new color.

To show or hide the Color Mixer panel:

Select Window > Color Mixer.

To change the color box display for the Color Mixer and Tints panels:

1 Display colors preferences by doing one of the following:

• In Windows, press Control+U, then click the Colors tab.

• On the Macintosh, press Command+U, then click the Colors category.

2 Do one of the following:

• Deselect Color Mixer/Tints Panel Uses Split Color Box to display a single color box.

• Select Color Mixer/Tints Panel Uses Split Color Box to display a split color box.

3 Click OK.

To display a color's components, do one of the following:

• Use the Eyedropper to drag a color swatch from any object or color box to the color box at the bottom of the Color Mixer panel.

• Hold down Alt (Windows) or Option (Macintosh) and click a color name in the Swatches panel.

    The Color Mixer panel displays the color's CMYK or RGB values, as appropriate.

To change a color mode:

Click a color mode button in the Color Mixer panel.

Color mode buttons for Windows (left) and Macintosh (right)

To define a CMYK color or an RGB color:

1 Click the CMYK or RGB mode button to change color modes.

2 To adjust color component values, move the sliders or enter values in each entry text box. Use the color box to monitor the color as you mix it.

3 To add the new color to the Swatches panel, do one of the following:

• Click the Add to Swatches button near the lower left corner of the Color Mixer panel. Enter a name for the color, and then specify Spot or Process. Click Add.

• Drag a color swatch from the color box to the arrow button on the Swatches panel. (For more details, see "Adding colors to the Swatches panel" on page 154.)

To define a hue/lightness/saturation (HLS) color:

1 In the Color Mixer panel, click the HLS button to display the HLS color picker.

2 To select the hue (color), click or drag the color point around the color wheel, or enter a value from 0° to 360° in the top, or hue, text box. Hues range from red (0°) through orange, yellow, green, blue, and purple.

3 Use the vertical slider or enter a percentage in the middle, or lightness, text box from 0% (black) to 100% (white).

4 To set the strength of the hue, click or drag the color point toward or away from the center of the color wheel, or enter a percentage in the bottom, or saturation, text box. Increasing saturation adds color; decreasing saturation removes color, leaving a grayer result.

5 Switch to RGB view to see the color component values for the new color.

6 To add the new color to the Swatches panel, do one of the following:

- Click the Add to Swatches button. Enter a name for the color, and then specify Spot or Process. Click Add.

- Drag a color swatch from the color box to the color list at the bottom of the Swatches panel. (For more details, see "Adding colors to the Swatches panel" on page 154.)

Using the Tints panel

Tints are lighter versions of a color. You create them by specifying a percentage of the original color. To apply, create, and edit tints, you use the Tints panel.

If you add a tint to the Swatches panel, its base color is also added. If you remove the base color from the Swatches panel, all tints based on that color are removed as well.

To show or hide the Tints panel:

Select Window > Tints.

To apply or create a tint:

1 In the Tints panel, select the base color of the tint by doing one of the following:

- Drag a color swatch from the Swatches panel to the color box in the Tints panel.

- Select a base color from the Tints pop-up menu in the Tints panel.

2 Select the tint by clicking a preset tint in the color bar, dragging the slider, or entering a percentage from 1 to 100.

3 To apply the color, do one of the following:

- Drag a swatch from any of the Tints panel color boxes to an object.

- Drag a swatch to the stroke or fill color box on the Tools panel (see "Applying color to objects" on page 147).

- Click the Apply Color button.

4 To add the new tint to the Swatches panel, do one of the following:

- Click the Add to Swatches button.

- Drag a color swatch from any of the Tints panel color boxes to the arrow button in the Swatches panel (for more information, see "Adding colors to the Swatches panel" on page 154).

  The tint's name is preceded by the percentage of the original color it represents.

Using the Swatches panel

The Swatches panel lets you store colors, edit and rename them, convert process colors to spot colors and vice versa, change the color space (RGB and CMYK), and import and export custom color libraries.

To show or hide the Swatches panel:

Select Window > Swatches.

Swatches panel

The Swatches panel displays the color list for the active document. It also has three selectors: Fill (left), Stroke (center), and Both for combined Fill and Stroke (right). The active selector button appears pressed. The selectors show the stroke and fill colors for a selected object. The colors also appear in the color boxes in the Tools panel.

Fill selector (left), Stroke selector (middle), and Both selector (right)

The default colors in a new document are None, White, Black, and Registration. These colors cannot be deleted or renamed. Black is a spot black that prints on the process black plate. The registration color, used for crop marks or trim marks, prints solid on all plates.

The Swatches panel uses italics to display process color names and uses plain type to display spot color names. It also displays a triple-dot icon next to RGB colors, no icon for CMYK colors, and a black hexagon for Hexachrome colors. RGB colors include those created in HLS mode, the Apple Color Picker (Macintosh), and the System Color Picker dialog box (Windows).

From top to bottom: a CMYK process color, a CMYK spot color, an RGB process color, and an RGB spot color

Adding colors to the Swatches panel

You can create colors in the Color Mixer or Tints panel and then add them to the color list in the Swatches panel for use in your illustrations.

You can name a color when you add it to the Swatches panel, or you can let FreeHand name the color using the color mix values in the appropriate color mode. If your illustration includes unnamed colors, you can use the Name All Colors Xtra to add them to the Swatches panel (see "Naming colors" on page 155).

The Swatches panel also displays the names of any spot or process colors in artwork you copy or import from other files, such as editable Encapsulated PostScript (EPS), Adobe Illustrator, and CorelDRAW files. These named colors remain in the color list even if you delete the copied or imported objects.

If you import a color with the same name as one in the Swatches panel, FreeHand changes the name of the color to the color mix values as shown in the Swatches panel.

To add colors to the Swatches panel, do one of the following:

- Create a color in the Color Mixer or Tints panel. Click the Add to Swatches button. Enter a name for the color or accept the default name, and then specify Spot or Process. Click Add.

  Note: Control-click (Windows) or Command-click (Macintosh) the Add to Color List button to bypass the dialog box. The new color takes the default name and becomes a spot or process color depending on the choice made the last time the dialog box was used.

- Drag a color from the color box of the Color Mixer or Tints panel either to the empty space at the bottom of the list of swatches or onto the arrow button at the top of the Swatches panel. Drag onto an existing color swatch to replace a color.

- In Windows, right-click any color box in the Color Mixer or Tints panel and select Add to Swatches from the context menu. This bypasses the dialog box and adds the color with a default name.

To duplicate a color:

1 In the Swatches panel, select a color name.

2 Click the Swatches panel Options menu control and select Duplicate.

The new color is named "Copy of [*original color*]."

Naming colors

Colors listed in the Swatches panel must have a name. Unnamed colors appear in the drawing if you've added colors to objects using the Color Mixer panel or a pop-up color palette.

When you add a color to the Swatches panel, FreeHand assigns a name based on the color's RGB or CMYK values. By default, dragging a different color swatch onto that color renames it according to its new values. You can turn off this automatic renaming in FreeHand preferences.

If you drag a swatch into the Swatches panel and drop it onto a color named something other than the default FreeHand name, the color is changed but not its name. For example, if you have imported a purple color named *Grape* into the Swatches panel, and you drag a red color swatch onto it, *Grape* will now be red.

If you add two or more identical colors from the Color Mixer or Tints panels to the Swatches panel and use the default color names, FreeHand displays the copies with a dash and number after the color name, as the following illustration shows:

If you duplicate a color using the Duplicate command from the Swatches panel's pop-up Options menu, the new color is named "Copy of [*original color*]."

The Name All Colors Xtra adds all unnamed colors used in a document to the Swatches panel with default names. The Name All Colors Xtra also lists any colors you have created by applying the Xtras that manipulate colors, such as Color Control, Desaturate, Darken, Lighten, Randomize, or Saturate Colors. (For more information, see "Editing colors" on page 161.)

The Name All Colors Xtra does not name colors in bitmap images.

To set automatic renaming preferences for default color names:

1 Display colors preferences by doing one of the following:

• In Windows, press Control+U, then click the Colors tab.

• On the Macintosh, press Command+U, then click the Colors category.

2 Do one of the following:

• Select Auto-Rename Colors to automatically rename a color when you change it.

• Deselect the option to keep the original name when you change a color.

3 Click OK.

To rename a color in the Swatches panel:

1 Select Edit > Select > None or press Tab to deselect all objects.

2 In the Swatches panel, double-click the color name.

3 Type a unique name for the color.

4 Press Enter (Windows) or Return (Macintosh) or click anywhere in the application to apply the name.

   If you enter the same name as another color in the panel, you'll be prompted to rename the color.

To add unnamed colors to the Swatches panel:

1 Select an object whose color you want to add to the Swatches panel.

2 Choose from the following options:

• Select Window > Object to display the Object panel. Drag from any of the Object panel color boxes to the arrow button on the Swatches panel.

• In the Object panel, select Add to Swatches from the color pop-up menu. Enter a name for the color, select Spot or Process, and click Add.

• Select the Eyedropper tool and drag a color swatch from the object to the arrow button on the Swatches panel.

• Select Xtras > Colors > Name All Colors to add all unnamed colors, including tints, in a document to the Swatches panel.

Converting between RGB and CMYK

When creating artwork and printing it, you can specify color as RGB or CMYK in the Swatches panel. For more information on color management, see Chapter 13, "Color Management," on page 363. You can also convert colors in the Separations panel in the Print Setup dialog box. For information on converting RGB colors to process colors when printing a document, see Chapter 14, "Printing," on page 375.

To convert between RGB and CMYK using the Swatches panel:

1 Select Edit > Select > None or press Tab to deselect all objects.

2 In the Swatches panel, select the color you want to convert. To convert a color, it must be named in the Swatches panel.

3 Click the Swatches panel Options menu control and select one of the following:

Make RGB converts CMYK colors to the nearest RGB value and may produce a noticeable color shift.

Make CMYK converts RGB colors to the nearest CMYK value and may produce a noticeable color shift.

Note: Converted colors may appear unchanged after conversion, especially if a color management preference is active.

Specifying colors as process or spot

The Swatches panel lets you specify a color as a process color (made up of the four color components) or a spot color (custom). Process colors are output on four separate plates or pages, corresponding to the four process inks. Spot colors are printed using a separate plate, so they don't need to be separated.

For best results, don't specify a process color based on how it looks on your monitor unless you have set up a color management system properly. For more information, see Chapter 13, "Color Management," on page 363. Use RGB colors for documents intended only for online viewing.

For more information on converting between process colors and spot colors for printing, see Chapter 14, "Printing," on page 375.

To convert a color to a process or spot color:

1 In the Swatches panel, select the color.

2 Click the Swatches panel Options menu control and select one of the following:

Make Spot makes the color a custom color.

Make Process makes the color a process color.

For information on printing spot colors as process colors, see Chapter 14, "Printing," on page 375.

Adding colors from color libraries

FreeHand comes with predefined spot- and process-color libraries that are part of commercially available color-matching systems. Color-matching systems provide printed and onscreen color swatches for designers and contain instructions for print professionals so that they can print the colors you specify. Consult with your commercial printer to learn which color libraries they support and recommend.

The following color libraries (all process color, unless noted) are shipped with FreeHand:

- Crayon arranges colors as commonly found in multicolor crayon sets.

- DIC Color Guide provides a standard set of spot colors used for printing color illustrations (used primarily in Japan).

- Focoltone organizes colors by their common percentage of cyan, magenta, yellow, or black.

- Grays displays only tints of black.

- Munsell colors are organized by hue, value, and chroma.

- PANTONE spot colors appear in chromatic order.

- PANTONE process (four-color and Hexachrome) colors are in chromatic order, including process-color simulations of the spot-color library.

- Toyo organizes spot colors first by hue and then by saturation.

- Web Safe is a library of 8-bit-compatible color containing 216 colors named after their RGB and hexadecimal values.

Custom colors display the name of the custom color library with a library-specific color reference. PANTONE Hexachrome colors comprise two of the custom color libraries in FreeHand. In the Swatches panel, these colors appear with hexagon-shaped icons to the right of the color names.

PANTONE HEXACHROME H 10-12 CVC
PANTONE HEXACHROME Green CVC
PANTONE HEXACHROME H 530-2 CVC

To add colors from a color-matching system library or custom color library:

1 Click the Swatches panel Options menu control and do one of the following:

• Select a library from the Options pop-up menu.

PANTONE Hexachrome Coated color library

• If a custom color library is stored outside the Color folder in the FreeHand application folder, select Import from the Options pop-up menu to locate and open the library.

2 In the Library dialog box, select colors that you want to add to the Swatches panel. Control-click (Windows) or Shift-click (Macintosh) to add multiple colors.

3 Click OK.

Using Photoshop color tables

You can import the colors from a Photoshop color index table into the FreeHand color list to ensure that the same color values are found in both applications.

To import a Photoshop color index table:

1 Select Xtras > Colors > Import RGB Color Table.

2 Locate the Photoshop ACT file that contains the index to import.

Some versions of Photoshop store color tables in its application Color Swatches folder within the Goodies folder. Other versions of Photoshop store color tables in the Presets\Optimized Colors folder or the Presets\Save for Web Settings folder. Photoshop color tables have the .act file extension.

Managing the color list in the Swatches panel

You can sort colors by name, rearrange colors, hide or show color names, and delete unused colors from your artwork.

FreeHand sorts colors (other than the defaults) first numerically and then alphabetically.

You can change the Swatches panel to show only color swatches and hide color names. Changing the panel lets you display more colors at the same time. The active color is outlined with a solid border. You cannot rearrange colors when the color names are hidden.

To sort the color list by color name:

1 Click the Swatches panel Options menu control to display the Options pop-up menu.

2 If the color list is displayed by color swatch only, select Show Names from the Options pop-up menu to display the color names.

3 Select Xtras > Colors > Sort Color List by Name.

To rearrange colors in the color list:

1 Select a color name.

2 Drag the color name to a new position.

Be sure to drag the color name and not the color swatch; dragging the color swatch replaces an existing color.

To hide color names in the color list:

Click the Swatches panel Options menu control and select Hide Names.

Removing colors

Removing colors from the color list in the Swatches panel retains the colors in any corresponding objects as unnamed colors. When you remove multiple colors, a dialog box prompts you either to remove all colors or to remove only the unused colors.

Removing spot, Hexachrome, and tint colors does the following:

- Spot colors are converted to process colors. Objects containing these spot-to-process converted colors may not print separations as intended.

- Hexachrome colors are converted to RGB values. The Hexachrome icon appears to the side of the name in the Swatches panel.

- Removing the base color of a tint also removes any tints of that color.

   Note: You can't remove or replace imported spot or process colors from an unconverted EPS file. To determine whether an imported EPS file is unconverted, select the object in your drawing. The Object panel displays "EPS" for unconverted EPS files.

To remove specific colors:

1 Select Edit > Select > None or press Tab to deselect all objects.

2 Click a color name in the Swatches panel. Shift-click to select additional colors that are adjacent. Control-click (Windows) or Command-click (Macintosh) to select additional colors that are not adjacent.

3 Click the Swatches panel Options menu control and select Remove.

4 At the prompt, click Remove to remove all selected colors or Cancel to cancel the operation.

To remove all unused named colors:

Select Xtras > Delete > Unused Named Colors to remove unused named colors.

Editing colors

You can edit colors in your artwork by using various techniques in FreeHand: you can brighten or dull colors, add or subtract percentages of color values, create grayscale and monochome effects; convert colors to grayscale, and globally change color throughout your artwork.

To alter color component values of an existing color, you use the Color Mixer panel (see "Using the Color Mixer panel" on page 150).

Brightening and dulling colors

Using the Colors Xtras, you can brighten colors or dull them in a single step. To control colors more precisely, use the Color Control Xtra (see "Controlling color values" on page 162). The Lighten, Darken, Saturate, and Desaturate Colors Xtras do not affect spot colors.

To brighten or dull colors:

1 Select an object.

2 Select Xtras > Colors and then select an option:

Lighten Colors makes the color lighter.

Darken Colors makes the color darker.

Saturate Colors makes the color more intense.

Desaturate Colors dulls the color.

The effect increases each time you apply the Xtra until the maximum effect is reached.

Controlling color values

The Color Control Xtra adds or subtracts a percentage of a CMYK, RGB, or HLS color value to or from all colors in a selection. If a color already consists of minimum or maximum values, or if it is a spot color, the Color Control Xtra has no effect.

Using the Color Control Xtra to modify objects with named colors produces unnamed colors. The original named colors remain in the Swatches panel. To add the modified colors to the Swatches panel, you must name them (see "Naming colors" on page 155).

To control color values:

1 Select Xtras > Colors > Color Control.

2 In the Color Control dialog box, select a color mode: CMYK, RGB, or HLS.

3 Select Preview to view changes as you make them.

4 Drag the sliders or enter values to adjust the color components, between -100% and 100%, and -360° to 360° for Hue; the default is 0 for no change.

Creating grayscale effects

You can convert vector objects to grayscale or convert grayscale graphics to another color for a monochrome effect using the Convert to Grayscale Xtra. Converting a color also converts any tints based on it.

To convert a selected object to grayscale:

Select Xtras > Colors > Convert to Grayscale.

Objects are converted to tints of black.

Making global color changes

You can replace all colors of the same name in your artwork by replacing the global process color or spot color swatches in the Swatches panel. See "Finding and replacing graphics" on page 126.

You can also randomly change all of the colors in the color list, using the Randomize Named Colors Xtra. Experiment with this Xtra to create new color combinations.

You cannot replace the default Black, White, None, or Registration colors.

To replace colors in the color list:

1 In the Swatches panel, select a color name.

2 Click the Swatches panel Options menu control and select Replace.

3 In the Replace Color dialog box, select the source of the replacement color—either a color library or the color list in the Swatches panel.

4 Use the pop-up menus or color swatch to select a new color. All fills and strokes containing the original color are redrawn using the new color.

To randomly change all named colors:

Select Xtras > Colors > Randomize Named Colors.

Exporting colors

You can export colors from the color list in the Swatches panel to use as a color library, which you can then use in other documents.

When you export artwork to some file formats, you can also choose to convert the colors to RGB or CMYK. For more information, see "Saving files" on page 341.

To create a custom color library by exporting colors:

1 Click the Swatches panel Options menu control and select Export.

2 In the Export Colors dialog box, select the color or colors you want to export.

3 Click OK.

4 In the Create Color Library dialog box, type a library name and then type a filename. Enter the number of rows and columns and any notes.

5 Click Browse (Windows) or Save As (Macintosh) and specify the folder where the colors are to be stored.

   Note: Color libraries that appear in the Swatches panel are stored in the Macromedia/FreeHand/11/English/ Settings/Colors folder within your user-specific Application Data (Windows) or Application Support (Macintosh) folder. The location of your user-specific Application Data or Application Support folder can vary depending upon your operating system. For information on how to locate this folder, refer to your operating system's documentation.

6 Click Save.

You can apply colors to strokes and fills several ways in Macromedia FreeHand MX: by using the Object panel, by dragging colors, by choosing colors from the pop-up color palettes on the Tools panel, and by using the Eyedropper tool to copy colors from other objects in the document.

In addition to basic colors, you can also apply a variety of advanced stroke and fill effects to objects.

Adding strokes and fills to objects

FreeHand MX objects can have multiple properties, such as strokes, fills, and special effects. (For more information on special effects, see Chapter 7, "Special Effects," on page 193.) Use the Object panel to add properties to objects and to modify the attributes of the properties you add.

The upper portion of the Object panel displays a Properties list for the current selection in the Document window. The bottom portion of the Object panel displays attributes for the current selection in the Properties list.

Properties list

Attributes

The Properties list is hierarchical, and the order of properties in the list affects the appearance of the object. You can change an object's appearance by dragging to rearrange items in the list.

To add a stroke to a selected object, do one of the following:

- Click the Add Stroke button in the Object panel.

- Click the Object panel Options menu control and select Add Stroke.

To add a fill to a selected object, do one of the following:

- Click the Add Fill button in the Object panel.

- Click the Object panel Options menu control and select Add Fill.

To delete a stroke or fill from a selected object:

1 Select the stroke or fill in the Object panel.

2 Click the Remove Item button in the Object panel.

To move a stroke or fill up or down in an object's hierarchical Properties list:

Drag the stroke or fill within the Properties list in the Object panel.

Applying attributes to strokes

There are six different attributes for stroke styles in the Object panel—Basic, Brush, Calligraphic, Custom, Pattern, and PostScript.

Use the Object panel to apply stroke styles to selected strokes or to set the default stroke attributes for new objects in the active document. You can choose from preset stroke widths, or you can enter a custom width.

For more information on applying colors to strokes, see Chapter 5, "Working with Color," on page 147.

To set default stroke attributes for new objects:

1 Select Edit > Select > None to deselect all objects in the document.

2 Select Window > Object to display the Object panel.

3 Select a stroke in the Properties list.

4 Set the stroke attributes you want applied to new objects.

To edit the list of preset stroke widths:

1 Display object preferences by doing one of the following:

• In Windows, press Control+U, then click the Object tab.

• On the Macintosh, press Command+U, then click the Object category.

2 In the Default Line Weights text box, enter the values in points. Separate values with a space.

3 Click OK.

4 Relaunch FreeHand for the changes to take effect.

Using basic stroke attributes

Paths that use Basic stroke attributes are simple lines. You can change the stroke width and color. You can change how a basic stroke is terminated, or capped, and how it joins other strokes.

You can also apply attributes to basic strokes to make them dashed or to give them arrowheads. You can edit the preset dashes and arrowheads, and you can create new ones.

To apply a basic stroke attribute to a selected stroke in the Object panel:

1 In the Object panel, select Basic from the stroke type pop-up menu.

2 To choose a color for the stroke, do one of the following:

• Select a color from the stroke color pop-up menu in the Tools panel.

• Drag a color swatch to the stroke color in the Properties list.

3 Specify a stroke width by doing one of the following:

• Select one of the preset values from the width pop-up menu. Preset values appear in points.

• Type a value from 0 to 288 (Windows) or 0 to 16,164 (Macintosh) points in the width text box, and press Enter.

4 Select a Cap option to set the style for a path end: Butt, which is flush with the path's end, Round, or Square, which extends beyond the path by half the stroke width.

Butt, Round, and Square caps

5 Select a Join option to define how two path segments meet: Miter, Round, or Beveled. To change the corners in an open or closed path, select a path and select another join option.

Miter, Round, and Beveled join

6 To avoid beveling a Miter join, enter a Miter limit from 1 to 57.

Line lengths exceeding this value are squared off instead of pointed. For example, a miter limit of 2 for a 3-point stroke means that when the length of the point is twice the stroke weight, FreeHand switches to a Bevel join.

Miter (left) and Beveled (right) joins, with arrows showing the length of the Miter join

7 To apply a dashed stroke, select a style from the dash style pop-up menu. Select No Dash for a solid stroke.

8 To apply an arrowhead to an open path, select from the Arrowheads pop-up menus.

The left pop-up menu applies an arrowhead to the first point (origin) of the selected path, and the right pop-up menu applies to the last point. Arrowheads follow the path direction.

To create a new dashed stroke style:

1 In the Object panel, hold down Alt (Windows) or Option (Macintosh) as you select a dash from the dash style pop-up menu.

2 To set dash sizes, enter values in any of the On text boxes in the Dash Editor. To set the space sizes between dashes, enter values in any of the Off text boxes.

3 Click OK to add a new dash to the dash style pop-up menu and apply the new dash to any selected paths.

Note: The dash style pop-up menu can display up to 255 dashed strokes. You cannot remove styles from the menu.

To create a new arrowhead:

1 In the Object panel, select New from one of the Arrowheads pop-up menus to display the Arrowhead Editor.

The Arrowhead Editor provides a subset of FreeHand tools, including the Pen tool, for drawing or editing.

2 Use the tools to draw a new arrowhead.

3 Click New.

To create an arrowhead from an existing one:

1   In the Object panel, hold down Alt (Windows) or Option (Macintosh) and select an arrowhead from the Arrowhead pop-up menus to display the Arrowhead Editor.

The Arrowhead Editor provides a subset of FreeHand tools, including the Pen tool, for drawing or editing.

2   Edit the arrowhead.

3   Click New to add the new arrowhead to the Arrowheads pop-up menu.

Note: The Arrowheads pop-up menus can display up to 255 arrowheads. You cannot remove arrowheads from the menus.

Using brush stroke attributes

You can apply symbols to a stroke using the brush feature. You can use the symbols that came with FreeHand, or you can import or create your own. For more information on using symbols, see "Using the Library panel" on page 297.

You can apply a brush in one of two modes. Spray repeats an instance along the path. Paint stretches a specified number of instances along the path.

Spray and Paint modes for a brush

To apply a brush to a selected stroke in the Object panel:

1   Select Brush from the stroke type pop-up menu.

2   Select the brush you want to apply from the brush pop-up menu.

3   Enter a percentage value in the width text box to set the size of the brush. This value can be from 1% to 400%.

To create a brush from a selected object:

1   Select Modify > Brush > Create Brush.

2   Select an option:

Copy creates a symbol from the selected object, but does not convert the object to a symbol.

Convert creates a symbol from the object and replaces the object with an instance of the symbol.

3 In the Edit Brush dialog box, type a name for this brush in the Brush Name text box.

4 Use the Include Symbol controls to add other symbols to the brush. (The Brush Preview window at the bottom of the dialog box shows what the brush will look like.)

• Click the Plus (+) button to select from a list of available symbols to add to this brush.

• Click the Minus (-) button to remove a symbol from the brush.

• Select a symbol in the list and use the arrow buttons to move it up or down in the stack list. The stack list determines the stacking order of instances as they are applied to the path.

5 Select Paint or Spray to set the mode for this brush. If you select Paint, enter a value from 1 to 500 in the Count text box to set the number of instances to appear on this brush.

6 Select Orient on Path if you want this brush to rotate to follow the orientation of the path to which it is applied. If you deselect Orient to Path, the brush does not follow the path: when set to Paint, the brush stretches between the endpoints of the path, and when set to Spray, the brush maintains its original orientation regardless of the path.

7 Select Fold Corners to use the type of brush strokes used by earlier versions of FreeHand.

8 Set the spacing, or the distance between instances of the brush symbol. Select one of the following options:

Fixed sets a fixed spacing as a percentage of the size of the symbol. Enter a value from 1% to 200%, or click the arrow to set the spacing with the slider.

Random sets a random spacing. Enter the minimum (Min.) and maximum (Max.) values for the variation.

Variable varies the spacing between each instance of the brush symbol from the Min. to the Max. values.

9 Set the angle to specify the rotation of the instance as it is applied to the path. Select from the following options:

Fixed sets a fixed rotation. Enter a value from 0° to 359°, or click the arrow to set the angle with the slider.

Random sets a random rotation. Enter the Min. and Max. values for the variation.

Variable varies the rotation smoothly from the Min. to the Max. values.

10 Set the offset between the brush and the path. Select from the following options:

Fixed sets a fixed offset. Enter a value from -200% to 200%, or click the arrow to set the offset with the slider.

Random sets a random offset. Enter the Min. and Max. values for the variation.

Variable varies the offset smoothly from the Min. to the Max. values.

Flare increases/decreases the offset according to the minimum and maximum scaling values, if the brush type is Spray.

11 To set the scaling for the brush, select one of the following options:

Fixed sets a fixed scaling. Enter a value from 1% to 200%, or click the arrow to set the size with the slider.

Random sets a random scaling. Enter the Min. and Max. values for the variation.

Variable varies the scaling smoothly from the Min. to the Max. values.

Flare spreads/expands the brush according to the minimum and maximum scaling values, if the brush type is Paint.

12 Click OK.

To import a brush:

1 In the Object panel, select a stroke to display the stroke attributes.

2 Select Brush from the stroke type pop-up menu.

3 Click the Options button and select Import.

4 In the Import Brushes dialog box, select the file that contains the brushes you want to import; then click Open.

5 In the Import Symbols dialog box, select the brushes you want to import. Control-click (Windows) or Command-click (Macintosh) to select multiple brushes.

6 Click Import.

Note: When you import a brush file, the colors used in that file are added to the current document's color list, and the symbols used as brush tips are imported into the library.

To edit a brush:

1 In the Object panel, select a stroke to display the stroke attributes.

2 Select Brush from the stroke type pop-up menu.

3 Select the brush you want to edit from the brush pop-up menu.

4 Click the Options button and select Edit.

5 Edit the brush. For more information on editing brushes, see steps 3–11 in the previous procedure.

6 Click OK.

7 If the brush you edited is in use, a dialog box appears. Select Change to apply your edits to all paths using that brush. Select Create to create a new brush. The new brush is automatically named "Copy of [*old brush name*]."

Note: You can also edit a brush by editing its symbols in the Library panel (see "Editing symbols" on page 300).

To duplicate a brush:

1 In the Object panel, select the brush you want to duplicate from the brush pop-up menu.

2 Click the Options button and select Duplicate.

3 A new brush called "Copy of [*original brush*]" appears in the brush pop-up menu.

To delete a brush:

1 In the Object panel, select the brush you want to delete from the brush pop-up menu.

2 Click the Options button and select Remove.

3 In the dialog box that appears, select an option:

Release separates the brush stroke from its path. The stroke is converted to a group of objects, and this group is grouped with the object that originally contained the brush stroke.

Delete deletes the brush and any paths that use the brush.

To export a brush:

1 Select the brush you want to export in the Brush pop-up menu.

2 Click the Options button and select Export.

3 In the Export Brushes dialog box, select the brushes you want to export. Shift-click to select multiple brushes.

4 Click Export.

5 In the Export Brushes dialog box, type a filename and select the location for the new brush file. Click Save.

Using calligraphic stroke attributes

Calligraphic stroke attributes simulate a calligraphic pen by letting you use any object shape as the tip, or *nib*, used to draw a stroke. You can change the width, height, and angle of calligraphic stroke tips.

You can use any object that consists of a single closed path as a calligraphic tip.

To apply a calligraphic attribute to a selected stroke in the Object panel:

Select Calligraphic in the stroke type pop-up menu.

To use an object as a custom calligraphic tip:

1 Select the object you want to use as a calligraphic tip.

2 Select Edit > Copy.

3 In the Object panel, select the stroke to which you want to apply the calligraphic attribute.

4 Select Calligraphic in the stroke type pop-up menu.

5 Click Paste In to create a calligraphic tip based on the contents of the Clipboard.

To copy a custom calligraphic tip from a selected stroke in the Object panel:

1 Select the stroke that contains the calligraphic attribute you want to copy.

2 In the Object panel, the calligraphic tip appears in the preview window. Click Copy Out to copy the tip object to the Clipboard.

You can now copy the calligraphic tip object into your document or use it to create a calligraphic stroke for another object.

Using custom stroke attributes

A custom stroke attribute applies one of 23 preset, repeating PostScript patterns to a path. You can change the stroke's width, and you can change the length of each pattern tile and the spacing between tiles. You can also change the color, except for the Neon stroke. Custom stroke attributes do not display onscreen, but appear when you print to a PostScript printer.

Transforming a custom stroke pattern changes the pattern's orientation to the path but keeps the same length and spacing.

Custom stroke attributes do not print when combined with raster effects. For more information on raster effects, see "Applying live raster effects" on page 198.

FreeHand offers the following custom strokes.

Arrow	
Ball	
Braid	
Cartographer	
Checker	
Crepe	
Diamond	
Dot	
Heart	
Left Diagonal	
Neon	
Rectangle	

Right Diagonal	
Roman	
Snowflake	
Squiggle	
Star	
Swirl	
Teeth	
Three Waves	
Two Waves	
Wedge	
ZigZag	

To apply a Custom stroke attribute to a selected stroke in the Object panel:

1 Select Custom from the stroke type pop-up menu.

The preview shows a sample of the selected stroke.

2 Select a color for the stroke.

3 Set the stroke width, length, and spacing.

4 Press Enter (Windows) or Return (Macintosh).

Using pattern stroke attributes

You can choose from 64 predefined pattern stroke attributes. You can also edit each pattern. The Object panel displays an editable version of the pattern on the bottom left, and a preview to the right that updates as you edit the pattern.

Note: Pattern stroke attributes print based on the resolution of the printer, and therefore look best when printed at 300 dpi or lower.

To apply a pattern attribute to a selected stroke in the Object panel:

1 In the Object panel, select Pattern from the stroke type pop-up menu.

2 Select a color for the pattern.

3 Set the stroke width.

4 Click a pattern in the lower right corner of the panel. Use the slider to scroll through the available patterns.

To edit a pattern:

1 In the Object panel, select Pattern from the stroke type pop-up menu.

2 Select a pattern, using the slider at the bottom of the panel to scroll through the available patterns.

The selected pattern appears in the preview windows.

Pattern preview in the Object panel

3 Click one pixel at a time or drag in the left preview. Clicking a pixel toggles between black (opaque, in the selected color) and white (transparent).

4 Select Clear to remove a pattern from the preview window.

5 Click Invert to reverse pixel color—from color to white or from white to color.

Using PostScript stroke attributes

PostScript applies a stroke with a unique pattern and shape that you create in the PostScript Code text box. FreeHand sends the PostScript code to the PostScript interpreter in your printer's Raster Image Processor (RIP). If your code is incorrect, you will receive a PostScript error message when printing.

PostScript stroke attributes do not appear onscreen, but appear when you print to a PostScript printer.

Note: PostScript programming is beyond the scope of this document. For more information, refer to a PostScript language manual.

To apply a PostScript attribute to a selected stroke in the Object panel:

1 Select PostScript from the stroke type pop-up menu.

2 Enter up to 255 characters of code in the PostScript Code text box. You can type the code directly or paste it from another source.

Separate commands with a space, and allow them to wrap on their own.

3 Press Enter (Windows) or Return (Macintosh) to apply the stroke.

Object panel and PostScript random stroke attribute applied to centerline

Applying attributes to fills

You can apply eight different fill attributes to fills—Basic, Custom, Gradient, Lens, Pattern, PostScript, Textured, and Tiled.

A fill is defined by the boundaries of a path. If the path is open, the fill is contained within the boundaries drawn by an imaginary line between the beginning and ending points.

You use the Object panel to apply fill attributes to selected fills or to set the default fill attributes for new objects in the active document.

For more information on applying colors to fills, see "Applying color to objects" on page 147.

Note: Your onscreen display and printed results depend on the complexity of the fill and your output device. For more information, see Chapter 14, "Printing," on page 375.

Using basic fill attributes

A basic fill attribute creates a solid color fill.

To apply a basic attribute to a selected fill in the Object panel:

1 Select Basic from the fill type pop-up menu.

2 To choose a color for the fill, do one of the following:

• Select a color from the colors pop-up menu.

• Drag a color swatch from the Swatches panel to the stroke in the Object panel.

• Use the Eyedropper tool to drag a color swatch to the color box next to the color pop-up menu.

Note: For information on the Overprint option, see Chapter 14, "Printing," on page 375.

Using custom fill attributes

You can choose Custom fill to apply a preset, repeating PostScript pattern to an object. All custom fills except Black & White Noise can be edited.

Custom PostScript fill attributes do not appear onscreen, but appear when you print to a PostScript printer.

Opaque custom fills are Black & White Noise, Noise, Bricks, and Tiger Teeth. Objects behind the fill aren't visible when printed. Transparent custom fills are Circles, Hatch, Random Grass, Random Leaves, Squares, and Top Noise.

Custom fills

You can edit custom fills by changing their spacing, angle, width and other attributes. You can also change the color of the Bricks, Circles, Hatch, and Squares fills. A custom fill prints at one size on PostScript output devices and does not scale with the object it fills.

To apply a custom fill attribute to a selected fill in the Object panel:

1 Select Custom from the fill type pop-up menu.

2 Select one of the following patterns from the custom fill pop-up menu and then specify its options:

Black & White Noise applies an opaque, black-and-white fill. It has no options.

Brick simulates a brick fill. Specify a Mortar color using the color box; brick width and height values in the document's unit of measure; and an angle to rotate the fill clockwise (positive value) or counterclockwise (negative value).

Circles applies a fill of circles. Specify a radius to change the size of circles, and to set the spacing between circles as measured from radius point to radius point. To avoid overlapping circles, set the spacing to more than twice the radius. Enter an angle to rotate the fill clockwise (positive value) or counterclockwise (negative value).

Hatch draws lines to simulate pen hatching. Specify a color. Enter Angle 1 and Angle 2 values to rotate the first and second set of parallel lines clockwise (positive value) or counterclockwise (negative value). Specify spacing between hatch lines and their width.

Noise applies a Whiteness value as a percentage from 0% (black) to 100% (white). Larger Whiteness values result in a noisier fill.

Random Grass and **Random Leaves** apply a grass or leaf pattern fill. Specify from 1 to 32,000 blades of grass or leaves.

Squares applies a fill of squares. Set Side Length to change the size of squares in the fill. Set the spacing between squares as measured from center to center. To avoid overlapping squares, set Spacing to more than the side length. Enter an angle to rotate the fill clockwise (positive value) or counterclockwise (negative value), and a stroke width.

Tiger Teeth applies a tooth-like pattern. Specify a color and background fill color using the color boxes. Set the number of teeth, from 1 to 700, to change the fill's density. Enter an Angle value to rotate the fill clockwise (positive value) or counterclockwise (negative value).

Top Noise applies a gray noise value as a percentage from 0% (black) to 100% (white).

Using gradient fill attributes

Gradients apply color in smooth transitions from one color to the next. You can specify two or more colors to define a gradient ramp. In each of the six gradient types, the gradient starts at the start point and extends to one or more gradient handles. You can drag the start point and handles to affect the placement, length, and angle of gradients. Gradient attributes appear in the Object panel when a gradient fill is selected.

Gradient behaviors affect how a gradient fills an object. In Normal behavior, the position of the end points determines the length of the gradient. In Repeat behavior, the gradient repeats a specified number of times. In Reflect behavior, the colors transition from one end of the gradient ramp and then back, going through one transition for each Repeat count. In Auto Size behavior, the length of the gradient is set to the exact width and height of the object.

Note: When Auto Size is selected, the gradient end point handles do not appear for a selected object. For linear and logarithmic gradients, neither the start point nor end point handles appear. Use the Object panel to adjust gradient attributes when Auto Size is selected.

Fill type
Gradient type
Repeat count
Behavior type
Gradient ramp

Note: Changing the fill from Gradient to Basic fills the object with the color displayed in the left color box.

You can set preferences to control the number of colors displayed in gradient fills to speed redrawing of the screen.

To set display preferences for gradient fills:

1 Display redraw preferences by doing one of the following:

• In Windows, press Control+U, then click the Redraw tab.

• On the Macintosh, press Command+U, then click the Redraw category.

2 Do one of the following.

• Select the Better (but Slower) Display option to display as many colors as possible for gradient fills.

• Deselect the Better (but Slower) Display option to limit the number of colors displayed and increase drawing speed.

3 Click OK.

To apply a gradient fill to a selected object by dragging a color swatch, do one of the following:

• To apply a color as a linear gradient, hold down Control as you drag a color swatch onto an object. The location at which you drop the color determines the angle of the gradient.

• To apply a color as a radial gradient, hold down Alt (Windows) or Option (Macintosh) as you drag a color swatch onto an object. The location at which you drop the color determines the gradient's center.

• To apply a color as a contour gradient, hold down Alt+Control (Windows) or Command+Option (Macintosh) as you drag a color swatch onto an object. The location at which you drop the color determines the gradient's center.

Using Linear or Logarithmic gradients

Linear gradients apply color in a straight, graduated transition using equal increments. Logarithmic gradients apply color in a straight, graduated transition using increasingly wide bands. Both gradient types have two handles: a start point and an end point.

Linear (top) and Logarithmic (bottom) gradients

To apply a linear or logarithmic gradient to a selected fill in the Object panel:

1 Select Gradient from the fill type pop-up menu.

2 Select Linear or Logarithmic from the gradient type pop-up-menu.

3 Click the color swatch at either end of the color ramp, and then select a color from the pop-up color menu. The left swatch sets the color for the start point and the right swatch sets the color for the end point.

4 To adjust the gradient, do any of the following:

• To reposition the gradient, drag the start point.

• To adjust the length or angle of the gradient, drag the end point.

• To add a color, drag a color swatch to any position on the color ramp.

• To reposition a color within the gradient, drag its swatch to a new position. If you drag an end swatch, a new one appears in its place.

• To copy an existing color on the ramp to a new location, hold down Alt (Windows) or Command (Macintosh) and drag.

• To remove a color from the color ramp, drag its swatch off the color ramp.

Using Radial or Rectangle gradients

Radial gradients apply color in concentric elliptical increments, regardless of fill shape. Rectangle gradients apply color in concentric rectangular increments, regardless of fill shape. Both gradient types have three handles: a start point and two end points.

To apply a radial or rectangle gradient to a selected fill in the Object panel:

1 Select Gradient from the fill type pop-up menu.

2 Select Radial or Rectangle from the gradient type pop-up-menu.

3 Click the color swatch at either end of the color ramp, and then select a color from the pop-up color menu. The left swatch sets the color for the start point and the right swatch sets the color for the end point or end points.

4 To adjust the gradient, do any of the following:

• To reposition the gradient, drag the start point.

> **Note:** To simultaneously set a radial fill's center position and center color, hold down Alt (Windows) or Option (Macintosh) as you drag a color swatch onto the object.

• To adjust the width, height, or angle of the gradient, drag the end point or end points.

• To add a color, drag a color swatch onto the color ramp.

• To reposition a color within the gradient, drag its swatch to a new position. If you drag an end swatch, a new one appears in its place.

• To copy an existing color on the ramp to a new location, hold down Alt (Windows) or Command (Macintosh) and drag.

• To remove a color from the color ramp, drag its swatch off the color ramp.

Using Contour gradients

Contour gradients apply color based on the shape of the fill. Contour gradients have two handles: a start point and an end point.

To apply a contour gradient to a selected fill in the Object panel:

1 Select Gradient from the fill type pop-up menu.

2 Select Contour from the gradient type pop-up-menu.

3 Click the color swatch at either end of the gradient ramp, and then select a color from the pop-up color menu. The left swatch sets the color for the start point and the right swatch sets the color for the end point.

4 To adjust the gradient, do any of the following:

• To reposition the gradient, drag the start point.

• To adjust the length of the gradient, drag the end point.

• To add a color, drag a color swatch onto the color ramp.

• To reposition a color within the gradient, drag its swatch to a new position. If you drag an end swatch, a new one appears in its place.

• To copy an existing color on the ramp to a new location, hold down Alt (Windows) or Command (Macintosh) and drag.

• To remove a color from the color ramp, drag its swatch off the color ramp.

Using Cone gradients

Cone gradients apply color in a 360-degree graduated sweep. Cone gradients have two handles: a center point and an angle point.

To apply a cone gradient to a selected fill in the Object panel:

1 Select Gradient from the fill type pop-up menu.

2 Select Cone from the gradient type pop-up-menu.

3 Click the color swatch at either end of the gradient ramp, and then select a color from the pop-up color menu. The left swatch sets the color for the start point and the right swatch sets the color for the end point.

4 To adjust the gradient, do any of the following:

- To reposition the gradient, drag the start point.

- To adjust the start angle of the gradient, drag the end point.

- To add a color, drag a color swatch onto the color ramp.

- To reposition a color within the gradient, drag its swatch to a new position. If you drag an end swatch, a new one appears in its place.

- To copy an existing color on the ramp to a new location, hold down Alt (Windows) or Command (Macintosh) and drag.

- To remove a color from the color ramp, drag its swatch off the color ramp.

Using lens fill attributes

A lens fill attribute transforms a fill into any of six special-effect lenses that modify the appearance of objects underneath the lens by inverting colors or by changing the transparency, color, lightness, darkness, or magnification of the object.

Note: Repeatedly using lens fills, especially on top of each other, can add numerous objects to the document, increase file size, and cause printing problems.

You cannot apply a lens fill to EPS files, to clipping paths, or to text unless the text has been converted to paths. A lens-filled object can be pasted inside another object.

To apply a lens fill attribute to a selected fill in the Object panel:

1 Select Lens from the fill type pop-up menu.

2 Select a lens fill:

Transparency makes objects appear partially or completely transparent.

Magnify enlarges objects under the lens.

Invert reverses colors to their complementary CMYK colors (their opposites on a color wheel) for a negative effect.

Invert lens

Lighten lightens the colors of the objects beneath the lens.

Darken darkens the colors of the objects beneath the lens.

Monochrome displays colors underneath as monochrome tints of the selected color. The amount of lightness in the original color determines the tint value.

Monochrome lens

Lens fill options vary according to the type of lens.

3 For Transparency and Monochrome lenses, select a color using the color box or pop-up menu (see Chapter 5, "Working with Color," on page 147).

Spot colors under a lens are converted to process colors for output. Use the Eyedropper tool to capture new colors created by a lens fill effect.

4 For a Magnify lens, enter a value from 1 to 20 or drag the slider to set the magnification of objects under the lens.

5 For Transparency, Lighten, and Darken lenses, adjust the effect by entering a value or dragging the slider, as follows:

- For a Transparency fill, values range from 0 (completely transparent) to 100 (completely opaque).

Transparency fill applied to a circle

- For a Lighten fill, a 0 value has no effect and 100 fills the path of the lens completely white.

Lighten fill simulating a ray of light

- For a Darken fill, a 0 value has no effect and 100 fills the path of the lens completely black.

Darken fill

6 Select Centerpoint to display a handle at the center of a selected lens.

To reposition the center point anywhere in a document, drag the center point using the Pointer tool. Shift-click the center point to return it to the center of the lens. The center point disappears when you deselect the object.

7 Select Objects Only to apply the lens effect to objects, not empty areas, under the lens.

Invert fill with Objects Only selected (left) and deselected (right)

8 Select Snapshot to capture the current contents of the lens, so that the lens can be moved anywhere in the Document without changing the lens contents.

Magnify fill at 3x with Snapshot selected to retain the fill contents

Note: Choosing a new lens type automatically deselects the Centerpoint, Objects Only, and Snapshot options.

Using pattern fill attributes

You can choose from 64 predefined pattern fill attributes. You can also edit each pattern. The lower portion of the Object panel displays an editable version of the pattern on the left, and a preview to the right updates as you edit the pattern. A pattern fill prints at one size on PostScript output devices and does not scale with the object it fills.

Note: Pattern stroke attributes print based on the resolution of the printer, and therefore look best when printed at 300 dpi or lower.

For an example of the patterns available, see "To apply a Custom stroke attribute to a selected stroke in the Object panel:" on page 175.

To apply a pattern fill attribute to a selected fill in the Object panel:

1 Select Pattern from the fill type pop-up menu.

2 Select a color for the fill.

3 Click a pattern in the lower right corner of the panel. Use the slider to scroll through the available patterns.

To edit a pattern fill in the Object panel:

1 Select a pattern, using the slider at the bottom of the panel to scroll through the available patterns.

The selected pattern appears in the preview panes.

2 Click one pixel at a time or drag in the left preview. Clicking a pixel toggles between black (opaque, in the selected color) and white (transparent).

3 Select Clear to remove a pattern from the preview pane.

4 Click Invert to reverse pixel color—from color to white or from white to color.

Using PostScript fill attributes

PostScript applies a fill with a unique pattern and shape that you create in the PostScript Code text box. FreeHand sends the PostScript code to the PostScript interpreter in your printer's Raster Image Processor (RIP). If your code is incorrect, you will receive a PostScript error message when printing.

PostScript fills do not appear onscreen, but appear when you print to a PostScript printer.

Note: PostScript programming is beyond the scope of this document. For more information, refer to a PostScript language manual.

To apply a PostScript fill attribute to a selected fill in the Object panel:

1 In the Object panel, select PostScript from the fill type pop-up menu.

2 Enter up to 255 characters of code in the PostScript Code text box. You can type the code directly or paste it from another source.

Separate commands with a space, and allow them to wrap on their own.

Object panel with PostScript fill code

3 Press Enter (Windows) or Return (Macintosh) to apply the fill.

Using textured fill attributes

FreeHand includes several textured fill attributes. You cannot edit attributes.

Textured fill attributes

FreeHand textured fills are PostScript textures that do not appear onscreen, but will appear when printed to a PostScript printer. A textured fill prints at one size on PostScript output devices and does not scale with the object it fills.

To apply a textured fill attribute to a selected fill in the Object panel:

1 Select Textured from the fill type pop-up menu.

2 Select a texture from the texture pop-up menu.

3 Select a color from the color pop-up menu.

Using tiled fill attributes

Tiled fill attributes are patterns based on a repeating object, or tile, that you create from graphics or text pasted into the Object panel. You cannot create a tiled fill from an EPS image, bitmap image, another tiled fill, or a lens-filled object.

To create and apply a tiled fill attribute to a selected fill in the Object panel:

1 Copy the graphics or text you want to use as a tile.

2 Select the object you want to fill.

3 In the Object panel, do one of the following:

• Select the fill to which you want to add a tiled attribute.

• Click the Add Fill button.

4 Select Tiled from the fill type pop-up menu.

5 Click Paste In to paste the tile in the preview pane.

6 For Angle, enter a value or drag the dial to set the tile's orientation.

7 In the scale text boxes, enter x and y percentage values to resize the tile.

8 In the offset text boxes, enter values to shift the tile's position within the object being filled:

• Positive x values move the fill to the right; negative values move it left.

• Positive y values move the fill up; negative values move it down.

To copy a tile attribute from a selected fill in the Object panel:

1 Select the fill that contains the tile attribute you want to copy.

2 In the Object panel, the tile appears in the preview pane. Click Copy Out to copy the tile object to the Clipboard.

You can now copy the tile object into your document or use it to create a tiled fill for another object.

To shift a tiled fill attribute's position within a selected fill:

1 Select Window > Transform to display the Transform panel, and deselect the Fills option.

2 Drag the object with the Pointer tool. The object moves, but the tiled fill stays in place.

3 In the Transform panel, select Fills. When you move the object now, the tiled fill moves with the object.

There are two ways to easily create special effects in Macromedia FreeHand MX. Live special effects, available in the Object panel, change the appearance of an object while keeping the object itself intact. Other commands and tools in FreeHand let you create special effects by manipulating objects in ways that change their paths, fills, or other properties.

Adding live special effects to objects

FreeHand MX objects can have multiple properties, such as strokes, fills, and live special effects. (For more information on strokes and fills, see Chapter 6, "Using Strokes and Fills," on page 165.) Live effects are properties of an object, and only affect the appearance of the object to which they are applied. For example, the transformation tools can modify the actual width or height of an object, whereas the Transform effect can make the object appear to be wider or taller than it really is.

Use the Object panel to add properties to objects and to modify the attributes of the properties you add. The upper portion of the Object panel displays a Properties list for the current selection in the Document window. The bottom portion of the Object panel displays attributes for the current selection in the Properties list.

The Properties list is hierarchical, and the order of properties in the list affects the appearance of the object. You can change an object's appearance by dragging to rearrange items in the list.

To add a special effect to an object, fill, or stroke:

- Select the object in the Document window, or select the fill or stroke in the Object panel's Properties list.

- Click the Add Effect button in the Object panel and select the effect you want from the pop-up menu.

To delete a special effect from a selected object:

1 Select the special effect in the Object panel.

2 Click the Remove Item button in the Object panel.

To move a special effect up or down in an object's hierarchical Properties list:

Drag the special effect up or down within the Properties list in the Object panel.

Applying live vector effects

Live vector effects work similarly to some of the other object manipulation capabilities of FreeHand, except that they act as properties of the object they are applied to, and do not modify the object itself. Like the objects they affect, live vector effects produce vector graphics. Therefore, vector effects are independent of display or printer resolution, and scale smoothly to any size.

Using a Bend effect attribute

The Bend effect distorts a shape by pulling the points on the perimeter toward or away from the center point. You can adjust the amount of distortion and move the center point to alter the appearance of the effect.

Positive (left) and negative (right) Bend effects

To apply a Bend attribute to a selected effect in the Object panel:

1 Select Bend in the effect type pop-up menu.

2 Modify the attributes of the effect:

- For Size, enter a value to determine how far from the center point to move the points on the shape. A negative value moves the points toward the center. A positive value moves the points away from the center.

- Edit the x and y coordinates or drag the center point to relocate it.

Using a Duet effect attribute

The Duet effect creates one or more clones of a shape and combines the clones with the original to create a single complex shape. You can define the number of clones to create and determine whether the clones are to be rotated or reflected from the original shape. You can also define the center point around which the clones are rotated or reflected.

Reflected effect (left), original object (center), and Rotated effect (right)

To apply a Duet attribute to a selected effect in the Object panel:

1 Select Duet in the effect type pop-up menu.

2 Modify the attributes of the effect:

• Select Reflect to create a single mirror image of the original.

• Select Rotate to create duplicates rotated around a center point.

• Drag the center point or edit the x and y coordinates to change the angle and orientation of cloned shapes.

• For Copies, enter a number to set the number of clones to rotate.

• Select Joined to automatically connect the original shape with its clones.

• Select Closed to close either the cloned shapes (if Joined is deselected) or the entire new path (if Joined is selected).

• Select Even/Odd fill to make overlapping areas of a fill alternate between filled and transparent.

Using an Expand Path effect attribute

The Expand Path effect widens a path and creates an outline of the resulting shape. For example, a path with only two points becomes a closed, rectangular shape after you expand it. Expanding a path lets you add fills within the path.

Note: The Expand Path effect changes only the appearance of the path, unlike the Expand Path Xtra, which alters the path itself.

Path expanded to outside only (left) and both directions (right)

To apply an Expand Path attribute to a selected effect in the Object panel:

1 Select Expand Path in the effect type pop-up menu.

2 Modify the attributes of the effect:

• For Direction, select a setting to expand the path toward the inside only, the outside only, or both directions.

• For Width, enter a value from 0 to 50 points.

• For Cap, set the style for an open path end: Butt, which is flush with the path's end; Round; or Square, which extends beyond the path by half the stroke width.

• For Join, select an option to define how two path segments meet: Miter, Round, or Beveled. To change the corners in an open or closed path, select a path and choose another join option.

• Enter a miter limit from 1 to 57 to avoid beveling a Miter join.

Using a Ragged effect attribute

The Ragged effect randomly adds new points to alter a shape, giving it a jagged or smooth appearance.

Ragged effect with jagged (left) and smooth (right) appearance

To apply a Ragged attribute to a selected effect in the Object panel:

1 Select Ragged in the effect type pop-up menu.

2 Modify the attributes of the effect:

- For Size, enter a value to determine the maximum distance added points can vary from the original shape.

- For Frequency, enter a value to determine how many new points are added.

- For Copies, enter a value to determine how many copies of the original shape are added.

- Select Rough to give the effect a jagged appearance.

- Select Smooth to give the effect a smooth appearance.

- Select Uniform to make the Ragged effect uniform instead of random.

Using a Sketch effect attribute

The Sketch attribute simulates a pencil-sketched look by introducing random imperfections into a shape. You can control the amount of randomization, the number of pencil strokes to use in simulating the sketched appearance, and whether or not the added pencil strokes are connected.

Sketch effect using open strokes (left) and closed strokes (right)

To apply a Sketch attribute to a selected effect in the Object panel:

1 Select Sketch in the effect type pop-up menu.

2 Modify the attributes of the effect:

- For Amount, enter a value to determine how much imperfection to apply. Higher numbers produce more variance from the original shape.

- For Copies, enter the number of simulated strokes to apply.

- Select Closed to connect the ends of the simulated strokes.

Using a Transform effect attribute

The Transform effect performs many of the same operations as the transformation tools, but works as an attribute of an object or its properties.

Note: The Transform effect changes only the appearance of the object, unlike the transformation tools, which alter the path itself. For more information on the transformation tools, see "Using the transformation tools" on page 137.

To apply a Transform attribute to a selected effect in the Object panel:

1 Select Transform in the effect type pop-up menu.

2 Modify the attributes of the effect:

- For Scale options, enter percentages for scaling. Select Uniform to scale proportionally.

- For Skew horizontal and vertical options, enter positive values to skew up or to the right, respectively, and negative values to skew down or to the left, respectively.

- For Rotate, enter a positive value to rotate counterclockwise around the center point, and a negative value to rotate counterclockwise around the center point.

- For Move X-axis and Y-axis, enter positive values to move to the right and up, and negative values to move to the left and down, respectively.

- For Center X-axis and Y-axis, enter positive values to move the center point to the right and up, and negative values to move to the left and down, respectively.

- Enter a value in the Copies box. A value of 1 transforms only the original selection. Higher values create the specified number of copies, each of which is progressively affected by the other transform options.

Applying live raster effects

Live raster effects work similarly to some of the image manipulation tools found in photo editing software such as Macromedia Fireworks. Raster effects act as properties of the object they are applied to, and do not modify the object itself. Unlike the objects they affect, live raster effects produce raster, or bitmap, graphics. Therefore, raster effects look best when rendered at the correct resolution for the computer monitor or output device on which they are intended to be displayed.

Note: If you use raster effects with spot colors, the colors are converted to RGB for display on the screen, and then converted to CMYK process color for printing. PostScript fills do not print correctly when combined with raster effects.

To set the raster effects resolution for a document:

1 Select File > Document Settings > Raster Effects Settings.

2 Enter a value for Resolution corresponding to the resolution of the output or display device for which your drawing is intended.

> **Note:** To speed rendering of raster effects while drawing for high-resolution output devices, set the resolution to a low number while drawing, then increase the setting to the resolution of the output device when you complete the drawing.

3 Select Optimal CMYK Rendering to render raster effects without using the current color management settings.

> **Note:** Use the Optimal CMYK Rendering setting only when *all* of the colors in your document are CMYK.

To set the raster effects resolution for an object:

1 Select the object in the drawing area.

2 If necessary, select Window > Object to display the Object panel.

3 Click the Object panel Options menu control and select Raster Effect Settings.

4 Deselect the Use Document Raster Effects Resolution option.

5 Enter a value for Resolution corresponding to the resolution of the output or display device for which your drawing is intended.

Using Bevel and Emboss effect attributes

Applying a beveled edge produces a raised look. You can create an inner bevel or an outer bevel. You can use emboss effects to make an image, object, or text appear inset into or raised from the canvas.

Inner bevel (left), original object (center) and raised emboss (right)

Use the object panel to adjust the appearance of bevelled or embossed effects.

To apply a bevel attribute to a selected effect in the Object panel:

1 Select Bevel and Emboss > Outer Bevel in the effect type pop-up menu.

2 Modify the attributes of the effect:

- For outer bevels, select a color for the bevel from the pop-up color palette.

- For width, enter a value to define the width of the bevel.

- For contrast, enter a value to define the brightness and darkness of the highlights and shadows in the bevel.

- For softness, enter a value to affect the smoothness of the bevel without affecting its width.

- For angle, enter a value or use the pop-up dial to set the angle of the light source.

- Select an edge shape from the Edge Shape pop-up menu.

- Select a button highlighting effect from the Button Preset pop-up menu.

To apply an emboss attribute to a selected effect in the Object panel:

1 Select Bevel and Emboss > Inset Emboss or Emboss > Raised Emboss in the effect type pop-up menu.

2 Modify the attributes of the effect:

- For width, enter a value to define the depth of the emboss.

- For contrast, enter a value to define the brightness and darkness of the highlights and shadows in the emboss.

- For softness, enter a value to affect the smoothness of the emboss without affecting its width.

- For angle, enter a value or use the pop-up dial to set the angle of the light source.

Using a Blur effect attribute

Blur effects soften the details of an image. A Basic blur produces an unfocused look. A Gaussian blur produces a hazy appearance, like viewing an image through semi-opaque glass.

Blur (left), original image, and Gaussian Blur (right)

To apply a blur attribute to a selected effect in the Object panel:

1 Select Blur > Basic or Blur > Gaussian Blur in the effect type pop-up menu.

2 For Radius, enter a value to determine the amount of blurring.

Using Shadow and Glow effect attributes

Shadow effects are useful for simulating drop shadows that would occur if a shape were a physical object raised above the drawing surface, or if it were a hole, cut out from the drawing surface. Glow effects produce a halo inside or outside the shape.

Left to right: Drop Shadow, Inner Shadow, Glow, and Inner Glow

To apply a shadow or glow attribute to a selected effect in the Object panel:

1 Select Shadow and Glow > Drop Shadow in the effect type pop-up menu. The effect attributes appear at the bottom of the Object panel.

2 Modify the attributes of the effect:

- Select a color for the shadow or glow from the pop-up color palette.

- For offset, enter a value to determine how far the shadow or glow appears from the original shape.

  Note: The direction in which the shadow or glow moves is determined by the angle setting.

- For opacity, enter a value to determine the level of transparency of the shadow or glow. Lower numbers are more transparent, and higher numbers are more opaque.

- For softness, enter a value to affect the smoothness of the shadow or glow without affecting its width.

- For angle, enter a value or use the pop-up dial to set the angle of the light source.

Using a Sharpen effect attribute

Sharpen effects sharpen an image by adjusting the contrast of adjacent pixels in the image. A Basic sharpen effect sharpens an entire shape. An Unsharp Mask effect sharpens an image by adjusting the contrast of the edges in the image.

Basic sharpen effect (left), original image (center) and Unsharp Mask effect (right)

To apply a sharpen attribute to a selected effect in the Object panel:

1 Select Sharpen > Basic or Sharpen > Unsharp Mask in the effect type pop-up menu.

2 Modify the attributes of the effect:

- For Amount, enter a value to determine the strength of the effect.

- For Pixel Radius (Unsharp Mask only), enter a value to determine how far from each pixel to evaluate when sharpening. Higher values produce a more pronounced effect.

- For Threshold (Unsharp Mask only), enter a value to determine saturation of pixels to be sharpened. A setting of 0 sharpens all pixels in the image, and a setting of 255 sharpens very few pixels.

Using a Transparency effect attribute

Transparency effects allow a fill or stroke (or parts of a fill or stoke) to appear clear or semi-opaque. Basic Transparency allows an entire shape to appear at the same level of transparency. Feather transparency allows the edges of a shape to fade out. Gradient Mask transparency defines transparency using any of the gradients available in FreeHand, where the darkness of the colors in the gradient determine the degree of transparency. White produces 100% transparency, and black produces 100% opacity. Any colors on the gradient ramp are converted to their grayscale equivalents.

Left to right: Basic transparency, Feather transparency, and Gradient Mask transparency

To apply a Basic Transparency attribute to a selected effect in the Object panel:

1 Select Transparency > Basic Transparency in the effect type pop-up menu.

2 Enter a value to determine the degree of transparency. Higher values produce greater transparency.

To apply a Feather transparency attribute to a selected effect in the Object panel:

1 Select Transparency > Feather in the effect type pop-up menu.

2 Modify the attributes of the effect:

• For Radius, enter a value to determine how far inside the perimeter of the shape to feather.

• For Softness, enter a value to define the edges of the feather without affecting its width. High settings produce a softer edge, and low settings produce a more crisp effect.

To apply a Gradient Mask transparency attribute to a selected effect in the Object panel:

1 Select Transparency > Gradient Mask in the effect type pop-up menu.

2 Modify the attributes of the gradient in the same way you edit gradient fills. For more information, see "Using gradient fill attributes" on page 179.

Extruding objects

The Extrude tool lets you use FreeHand objects to simulate three-dimensional (3D) objects. Extruded objects have the appearance of 3D objects, but you can still edit the original 2D object you used to create the extrusion.

To extrude an object:

1 In the Tools panel, select the Extrude tool from its pop-up menu.

2 Drag the object you want to extrude to set its vanishing point.

To remove extrusion from a selected object:

Select Modify > Extrude > Remove.

The object is converted to its original state.

To convert a selected extruded object to a group of "flat" objects:

Select Modify > Extrude > Release.

To reset a selected extruded object to its original settings:

Select Modify > Extrude > Reset.

To share a single vanishing point among multiple extruded objects:

1 In the Tools panel, select the Pointer tool.

2 Select two or more extruded objects.

3 Select Modify > Extrude > Share Vanishing Points.

4 Click anywhere in the drawing area to set the vanishing point.

Note: You can edit the vanishing point of any of the extruded objects without affecting the other objects that share a vanishing point.

Editing an extruded object in the workspace

To edit the extrusion effects of an extruded object, you use the Extrude tool. The Extrude tool offers two editing modes. One mode lets you edit the position, depth, and vanishing point, much like the process of creating an extruded object. The rotation mode of the Extrude tool lets you rotate the extruded object in 3D space. You can edit any of these attributes using the Object panel.

Note: Although you can also manipulate an extruded object using the Pointer tool and basic transformation techniques such as skewing and rotating, doing so permanently "locks" the extrusion properties. The resulting object retains its extrusion properties, but those properties can no longer be edited.

To edit the position, depth, or vanishing point of an extruded object:

1 In the Tools panel, select the Extrude tool from its pop-up menu.

2 Select the extruded object to display the extrusion controls.

Vanishing point

Depth control

Z axis

Object center point

3 Do any of the following:

• Drag the object's center point to reposition the object, leaving the vanishing point in place.

• Drag the depth control to adjust the depth of the extrusion.

• Drag the vanishing point to reposition it within the document.

To rotate an extruded object in 3D space:

1 In the Tools panel, select the Extrude tool from its pop-up menu.

2 Double-click the extruded object to display the rotation circle.

Rotation circle

Z-axis marker

3 Do one of the following:

• Drag inside the rotation circle to rotate the object on its x or y axis.

• Drag outside the rotation circle to rotate the object on its z axis, relative to the active page.

4 To finish editing in 3D space, do one of the following:

• In the Tools panel, click the Pointer tool.

• Press Tab.

• Double-click the object.

Editing an extruded object using the Object panel

The Object panel lets you precisely edit the length, vanishing point, position, and rotation of an extrusion.

Note: Although you can also manipulate an extruded object using the Pointer tool and basic transformation techniques such as skewing and rotating, doing so permanently "locks" the extrusion properties. The resulting object retains its extrusion properties, but those properties can no longer be edited.

To edit an extrusion using the Object panel:

1 Using the Pointer tool or Extrude tool, select the extruded object.

2 Click the Extrude button in the Object panel.

3 Modify the attributes of the extrusion:

- For length, enter a value in points to set the length of the extrusion. The maximum length is 32,000.

- For Vanishing Point, enter the x and y coordinates, relative to the active page.

- For Position, enter the x, y, and z coordinates, relative to the active page.

- For Rotation, enter the x, y, and z rotation angles, relative to the 3D center of the extruded object.

Editing the surface of an extruded object

You can use the Object panel to alter the surface features of an extruded object. Surface features include how the surface is rendered, the amount of detail used to render it, the lightness of the extruded object, and light sources for shading.

To edit the surface features of an extrusion:

1 Select the extruded object.

2 Click the Surface button in the Object panel.

3 Select a surface type from the Surface pop-up menu:

Flat produces extruded sides using the same Basic fill color as the extruded object.

Shaded produces a realistic, smoothly shaded extrusion.

Wireframe produces an extrusion with no fills.

Mesh produces extruded sides using polygons that have strokes but no fills.

Hidden Mesh produces extruded sides using polygons that have strokes and fills.

4 For Steps, enter a value to determine the amount of detail used to render curvature around the the surface of the extrusion. Higher values produce smoother shading, but take longer to render and print.

Tip: To speed redrawing of an extruded object as you draw, set Steps to a low number while drawing, then increase the Steps setting when you finish your drawing.

5 For Ambient, enter a value to determine the overall lightness or darkness of the extruded object. Lower numbers produce a darker object, and higher numbers produce a lighter object.

6 For Light 1 and Light 2 Direction, select a lighting direction from the pop-up menu.

7 For Light 1 and Light 2 Intensity, enter a value to determine the light source intensity.

Note: The light source options are available only when the Shaded surface type is selected.

Editing the profile of an extruded object

By default, extrusions extend in straight lines toward the vanishing point. The Object panel lets you customize extrusions by altering their angle, by twisting them as they approach the vanishing point, or by altering the shape of the extrusion's profile.

The Profile Preview box in the Object panel lets you paste in an open path to use as the profile shape of an extruded object. You can select any open path as an extrusion profile, but paths that do not turn back on themselves produce the best extrusions.

Profile Preview box

To edit the profile shape of an extrusion:

1   Select an open path in the Document window.

2   Select Edit > Copy.

3   Select the extruded object.

4   Click the Profile button in the Object panel.

5   Select Bevel or Static in the extrude type pop-up menu.

6   Click the Paste In button to use the copied path as the extrusion profile shape.

7   The new profile shape appears in the Profile Preview box.

To edit the profile attributes of an extrusion:

1 Select the extruded object.

2 Click the Profile button in the Object panel.

3 Select a profile type from the Profile pop-up menu:

None produces a default extrusion.

Bevel produces an extrusion by sweeping the path profile around the perimeter of the object while matching the angles of the object's perimeter.

Static produces an extrusion by sweeping the path profile around the perimeter of the object while maintaining the original angle of the path profile.

4 If you selected Static in step 3, enter a value in the Angle box to determine the angle at which the profile path is applied to the extrusion.

5 For Steps, enter a value to determine the amount of detail used to render the surface from front to back. Higher values produce smoother shading, but take longer to render and print.

6 For Twist, enter a value, in degrees of clockwise rotation, to determine how far the rear face of the extrusion should rotate.

Working with blends

You can create a blend from two or more paths that have the same fill and stroke type. Blending creates a series of intermediate objects between the original paths. Beginning with the bottom object in the stacking order, each intermediate object's shape, stroke, and fill becomes closer to that of the object at the top of the stacking order.

FreeHand creates live blends that you can adjust dynamically. If you ungroup a blend, FreeHand converts the live blend objects to regular, editable objects.

You can modify a blend by using the Blend tool, by using the Object panel, or by modifying a subselection of the blend group. FreeHand automatically regenerates the blend.

You can create a blend between selected points on the original objects, creating different results than an object-to-object blend. The selected points determine the shape of the intermediate blend objects. Path direction can also affect blending.

Blends between spot colors result in intermediate steps using only tints of those spot colors and will print on two separation plates. When printing a spot-to-process blend, the spot color is set to overprint the process color. Steps in spot-to-spot and spot-to-process blends are set to process colors if the blend is ungrouped. This also occurs if incompatible colors or fills are chosen, or if the blends are exported to earlier versions of FreeHand or to applications such as Adobe Illustrator, which may not support spot colors in blends. For more information on colors, see Chapter 5, "Working with Color," on page 147.

You can blend basic fills and gradient fills interchangeably. Other types of fills can be blended only with their same fill type. You cannot blend bitmap images.

Using the Blend tool

The Blend tool lets you easily create and modify blends by dragging the blend "rubber band" from one object to another. Onscreen feedback lets you preview the outline of a blend as you drag with the Blend tool.

You can also select the start and end blend points to affect how the blend is drawn. Blend points appear as large circles. Moving either blend point (large circles) affects how a blend draws.

To create a blend from two objects using the Blend tool:

1 In the Tools panel, select the Blend tool from its pop-up menu.

2 Drag from the first blend object to the second blend object.

To add additional objects to a blend using the Blend tool:

1 In the Tools panel, select the Blend tool from its pop-up menu.

2 Drag from an existing blend object to the object you want to add.

To modify the start or end blend points of a blend:

1 In the Tools panel, select the Blend tool from its pop-up menu.

2 Drag the a blend point from one location on the blend object to another. As you drag, the blend is displayed in an onscreen preview to show the effect of moving the blend point.

Creating and modifying blends manually

You can create complex blends with precision using the tools and menu commands for blends.

To create a blend from two or more objects manually:

1 Check that the objects you want to blend are in the correct stacking order.

2 Select the objects.

3 Do one of the following:

- Select Window > Toolbars > Xtra Operations and click the Blend button on the Xtra Operations toolbar.

- Select Modify > Combine > Blend.

- Select Xtras > Create > Blend.

To blend objects from point to point:

1 Select objects and subselect points within each object.

2 Select Modify > Combine > Blend.

Modifying blends using the Object panel

You can adjust the number of steps and other options in a blend group using the Object panel.

To modify a blend:

1 Select the blend.

2 Select Window > Object to display the Object panel.

3 In the Object panel, enter a value in the Steps text box to change the number of intermediate objects; the more steps there are, the smoother the blend.

4 Enter a percentage value in the Range % text box to adjust where the intermediate objects begin and end. The First text box controls how closely the steps are placed to the bottom path, and the Last text box controls how closely the steps are placed to the top path.

To adjust a blend:

1 Select one of the original objects using the Subselect tool.

2 Do one of the following:

- Change the object's shape.

- Change the object's path direction.

- Change the object's stroke or fill color.

Joining a blend to a path

You can join a blend to a path to control the shape and orientation of the blend. When you join a blend to a path, the center point of the first object in the blend is placed over the path's start point, and the center point of the last object is placed over the end point. The rest of the blend is distributed along the path.

By default, the blend is rotated on the path so that the orientation of each blend object changes to follow the path. You can subselect the path and reverse its direction to make the blend flow in the opposite direction.

To join a blend to a path using the Blend tool:

Alt-drag (Windows) or Option-drag (Macintosh) the blend to the path.

To join a selected blend to a selected path manually:

1 Select Modify > Combine > Join Blend to Path.

2 To modify the way in which a blend fits its joined path, select Show Path in the Object panel to show the path.

3 To rotate the blend around the path, select Rotate on Path in the Object panel. Deselect the option to position the blend parallel to the path.

To remove a selected blend from a path, do one of the following:

- Select Modify > Split to create a separate blend and path.

- Select Modify > Ungroup to separate the path and the original objects. Intermediate objects remain grouped.

Blending composite paths and groups

You can create blends between composite paths and between groups. Groups must contain only simple paths and cannot contain composite paths, images, clipping paths, or other groups. Objects in both groups must have the same type of stroke and fill.

Many factors affect how composite groups and paths blend. Experiment with different settings to achieve the best results.

To blend selected composite paths or groups:

1 Select Modify > Combine > Blend.

2 Select Window > Object to display the Object panel.

3 In the Object panel, select a blend type:

Normal gives good results for most blends.

Horizontal and Vertical give optimal results between composite paths with nonoverlapping subpaths by dividing a segmented path into horizontal or vertical portions.

4 In the Object panel, select a blend order:

Positional blends the objects based on their position.

Stacking blends the objects based on their stacking orders.

Adding points to objects or paths

You can add points to an object or path to increase its complexity for applying other special effects. Added points appear on the path without distorting the shape of the path.

To add points to a selected object or path:

1 Select Window > Toolbars > Xtra Operations.

2 Do one of the following to add a point between every pair of points on the path:

- Click the Add Points button on the Xtra Operations toolbar.

- Select Window > Xtras > Distort > Add Points.

Roughening objects or paths

You can alter a path or object by roughening it with the Roughen tool. A roughened path appears jagged or wavy. You can also use the Ragged effect attribute to create a hand-drawn appearance for an object without permanently altering the object. For more information, see "Using a Ragged effect attribute" on page 196.

To roughen a selected path manually:

1 In the Tools panel, select the Roughen tool from its pop-up menu.

2 Drag to apply the effect to the selection.

To roughen a selected path or object precisely:

1 In the Tools panel, if the Roughen tool is not showing, select it from its pop-up menu.

2 Double-click the Roughen tool.

3 For Amount, enter the number of points added per inch, from 0 to 100.

4 For Edge, select Rough to use corner points to create a jagged edge, or select Smooth to use curve points to create a smooth, hand-drawn distorted edge.

5 Click OK.

6 Click anywhere on the path and drag. Dragging farther from the path makes the path rougher.

Note: To apply this effect to text, first select the text and then select Text › Convert to Paths.

Applying a fisheye lens effect

You can alter a path or object by applying a fisheye lens effect. Concave and convex fisheye lens effects are most easily seen on symmetrical shapes.

To apply a fisheye lens effect to an object manually:

1 In the Tools panel, select the Fisheye Lens tool from its pop-up menu.

2 Drag to apply the effect to the selection.

To apply a precise fisheye lens effect to a selected path or object:

1 In the Tools panel, if the Fisheye Lens tool is not showing, select it from its pop-up menu.

2 Double-click the Fisheye Lens tool.

3 For Perspective, enter an amount or drag the slider between Concave (–100) and Convex (100). The preview shows the amount of distortion.

4 Click OK.

Bending or bloating objects or paths

You can alter a path or object by bending or bloating the shape of the path. In a spiked effect, the path is curved inward while the anchor points are moved outward. In a bloated effect, the path is curved outward while the anchor points are moved inward. You can also use the Bend effect attribute to create a bent or bloated appearance for an object without permanently altering the object. For more information, see "Using a Bend effect attribute" on page 194.

To distort a selected object manually:

1 In the Tools panel, select the Bend tool from its pop-up menu.

2 Drag to apply the distortion to the selection.

To bend or bloat a selected path or object:

1 In the Tools panel, if the Bend tool is not showing, select it from its pop-up menu.

2 Double-click the Bend tool.

3 Enter a value from 1 to 10 or drag the slider to set the amount of distortion. The higher the value, the greater the distortion.

4 Click OK.

5 Click the mouse button to set the center point for the distortion and drag:

• Drag up for a spiked effect, curving the path inward while the anchor points are moved outward.

• Drag down for a bloated effect, curving the path outward while the anchor points are moved inward.

Adding a manual drop shadow to an object

A manual drop shadow is a copy of an object placed behind the original to give the illusion of a light source. You can customize a shadow's appearance by changing the Shadow tool options and by moving the shadow. The original object and its shadow form a group.

You can add one of three drop-shadow types to an object: Hard Edge, Soft Edge, and Zoom.

Hard Edge (left), Soft Edge (center), and Zoom (right)

You can also use the Smudge tool or the Drop Shadow live effect to create a shadow. For more information on the Smudge tool, see "Smudging an object" on page 220. For more information on the Drop Shadow effect, see "Applying live raster effects" on page 198.

The Shadow tool does not apply shadows to bitmap or EPS images, text, or clipping paths. You can apply a shadow to text using the Drop Shadow effect in the Object panel. For more information, see "Using Shadow and Glow effect attributes" on page 202.

To set drop shadow options:

1 In the Tools panel, if the Shadow tool is not showing, select it from its pop-up menu.

2 Double-click the Shadow tool.

3 In the Shadow dialog box, Select a shadow type: Hard Edge, Soft Edge, or Zoom.

4 For Hard Edge and Soft Edge shadows, select a Fill option:

   Tint defines the shadow color as a tint of the original object's color, from 0 (white) to 100%.

   Shade defines the shadow color as a percentage of black added to the original object's color.

   Color lets you set the shadow color by using the pop-up color palette.

5 For a Soft Edge shadow, drag a color to the Fade To color box to set the shadow's background color (white by default). Set a Soft Edge degree to soften the shadow's edges with the Fade To color, from 0 for a hard edge to 100 for soft throughout.

6 For a Zoom shadow, set a stroke color and fill color.

   For the Soft Edge and Zoom effects, the Shadow tool creates incremental colors. Applying soft-edged or zoomed shadows to objects with spot, Hexachrome, or RGB colors yields incremental CMYK process colors.

7 For Scale, specify the shadow's size as a percentage of the original.

8 For Offset, enter x and y values to offset the shadow relative the object.

9 Click Apply to preview the result without closing the Shadow panel, or click OK to apply the shadow and close the panel.

To add a drop shadow to one or more selected objects:

1 In the Tools panel, select the Shadow tool from its pop-up menu.

2 Click to place the shadow and drag to move it. Each time you click, the shadow reappears directly under the selected object.

To add a drop shadow to selected text:

Select Text > Convert to Paths before applying the drop shadow.

Note: Text that is converted to paths cannot be edited as text (for more information, see "Converting text to paths" on page 287).

To add a drop shadow to a clipping path:

Apply the shadow to an object before using it as a clipping path.

Smudging an object

The Smudge tool lets you soften the edges of objects for a drop shadow effect by blending the edge colors.

Smudging creates grouped copies of the original object. If you smudge an object more than once, FreeHand creates copies of each object in the group. An error message appears if a smudge command would exceed the tool's capabilities.

To set smudge options:

1 In the Tools panel, if the Smudge tool is not showing, select it from its pop-up menu.

2 Double-click the Smudge tool.

3 To set the fill color of the smudge, click the color box and select a color from the pop-up color palette.

4 To set the stroke color of the smudge, click the color box and select a color from the pop-up color palette.

To create a drop shadow effect, select a slightly darker tint of the background color as the fill color and select a stroke of None.

5 Click OK.

To smudge a selected object:

1 In the Tools panel, select the Smudge tool from its pop-up menu.

2 Position the pointer over the path to smudge, and then do one of the following:

• Drag outward without releasing the mouse button to see a preview of the selection, linked to the original object by a line, then release the mouse button.

• Hold down Alt (Windows) or Option (Macintosh) as you drag to smudge outward from the center for a soft edge.

Embossing an object

Use Emboss to create a 3D appearance in which the edges of an object are raised or lowered so the object appears to be embossed into the background. Applying the Emboss Xtra creates multiple objects much like blending or smudging.

You can only emboss closed paths with a Basic, Gradient, or Pattern fill.

You can also use the Emboss effect in the Object panel to create the appearance of embossing without altering the original object's properties. For more information, see "Applying live raster effects" on page 198.

To emboss a selected object:

1 Do one of the following:

• Select Xtras > Create > Emboss.

   Note: To apply the effect without opening the dialog box, hold down Control (Windows) or Command (Macintosh), and click the Emboss button.

• Select Window > Toolbars > Xtra Operations to display the Xtra Operations toolbar, and click the Emboss button.

2 In the Emboss dialog box, click a button at the top to select an effect: Emboss, Deboss, Chisel, Ridge, or Quilt.

3 From the Vary list, select an option to specify the relief and how an object's colors create highlight and shadow:

   Contrast specifies a tint of the path's original colors for the highlight and percentages of black combined with the path's original color for the shadow.

   Colors specifies colors using the Highlight and Shadow color boxes.

   The Emboss Xtra creates incremental colors to achieve an effect. Applying the effect to objects with spot, Hexachrome, or RGB colors yields incremental CMYK process colors.

4 For Depth, enter a value up to 72 or drag the slider between 1 and 20 to control the distance by which the effect is raised or impressed.

5 For Angle, enter a value or drag the dial to set the angle for the light source. Angle affects the direction of the highlight and shadow.

6 Select Soft Edge to blend the relief for the Emboss or Deboss effect.

Click Apply to preview the effect, or click OK to apply the effect and close the dialog box.

Creating envelopes

Envelopes let you warp and distort graphics and text blocks. An envelope is a hidden wrapper or enclosure that warps one or more objects. Changes made to an envelope's shape affect the shape of the objects contained within the envelope.

You can save envelope settings for later use by storing envelopes as presets. These presets are retained in the Envelope toolbar.

To display the Envelope toolbar:

Select Window > Toolbars > Envelope.

To apply the envelope effect to a selected object:

1 Select Window > Toolbars > Envelope to display the Envelope toolbar.

2 Select Modify > Envelope > Create, or click the Create button on the Envelope toolbar.

3 Modify the envelope as you would any FreeHand path and note the effect on the contents of the envelope.

   You can use any path-changing tool or operation to modify an envelope. For example, dragging a corner point of an envelope outward causes the objects enclosed to stretch in that direction. For more information on adjusting handles and points, see "Editing paths" on page 86.

To view the envelope map:

Select Modify > Envelope > Show Map, or click the Show Map button on the Envelope toolbar.

To copy a path and use it as an envelope on another object:

1 Select the envelope object and select Edit > Copy.

2 Select an object and select Modify > Envelope > Paste as Envelope, or click the Paste as Envelope button on the Envelope toolbar.

To convert an envelope to a path:

1 Select the envelope object.

2 Do one of the following:

• Select Modify > Envelope > Copy as Path.

• Click the Copy as Path button on the Envelope toolbar.

3 Select Edit > Paste.

To remove an envelope from an object, do one of the following:

- To remove the envelope but retain any changes to the object's shape, select Modify > Envelope > Release, or click the Release button on the Envelope toolbar.

- To remove the envelope and remove changes to the objects, select Modify > Envelope > Remove, or click the Remove button on the Envelope toolbar.

To save an envelope effect as a preset:

1 Select an enveloped object.

2 Select Modify > Envelope > Save as Preset, or click the Save as Preset button in the Envelope toolbar.

3 Type a name for the preset in the Name text box of the New Envelope dialog box and click OK.

   Envelope settings are stored in the file named Envelope.set (Windows) or Envelope (Macintosh) located in the Macromedia/FreeHand/11/English/Settings folder within your user-specific Application Data (Windows) or Application Support (Macintosh) folder.

   Note: The location of your user-specific Application Data or Application Support folder can vary depending upon your operating system. For information on how to locate this folder, refer to your operating system's documentation.

To delete an envelope preset:

1 Select an enveloped object.

2 Select Modify > Envelope > Delete Preset or click the Delete a Preset button in the Envelope toolbar.

   Note: Deleting the Envelope settings file removes all of your custom envelope presets.

Creating patterns

You can create simple or complex patterns using Xtra operations or tools. The Fractalize command creates intricate, square-like patterns. The Mirror Xtra tool reflects an existing path to create a pattern.

A circle (left) and a circle after the Fractalize command has been applied ten times (right)

To create a pattern using the Fractalize command:

1 Select an object.

2 Select Window > Toolbars > Xtra Operations.

3 Click the Fractalize button.

Each application of Fractalize almost doubles the number of points on the selected object. This can increase file size.

To set Mirror tool options:

1 Select Window > Toolbars > Xtra Tools.

2 Double-click the Mirror button in the Xtra Tools toolbar.

3 In the Mirror dialog box, select the axis around which the objects should reflect:

Horizontal reflects from top to bottom.

Vertical reflects from left to right.

Horizontal & Vertical reflects both ways at once.

Multiple reflects around multiple axes.

4 If you chose Multiple, set these additional options:

• Set the number of axes the object reflects around. (Specify 1 to 50 using the slider, or specify 1 to 100 by typing a value.)

• Select Reflect to multiply the path and its reflection, or select Rotate to multiply only the path.

5 Select Close Paths to close any open paths whose end points are within the Snap distance set in general preferences; deselect the option to leave the paths open.

6 Click OK.

To create a pattern by specifying Mirror Xtra tool options:

1 Select a path, text container, or image.

> **Note:** You must select the entire path, text container, or image. The entire path will be selected for mirroring, even if you've selected only some points on a path.

2 Select Window > Toolbars > Xtra Tools.

3 Click the Mirror button in the Xtra Tools toolbar.

4 Specify the reflection by dragging the pointer to specify the halfway point between the selected path and its reflection or the center point of a group of reflections. Keylines show the position of each reflection upon release.

As you drag, you can use modifier keys to control the reflection, as follows:

- To rotate keylines around the cursor, hold down Alt (Windows) or Option (Macintosh).

- To constrain the rotation to 45° increments, hold down Alt+Shift (Windows) or Option+Shift (Macintosh).

- To toggle between reflect and rotate when setting Multiple mirrors, press the Up or Down Arrow key.

- To increase or decrease the number of axes when setting multiple mirrors, press the Right or Left Arrow key.

Using 3D rotation

The 3D Rotation tool applies simple 3D rotations to two-dimensional (2D) objects. You can also rotate objects in 3D space using the Extrude tool (for more information, see "Extruding objects" on page 205).

To set 3D rotation options:

1 In the Tools panel, if the 3D Rotation tool is not showing, select it from its pop-up menu.

2 Double-click the 3D Rotation tool.

3 Select the amount of control over the rotation, Easy or Expert.

4 Select the point of rotation from the Rotate From pop-up menu:

Mouse Click rotates from the point you click with your mouse.

Center of Selection rotates from the center of the object selected.

Center of Gravity rotates from the visual center of the object.

Origin rotates from the lower left corner of the object.

5 Enter a Distance value. Alternatively, drag the slider to the left (smaller values) to maximize distortion, or drag to the right (larger values) to minimize distortion.

6 If you selected the Expert option, select the point of projection, or vanishing point.

Mouse Click makes the projection extend to the location you click with your mouse.

Center of Selection makes the projection center behind the selected object.

Center of Gravity makes the projection center behind the visual center of the object.

Origin makes the projection begin at the lower left corner of the object.

X/Y coordinates lets you enter x and y coordinates for the projection. The value defaults to the last mouse coordinates.

To rotate a selected object in 3D space:

1 In the Tools panel, select the 3D Rotation tool from its pop-up menu.

2 Click the object, and drag to rotate it. Hold down Shift to constrain the rotation to 45° increments.

Creating perspective

You can add perspective to objects by attaching them to a perspective grid. The perspective grid is a nonprinting array of lines that lets you define one-, two-, or three-point perspective with vanishing points, a horizon line, and grid lines for each plane. The perspective grid creates envelopes that adjust automatically as they're moved on the grid.

The Perspective tool lets you attach objects to the grid and move objects around the grid. Objects moved with the Perspective tool take on a new appearance as you move them around the grid. If you move an object using the Pointer tool or arrow keys, it is detached from the grid.

Attaching objects to a perspective grid

To attach objects to a perspective grid and give the object a 3D appearance, you display a perspective grid and then use the Perspective tool. The object retains the perspective even after it's released from the perspective grid.

To attach an object to the perspective grid:

1 Select View > Perspective Grid > Show to display the default perspective grid.

For instructions on editing perspective grids, see "Editing perspective grids" on page 230.

2 In the Tools panel, select the Perspective tool from its pop-up menu.

3 Select the object you want to attach to the grid, and drag the object to the desired area of the perspective grid. Do not release the mouse button yet.

4 While holding down the mouse button, press and release the arrow key that corresponds to where you want to attach the object to the perspective grid, as follows:

• For a perspective grid with only one vanishing point, press either the Left or Right Arrow key to attach an object to the vertical grid; press either the Up or Down Arrow key to attach an object to the horizontal grid.

• For a perspective grid with more than one vanishing point, press the Left or Right Arrow key to attach an object to the left or right grid, respectively. Press the Up Arrow key to attach an object to the floor grid, aligned with the right vanishing point. Press the Down Arrow key to attach an object to the floor grid, aligned with the left vanishing point.

5 Release the mouse button.

Unattached object

Attached object

To move an object on the perspective grid:

1 In the Tools panel, select the Perspective tool from its pop-up menu.

2 Reposition the object by using one of these methods:

• Drag the object to a new location on the perspective grid.

• To move an object while constraining it to the perspective grid lines, Shift-drag the object.

• To move the grid and clone all attached objects, hold down Alt+Shift (Windows) or Option+Shift (Macintosh) key and drag the grid.

Note: When View > Grid > Snap to Grid is selected, objects moved using the Pointer tool snap to the perspective grid but do not automatically obtain a perspective appearance.

To flip an object horizontally or vertically on the perspective grid:

1 Click the object with the Perspective tool. Do not release the mouse button yet.

2 While holding the mouse button down, press the Spacebar to flip a side grid object horizontally or a floor grid object vertically.

3 Release the mouse button.

To shrink an object on the perspective grid:

1 Select the object with the Perspective tool.

2 While holding down the mouse button, press one of the following keys on the keyboard to shrink the object by 1 pixel in the indicated directions:

• Press 1 for width and height.

• Press 3 for width.

• Press 5 for height.

To enlarge an object on the perspective grid:

1 Select the object with the Perspective tool.

2 While holding down the mouse button, press one of the following keys to enlarge the object by 1 pixel in the indicated directions:

• Press 2 for width and height.

• Press 4 for width.

• Press 6 for height.

To detach an object from the perspective grid, do one of the following:

• To discard perspective attributes, select View > Perspective Grid > Remove Perspective.

• To retain perspective attributes, select View > Perspective Grid > Release With Perspective.

Editing text on a perspective grid

You can use the Text Editor to edit text that is attached to a perspective grid. If you release text from the perspective grid while retaining its perspective (View > Perspective Grid > Release with Perspective), it is converted to grouped paths and can no longer be edited as text.

To edit text that is attached to a perspective grid:

1 In the Tools panel, select the Perspective tool from its pop-up menu.

2 Hold down Control+Alt (Windows) or Command+Option (Macintosh) and double-click the text.

3 In the Text Editor, edit the text. Click Apply to make the changes without closing the Text Editor, or click OK to apply the changes and close the text editor.

Editing perspective grids

You can define a new perspective grid, edit the grid, and store custom grid settings using the Define Grids command. You can alter the grid's attributes at any time.

The attributes of the perspective grid determine the look of your 3D objects. By defining the number of vanishing points and their positions, as well as the grid cell size, you can alter the viewer's perspective.

To create a new perspective grid:

1 Select View > Perspective Grid > Define Grid to open the Define Grids panel.

2 Click New to create a new grid or click Duplicate to copy an existing grid.

3 To rename the grid, select the grid name from the list and enter the new name. You cannot use the name of an existing grid.

4 For Vanishing Points, select a number from the pop-up menu: 1, 2, or 3.

5 Enter a value for the grid cell size. This value uses the units of measure specified for this document.

6 To change the grid color, click the Left, Right, or Horizontal Grid color swatches, and select a new color from the color palette.

7 When you have finished defining the grid, click OK.

To edit an existing grid:

1 Select View > Perspective Grid > Define Grid.

2 In the Define Grids dialog box, select the grid you want to modify.

3 Change the grid settings and click OK.

To delete a grid:

1 Select View > Perspective Grid > Define Grid.

2 Select the grid name and click Delete.

To replace a grid in the grid list, delete the unwanted grid and then create a new one.

To alter the grid angles and orientation:

1 In the Tools panel, select the Perspective tool from its pop-up menu.

2 Drag a gridline to adjust it. A small arrow beside the pointer indicates that the pointer is over an active area.

3 Adjust the grid in the following ways:

- To hide or show a grid associated with a particular vanishing point, double-click the vanishing point. A small arrow remains to mark the vanishing point's location.

- To hide or show a grid floor, double-click the horizon line. A line remains to show the horizon's location.

To create a new grid by modifying an existing grid:

Hold down Alt (Windows) or Option (Macintosh) as you drag the grid with the Perspective tool.

The new perspective grid appears in the Define Grids dialog box with the default name numbered in sequence (for example, Grid 2).

CHAPTER 8
Using Type

Text that you place in a Macromedia FreeHand MX document is contained in a text block. To control the appearance of text in your document, you can manipulate text and text blocks in a variety of ways. You can precisely control type specifications and apply stroke and fill colors to text and text blocks. You can format type in columns, rows, and tables. You can also place text inside objects or along paths, or place inline graphics in text blocks.

To ensure that text on your pages displays and prints correctly, use either PostScript or TrueType fonts. For more information, see "About printing fonts" on page 383.

Creating text

In FreeHand, you create text by clicking or dragging with the Text tool to create a text block, and then typing in the text block to enter text.

New text that you enter in FreeHand is formatted with the default text attributes in the Object panel or the currently selected text style in the Styles panel. For information on changing text specifications, see "Setting precise type specifications" on page 250.

By default, clicking with the Text tool creates an auto-expanding text block that expands as you enter text. You can change this behavior by setting text preferences. Dragging with the Text tool creates a fixed-size text block in which text automatically wraps from one line to the next. For more information, see "Working with text blocks" on page 234.

When you use the Text tool to create or select text, the text ruler is displayed. For information on hiding the text ruler, see "Selecting text" on page 238.

To create text:

1 Click the Text tool in the Tools panel.

2 Do one of the following:

- To create an auto-expanding text block, click in the Document window and begin typing to enter text. To create a line break, press Enter (Windows) or Return (Macintosh).

- To create a fixed-size text block, drag in the Document window and begin typing in the text block that appears.The text automatically wraps within the text block; to create a new paragraph, press Enter (Windows) or Return (Macintosh).

- To open the Text Editor as you create a new text block, hold down Alt (Windows) or Option (Macintosh) as you click in the Document window. For more information on the Text Editor, see "Using the Text Editor" on page 241.

- To add text to an existing text block, click in the desired location within the text block, and start typing.

3 To finish entering text, click outside the text block.

Note: By default, the Text tool reverts to the Pointer tool after you create a text block and moves the pointer outside the text block. To change this behavior, press Control+U (Windows) or Command+U (Macintosh), click Text, and deselect Text Tool Reverts to Pointer.

Working with text blocks

You can manipulate text blocks as you do other objects in FreeHand. You can move, delete, and resize text blocks. You can also convert fixed-size text blocks to auto-expanding text blocks, or the reverse.

Fixed-size text blocks can be a fixed width, a fixed height, or both. When selected, a fixed-width text block has solid side selection handles, and a fixed-height text block has a solid bottom center handle. You can resize a fixed-size text block by dragging any of the corner selection handles.

Auto-expanding text blocks have either hollow side selection handles or a hollow bottom center handle, or both.

A square link box appears at the lower right corner of a selected text block. When a fixed-size text block contains more text than it can display, a dot appears in the link box to indicate overflow text. (Auto-expanding text blocks do not overflow, because they expand as text is entered.) You can link text blocks to flow text from one block to another; see "Linking text blocks" on page 239.

Non est quod
contemnas hoc
studendi genus.

Non est quod contemnas hoc studendi genus

A fixed-size text block and an auto-expanding text block

You can apply stroke and fill colors to text blocks (see "Applying color to text and text blocks" on page 269). You can also apply transformations, such as rotating, skewing, or scaling, as well as remove the transformations you have applied (see "Using a Transform effect attribute" on page 197). And you can duplicate or group text blocks (see "Grouping objects" on page 119) or place them on different layers (see "Using layers" on page 289).

You can also apply live effects to text blocks. Live effects can be applied only to the text block, however, and not the text within it. For more information about live effects, see Chapter 7, "Special Effects," on page 193.

To remove transformations applied to a text block:

1 Using the Pointer tool, select the text block.

2 Select Text > Remove Transforms.

Except for move transformations, all other transformations applied with the Modify > Transform submenu options or the transformation tools in the Tools panel are removed.

Note: Live effects applied through the Object panel are not removed.

Moving, deleting, and resizing text blocks

You can move text blocks, and delete selected text blocks or all empty text blocks in a page or document. By dragging their corner selection handles, you can resize fixed-size text blocks. When working in Preview mode, you can turn selection highlights for text blocks on or off. For more information, see "Using layer highlight colors" on page 296.

To move or delete a text block:

1 Using the Pointer tool, select the text block.

2 Do one of the following:

• To move the text block, drag it.

• To delete a text block, press Delete or select Edit > Clear. To delete an empty auto-expanding text block, deselect the block.

To delete all the empty text blocks in a page or document:

Select Xtras > Delete > Empty Text Blocks. All empty text blocks in the document are removed.

To resize a fixed-size text block:

1 Select the Pointer tool.

2 Do one of the following:

- To adjust the size of a text block, drag a corner selection handle. Text within the container reflows to fill the new size.

- To resize a text block while constraining its width and height proportionally, Shift-drag a corner handle diagonally. Text within the container reflows to fill the new size.

- To scale a text block and its font size, hold down Alt (Windows) or Option (Macintosh) and drag a corner handle.

- To scale a text block and its font size while constraining width and height proportionally, hold down Shift+Alt (Windows) or Shift+Option (Macintosh) and drag a corner handle.

- To reduce the size of a text block to fit the text, double-click the link box at the lower right corner of the text block with the Pointer tool.

Converting fixed-size or auto-expanding text blocks

Clicking with the Text tool creates an auto-expanding text block by default. You can change the default behavior of the Text tool to create a fixed-size text block when you click the tool. Once you have created a text block, you can convert it from fixed-size to auto-expanding or the reverse.

To specify the type of text block created with the Text tool:

1 Display text preferences by doing one of the following:

- In Windows, press Control+U, then click the Text tab.

- On the Macintosh, press Command+U, then click the Text category.

2 Choose the desired behavior for clicking to create a text block:

- Select New Text Containers Auto-Expand (the default setting) to create an auto-expanding text block when you click with the Text tool.

- Deselect New Text Containers Auto-Expand to create a fixed-size text block when you click with the Text tool.

To convert a text block between auto-expanding and fixed-size:

1 Using the Pointer tool, select a text block.

2 Do one of the following:

- Double-click a text block's side handle (not a corner handle) to convert the text block from auto-expanding to fixed-width or the reverse. Solid side handles indicate that the text block is a fixed width. Hollow side handles indicate that the text block is auto-expanding.

- Double-click a text block's bottom handle (not a corner handle) to convert the text block from auto-expanding to fixed-height or the reverse. A solid bottom center handle indicates that the text block is a fixed height. A hollow bottom center handle indicates that the text block is auto-expanding.

To convert multiple text blocks between fixed-size and auto-expanding:

1 Using the Pointer tool, Shift-click the text blocks that you want to convert.

2 If the Object panel isn't visible, select Window > Object.

3 Do one of the following in the options section of the Object panel:

- If you are converting fixed-size text blocks to auto-expanding text blocks, click the Width button to set the blocks' width to auto-expand, or click the Height button to set the blocks' height to auto-expand.

- If you are converting auto-expanding text blocks to fixed-size text blocks, deselect the Width button to fix the blocks' width at the current size, or deselect the Height button to fix the blocks' height at the current size.

Importing text

In FreeHand, you can import RTF (Rich Text Format) text files with text formatting intact, and unformatted ASCII text files (plain text). If you import text containing fonts and font styles not installed on your system, the Missing Fonts dialog box prompts you to select replacement fonts and font styles. For more information, see "Handling font substitution" on page 65.

Note: Importing RTF text with custom tab leaders, custom strikethrough, or custom underline effects changes the effects. Outline, subscript, and superscript effects can be imported but not exported.

You can also drag text or copy and paste it to import it from another application. Once you import text, you can edit it as you would any text in FreeHand. For more information, see "Editing text" on page 240.

For information on exporting text files or text with inline graphics, see "Exporting text" on page 361.

The English version of FreeHand does not support double-byte text used in some Asian languages. When importing double-byte text, the English version of FreeHand rotates the text block to simulate vertical alignment, but the character orientation defaults to horizontal.

To import a text file:

1 Select File > Import to display the Import Document dialog box.

2 Select a text file to import and click Open.

3 Place the imported text by doing one of the following:

- Click to place the text file at its original size.

- Drag to set the position and the size of the text block.

Selecting text

To edit or delete text or change type attributes, you select the text with the Text tool.

When you click in a text block or select text with the Text tool, the text ruler appears. The text ruler displays the text block's width in points, as well as tab and indent markers. You can hide or show the text ruler, and you can set preferences to show text block handles when the text ruler is turned off.

To select text:

1 Click the Text tool.

2 Do one of the following:

• To select characters, words, or paragraphs, click in a text block to place an insertion point and drag to make a selection.

• To select a word, double-click anywhere in the word.

• To select a paragraph, triple-click anywhere in the paragraph.

• To select all text within a text block, click in the text block and select Edit > Select > All.

To show or hide the text ruler:

Select View > Text Rulers.

To show text block selection handles when the text ruler is hidden:

1 Display text preferences by doing one of the following:

• In Windows, press Control+U, then click the Text tab.

• On the Macintosh, press Command+U, then click the Text category.

2 Select Show Text Handles When Ruler Is Off (the default setting) to display text handles when you click in a text block with the Text tool and the text ruler is not visible. Deselect the option to hide text block selection handles when the text ruler is hidden.

Note: Text block selection handles appear when you click in a text block with the Pointer tool, whether or not this option is selected.

3 Click OK.

About text appearance

Like vector objects, text in FreeHand is anti-aliased in all drawing modes.

The exceptions are text that uses bitmap fonts and text that has been modified by the zoom text effect, the inline text effect, or rotation and skew transformations.

You can turn the anti-aliasing preference off; for more information, see "Anti-aliasing artwork" on page 28.

Note: On the Macintosh, anti-aliasing is only available if you're running Mac OS X or later.

Linking text blocks

You can link fixed-size text blocks to other text blocks or to objects, such as paths, to force text to flow between the linked blocks or objects. Generally, you link text blocks when they contain overflow text (indicated by a dot in the link box). However, you can also link empty or partially filled blocks and then add text.

The order in which text flows from one block to the next is indicated by a link line.

Linked text blocks

You can link an auto-expanding text block as the final object in a linked set; however, do not use an auto-expanding text block as the first or intermediary link in a set. Text will not flow out of an auto-expanding text block, because the block expands to contain all the text placed into it.

A linked object acquires text block attributes and retains these attributes even if the text is deleted.

Changes to selected text in a linked text block may affect text in other linked blocks. For example, when you enlarge the font size in one text block, text may reflow into the next block.

You can break a link between text blocks and retain the text blocks and the text placement that follow the broken link. You can also break a link and delete the text and the text blocks that follow the broken link.

To create a link:

1 Using the Pointer tool, select the fixed-size text block that you want to link.

> **Note:** If the originating text block contains overflow text, an indicator dot appears in its link box. You can link blocks with or without overflow text.

2 Drag from the link box of the originating text block to the inside of another text block or onto a path.

A link indicator appears in the link box of the originating text block to indicate that the block is linked. If the originating text block contains overflow text, the text flows into the empty text block or path.

3 Repeat steps 1 and 2 to link additional text blocks or paths. You can link any number of text blocks or paths on a single page or across multiple pages.

To break a link and retain text placement:

1 Using the Pointer tool, select the desired text block.

2 Drag the link line from the link box of the text block to one of the following:

• An empty area in the document

• A text block or object other than the one the previous text block was linked to

The text remains intact. If you dragged the link line to another text block or object, the text reflows into that text block or object.

3 (Optional) If the last linked text block or object in the linked set now has a dot in the link box (indicating it has overflow text), resize the text block so that all text is visible.

Editing text

You can edit text in FreeHand using various techniques. To edit text onscreen, you select it with the Text tool (see "Selecting text" on page 238). You can also edit text in the Text Editor.

You can check spelling, hyphenate text, use smart quotes, and insert nonprinting characters to control spacing. You can also change type attributes (see "Working with the type adjustment tools" on page 247).

Using the Text Editor

The Text Editor lets you review and edit text that's difficult to edit onscreen—for example, text that includes nonprinting characters.

You can choose to always use the Text Editor for editing by selecting the appropriate option in text preferences.

To edit text in the Text Editor:

1 Do one of the following:

• Using the Pointer tool, select the text block you want to edit and select Text > Editor.

• Using the Pointer tool, hold down Alt (Windows) or Option (Macintosh) and double-click a text block.

• Using the Text tool, Alt-click (Windows) or Option-click (Macintosh) a text block.

• In Windows, right-click a text block with the Text tool and select Editor from the context menu.

2 Select 12 Point Black to ignore formatting attributes and display text in 12-point black type in the Text Editor window. This option does not affect text formatting in the document, but makes the text more legible if you are editing text that is very large or small, or has a light color.

3 Select Show Invisibles to display nonprinting characters, such as spaces, tabs, or paragraph breaks, in the Text Editor window.

4 Edit the text in the Text Editor window.

5 Click one of the following:

OK applies the changes and closes the Text Editor.

Cancel closes the Text Editor without applying changes.

Apply applies changes to the text without leaving the Text Editor.

To always edit text in the Text Editor:

1 Display text preferences by doing one of the following:

• In Windows, press Control+U, then click the Text tab.

• On the Macintosh, press Command+U, then click the Text category.

2 Select Always Use Text Editor, then click OK.

Inserting special characters

You can insert characters from the Text > Special Characters submenu. The special characters allow you to apply additional formatting to control the appearance of text.

The following special characters are available:

End of column □	For text formatted into columns, indicates the final character in a column.
End of line	Indicates the final character in a line without creating a new paragraph.
Nonbreaking space	For two words separated by a space, ensures that the words do not break apart at a line break.
Em space	Inserts a space equal to the point size of the current typeface.
En space	Inserts a space equal to 1/2 the point size of the current typeface.
Thin space	Inserts a space equal to 1/10 the point size of the current typeface.
Em dash ▬	Inserts a dash the width of an em space.
En dash ▬	Inserts a dash the width of an en space.
Discretionary hyphen	Inserts a hyphen into a word only if the line breaks at its location.

To insert characters from the Special Characters submenu:

1 Do one of the following:

• Using the Text tool, click in the text block where you want to insert a special character.

• With the Text Editor open (see "Using the Text Editor" on page 241), click in the Text Editor window where you want to insert a special character.

2 Select Text > Special Characters, and select a character from the submenu.

Checking spelling

The FreeHand spelling checker lets you use standard word-processing spell check functions to correct errors in your document, including spelling, capitalization, and duplicate words. As you spell check, you can add new words, such as proper names or technical terms, to your personal dictionary.

The spelling checker uses the language dictionary appropriate for the version of FreeHand that you installed, but you can change dictionaries if you have others installed.

You can edit your personal dictionary, customize spell check behavior, or choose an alternate dictionary in the Preferences dialog box.

To use the spelling checker:

Select Text > Spelling.

To set spelling preferences:

1 Do one of the following:

- In Windows, press Control+U and click the Spelling tab.

- On the Macintosh, press Command+U and click the Spelling category.

- From the Spelling dialog box (Text > Spelling), click Setup.

2 Select or deselect any of the following Spelling options from the Preferences dialog box to set how FreeHand conducts a spell check:

- Find Duplicate Words

- Find Capitalization Errors

- Ignore Words with Numbers

- Ignore Internet and File Addresses

- Ignore Words in Uppercase

3 Select one of the following in the Add Words to Dictionary section to set how a highlighted word in the spelling checker is added to the dictionary when you click Add:

Exactly as Typed adds a highlighted word exactly as it appears.

All Lowercase adds a highlighted word in lowercase letters only.

4 If desired, select a different language dictionary from the Dictionary pop-up menu.

5 To locate a different saved personal dictionary (TLX file), click the Ellipses (...) button (Windows) or the Select button (Macintosh) and locate another personal dictionary.

6 Click Edit Personal Dictionary (Windows) or Edit (Macintosh) to edit the list of words added during spell check sessions. You can add more words directly from here, or change and delete existing words. Click OK when you have finished editing your personal dictionary.

Edit Personal Dictionary

```
contemnas
quod
studendi
```

`OK` `Cancel`

7 Click OK to accept the new spelling preferences.

Hyphenating text

You can turn on automatic hyphenation for a document or a selection. FreeHand uses the selected document language to determine where hyphenation should be placed.

You can also insert discretionary hyphens at specific points in the text. Discretionary hyphens allow lines to break at the points you specify, and only appear when they occur within a word that breaks at the end of a line. For more information, see "Inserting special characters" on page 242.

To set hyphenation options:

1 Specify the text to which the hyphenation options will be applied:

- To apply hyphenation to all text in a text block, select the entire text block. Selecting a linked text block applies hyphenation options to all blocks in the linked set.

- To apply hyphenation to selected text only, select the text with the Text tool.

- To apply hyphenation only to a specific paragraph, click in the paragraph with the Text tool.

2 Select Window > Object to open the Object panel if it's not already open.

3 Display the Paragraph options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

4 Select Hyphenate to turn on automatic hyphenation.

5 Click the Edit button beside the Hyphenate option to display the Edit Hyphenation dialog box.

6 For Document Language, select an option from the pop-up menu.

7 To set the number of consecutive hyphens allowed within a paragraph, enter a number for Consecutive Hyphens.

8 To prevent hyphenation of capitalized words, select Skip Capitalized Words.

9 To prevent hyphenation in the current text selection, select Inhibit Hyphens in Selection.

10 Click OK.

To turn off hyphenation:

1 Repeat steps 1 through 3 in the previous procedure.

2 Deselect the Hyphenate option in the Object panel.

Using smart quotes

When the Smart Quotes option is turned on, FreeHand uses a curved right or left quotation mark or marks when you type a single (') or double (") quotation mark. You can choose from six predefined smart quotation marks in the Define Quotes pop-up menu.

If the Smart Quotes option is on but you want to enter straight quotation marks, you can override the option temporarily. For example, you can use this technique to include feet and inch marks (as in 5' 6") when Smart Quotes is turned on.

To turn on the Smart Quotes option:

1 Display text preferences by doing one of the following:

- In Windows, press Control+U, then click the Text tab.

- On the Macintosh, press Command+U, then click the Text category.

2 Select Smart Quotes and select an option from the pop-up menu beside it:

- The first set of quotations marks is commonly used in Dutch, English, Italian, and Spanish.

  `“ ”`

- Double right quotation marks are commonly used in Danish, Finnish, and Swedish.

  `” ”`

- The first set of low-high quotation marks is commonly used in Czech and German.

  `„ “`

- The second set of low-high quotation marks is standard in Hungarian and Polish to mark a quote within a quote.

  `„ ”`

- Chevron quotation marks appear as an alternative to curved quotation marks in French, Greek, Italian, Norwegian, Russian, and Spanish.

  `« »`

- Reverse chevrons indicate a quote within a quote in Danish, German, and Hungarian.

  `» «`

  Note: To use more than one type of smart quote in a document, you must change the selection in the Smart Quotes pop-up menu in text preferences before typing the new quotation mark.

3 Click OK.

To type straight quotation marks when Smart Quotes is turned on:

Hold down Control and press the single-quote (') or double-quote (") key.

Note: On some international keyboards, pressing the Control key does not override the Smart Quotes preference.

Finding and replacing text

You can find and replace text using standard word-processing search procedures in the Find Text dialog box. To find and replace type attributes, you use the Find & Replace panel (see "Selecting, finding, and replacing type attributes" on page 259).

With the Find Text dialog box, you can locate and replace or delete any character, word, phrase, or special character in a document. You can find and replace a character string up to 255 characters long. You can also convert special characters—for instance, you can replace all double hyphens with em dashes.

To find and replace text:

1 Select the text blocks you want to search with the Pointer tool, or select a range of text with the Text tool. If you don't make a selection, text in the entire document will be searched.

2 Select Edit > Find and Replace > Text.

3 In the Find Text dialog box, enter text in the Find and Change To boxes. To find or change to a special character, select a character from the Special pop-up menu for the Find or Change To box.

Note: To delete the item in the Find box when found, leave the Change To box blank.

4 Select Whole Word, Match Case, or Show Selection to modify the search.

5 Click one of the following:

Find Next finds the next occurrence of the item in the Find box.

Change changes the item in the Find box.

Change All changes all occurrences of the item in the Find box.

Working with the type adjustment tools

You can apply precise type specifications to characters, lines of text, paragraphs, and entire text blocks using several different features: the type attributes in the Object panel; the Text toolbar; the Text menu and its submenus; and in Windows, the Text context menu.

Displaying type attributes in the Object panel

The Object panel lets you quickly apply common type specifications and text formatting.

Properties list

Text Block property
Text property
Options

Type attribute buttons

Text properties and type attributes in the Object panel

When text is selected in the document, the top portion of the Object panel, called the Properties list, displays properties applied to the selection.

The bottom half of the Object panel displays options for the selected property in the Properties list. When the Text property is selected in the Properties list, five buttons appear in the options section of the panel. These five buttons allow you to edit various type attributes. The options section of the Object panel is context-sensitive; when working with text, it changes depending on which property is selected in the Properties list and which type attribute button is pressed.

When no text or objects are selected in the document and a text style is selected in the Styles panel, the Object panel displays default text attributes. For more information, see "Using text styles" on page 274 and "Changing default attributes" on page 146.

To display type attributes in the Object panel:

1 Select Window > Object to open the Object panel if it's not already open.

2 Do one of the following:

• Using the Pointer tool, select a text block in the document.

• Using the Text tool, select a range of text.

• Select Edit > Select > None to deselect all objects in the document, then select a text style in the Styles panel (Window > Styles).

3 Click the Text property in the Object panel Properties list. It's the property with an *A* displayed beside it.

4 Click a type attribute button on the bottom left of the panel:

Character displays options that let you set the font, font style, size, text alignment, leading, and kerning; shift the baseline; and apply text effects and text styles.

Paragraph displays options that let you set paragraph spacing, indentation, and hyphenation; apply hanging punctuation to paragraphs; and apply rules to paragraphs.

Spacing displays options that let you scale characters horizontally, set word and letter spacing, and keep words and lines of text together to control breaks at the ends of lines and columns.

Columns and Rows displays options that let you create columns, rows, and tables.

Adjust Columns displays options that let you adjust text flow in columns.

The Text toolbar

The Text toolbar contains buttons for many common type adjustments. To apply an attribute, you select an option from the pop-up menus or click a button. You can use the Text toolbar to adjust the font, size, font style, leading, and alignment; attach a path to text or run text around a path, flow text within a path, or convert text to paths; open the Text Editor; check spelling; or flow text around a selection.

The Text toolbar can be customized with additional toolbar buttons. For more information, see "Customizing toolbars" on page 38.

The Text menu

The Text menu and its submenus include options for adjusting the font, size, font style, alignment, leading, effects, and case (capitalization). To use this menu, you select an option from the desired submenu.

The Text context menu (Windows)

In Windows, the Text context menu displays many of the choices that are also available in the Text menu, Text toolbar, and Object panel. You display the Text context menu by right-clicking a text block.

Setting precise type specifications

You can perform the following tasks to create and manage type attributes:

- Specify font, font style, and type size

- Convert type case to change characters to all uppercase, all small caps, or other options

- Set alignment, leading, range kerning, and baseline shift

- Space characters and words precisely to adjust horizontal scaling or space between words or letters

- Select or find and replace type attributes

If you change type specifications with text selected, the settings are applied to the selection only, and type specifications revert to the default settings for subsequent text. If you change type specifications with no text selected, the settings are applied to any subsequent text you create.

Choosing a font, type size, and style

You can choose a font, type size, and style using the Character options in the Object panel, the commands in the Text menu, or the tools in the Text toolbar.

You can set text preferences to control the display of font previews and to "greek" type (display type as a gray bar) below a specified point size.

To choose a font for selected text, do one of the following:

- Select Text > Font and select a font from the submenu.

- From the Character options in the Object panel, select a font from the Font Name pop-up menu. (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

- In the Text toolbar, select a font from the Font Name pop-up menu.

To specify a point size for selected text, do one of the following:

- Select Text > Size and select a point size from the submenu. To change the point size by 1-point increments, select Smaller or Larger from the submenu. To specify a point size that does not appear in the menu, select Other and enter a value in the Type Size dialog box, then click OK.

- In the Text toolbar, select a point size from the Type Size pop-up menu, or enter a value in the Type Size text box and press Enter (Windows) or Return (Macintosh).

- From the Character options in the Object panel, select a point size from the Type Size pop-up menu, or enter a value in the Type Size text box and press Enter (Windows) or Return (Macintosh). (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

- In Windows, right-click a text block, select Size, and select an option from the submenu.

To specify a font style for selected text, do one of the following:

• Select Text > Font Style and select a style from the submenu.

• From the Character options in the Object panel, select a style from the Font Style pop-up menu. (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

• In Windows, click a font style button in the Text toolbar.

B *I*

• On the Macintosh, select a style from the Font Style pop-up menu in the Text toolbar.

• In Windows, right-click a text block. Select Style, and select an option from the submenu.

To control the display of font previews:

1 Display text preferences by doing one of the following:

• In Windows, press Control+U, then click the Text tab.

• On the Macintosh, press Command+U, then click the Text category.

2 To display font previews, select Display Font Preview (the default). To turn off font preview display, deselect this option.

3 Click OK.

To preview a font, do one of the following:

• From the Character options in the Object panel, move the pointer over a font in the Font Name pop-up menu to preview it. (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

• In the Text toolbar, move the pointer over a font in the Font Name pop-up menu to preview it.

To greek text or display it as a gray bar:

1 Display redraw preferences by doing one of the following:

• In Windows, press Control+U, then click the Redraw tab.

• On the Macintosh, press Command+U, then click the Redraw category.

2 In the Greek Type Below box, enter the pixel size below which you want text to appear as a gray bar onscreen. By default, type set at 8 pixels or smaller is greeked.

Greeked text redraws more quickly than characters, so using it can improve display speed as you edit.

3 Click OK.

Note: Selected text displays as characters regardless of the Greek Type Below setting.

Converting type case

You can use the Convert Case commands to format text as uppercase, lowercase, or small caps, or to apply title capitalization (uppercase for the first letter of each word) or sentence capitalization (uppercase for the first letter of each sentence).

You can specify a size for small caps relative to the font size. (By default, small caps are 75% of the current font size.) You can also specify exceptions to prevent specified words from changing case.

To convert the type case:

1 Select a text block with the Pointer tool or select a range of text with the Text tool.

2 Select Text > Convert Case, and select an option from the submenu: Uppercase, Lowercase, Smalls Caps, Title, or Sentence.

To specify a size for small caps:

1 Select Text > Convert Case > Settings.

2 In the Settings dialog box, enter a percentage value for Small Caps, relative to the font size.

To specify exceptions to case conversion:

1 Select Text > Convert Case > Settings.

2 Under Use Exceptions For, select the case or cases to which the exceptions will apply. For example, if you are converting a text passage to Small Caps but want to prevent certain words in the passage from being converted, select Small Caps.

3 Click Add and enter a word into the list that you want to protect from case conversion.

4 Repeat step 3 to add additional exceptions. The words you enter will be prevented from converting when you apply the case conversion specified in step 2.

5 To delete an exception, select it in the list and click Delete.

6 Click OK.

Setting alignment, leading, range kerning, and baseline shift

Alignment determines the position of each line of type in a paragraph relative to the left and right edges of the text block. Type can be aligned to the left or right edge of the text block, centered within the text block, or aligned to both edges of the text block (full justification).

Leading is the distance between lines of text. Specifically, it is the distance from the baseline of a line of text to the baseline of the next line of text. By default, leading is equal to the current type size. You can change leading for selected text by using the Text > Leading submenu, the Text toolbar, or the Object panel, or by dragging text block selection handles.

You can specify custom leading values in three ways. With the Extra (+) option, you specify a value in points to be added to the current type size. For example, if the current type size is 24 and you enter 20, the leading will be 44; if you change the type size to 30, the leading will be 50. With the Fixed (=) option, you specify leading as an exact point size; the leading remains at the size entered even if you change the current type size. With the Percentage (%) option, you specify leading as a percentage of the current type size; the leading value changes if you change the current type size.

Kerning controls the space between two characters, relative to the point size of the current font. A positive kerning value increases the space between characters; a negative value decreases the space. Range kerning controls the space between all characters in a selection.

You can also control the spacing between words or characters numerically. For more information, see "Spacing characters and words precisely" on page 256.

Baseline shift controls where type appears in relation to its baseline.

To specify alignment for selected text, do one of the following:

• Select Text > Align and select an alignment option from the submenu.

• From the Character options in the Object panel, click an alignment button. (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

• In the Text toolbar, click an alignment button.

• In Windows, right-click a text block, select Align, and select an option from the menu.

To modify leading for selected text directly in the workspace:

Drag a text block's top or bottom center selection handle. Dragging away from the text block increases leading, and dragging toward its center decreases leading.

To set leading for selected text to be equal to the current type size:

Select Text > Leading > Solid.

To set leading for selected text as 120% of the current type size:

Select Text > Leading > Auto.

To specify leading for selected text as a point value to be added to the current type size:

1 Do one of the following:

• Select Text > Leading > Other to display the Leading dialog box, and select Extra from the pop-up menu.

• In the Text toolbar, select + from the Leading pop-up menu.

• From the Character options in the Object panel, select + from the Leading pop-up menu. (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

2 In the Leading text box, enter a value in points for the amount of leading you want to add to the current type size, and press Enter (Windows) or Return (Macintosh). To specify leading equal to the current point size, enter **0**.

To specify leading for selected text as a fixed point value:

1 Do one of the following:

• Select Text > Leading > Other to display the Leading dialog box, and select Fixed from the pop-up menu.

• In the Text toolbar, select = from the Leading pop-up menu.

• From the Character options in the Object panel, select = from the Leading pop-up menu. (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

2 In the Leading text box, enter a value in points to set leading to the exact size specified, and press Enter (Windows) or Return (Macintosh).

To specify leading for selected text as a percentage of the current point size:

1 Do one of the following:

• Select Text > Leading > Other to display the Leading dialog box, and select Percentage from the pop-up menu.

• In the Text toolbar, select % from the Leading pop-up menu.

• From the Character options in the Object panel, select % from the Leading pop-up menu. (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

2 In the Leading text box, enter a leading value as a percentage of the current point size, and press Enter (Windows) or Return (Macintosh). To specify leading equal to the current point size, enter **100**.

To modify kerning for selected text directly in the workspace:

Drag a text block's side selection handle. Dragging away from the text block increases kerning, and dragging toward its center decreases kerning.

To specify kerning or range kerning:

1 Do one of the following:

• To specify kerning, click in a text block with the Text tool to set the insertion point between two characters.

• To specify range kerning, select the text to which you want to apply kerning.

2 Do one of the following:

• From the Character options in the Object panel, enter a value in the Kerning or Range Kerning text box to adjust spacing by a percentage of an em space, and press Enter (Windows) or Return (Macintosh). (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

Free|Hand   A͞V 25   % em

• Hold down Control+Alt (Windows) or Command+Option (Macintosh) and press the Right Arrow or Left Arrow key to increase or decrease kerning by 1 em space. Press Control+Alt+Shift (Windows) or Command+Option+Shift (Macintosh) while using an arrow key to increase or decrease kerning by 10% of an em space.

To specify baseline shift, do one of the following:

1 Using the Text tool, select a character or range of characters.

2 Do one of the following:

• From the Character options in the Object panel, enter a value in the Baseline Shift text box, then press Enter (Windows) or Return (Macintosh). (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

FreeHand   AA 0

Free^Hand   AA 10

• Hold down Control+Alt (Windows) or Control+Option (Macintosh) and press the Up Arrow or Down Arrow key to raise or lower the baseline.

Note: To create footnotes and superscript special characters such as ™, raise the baseline and reduce the font size.

Spacing characters and words precisely

Using the Text Spacing options in the Object panel, you can precisely space words and characters. You can scale text horizontally, adjust word or letter spacing, and keep specified lines or words from separating:

- Scaling horizontally modifies the character shapes but not the character spacing or height; you can make the text wider or narrower without changing the text's height.

- Adjusting word spacing changes the amount of space between words to fall within a specified range, measured as a percentage of standard spacing. Adjusting word spacing does not affect letter spacing.

- Adjusting letter spacing changes the amount of space between letters to fall within a specified range, measured as a percentage of standard spacing. Adjusting letter spacing does not affect word spacing.

   Note: You can also use Range Kerning to adjust the space between characters, measured as a percentage of an em space in the current font. For more information, see "Setting alignment, leading, range kerning, and baseline shift" on page 253.

- Keeping lines or words from separating allows you to prevent widow and orphan lines—short lines on their own at the beginning or end of a column, text block, or page—and prevent specified word groups from breaking apart at line breaks.

To scale characters horizontally:

1 Select a text block with the Pointer tool or a range of text with the Text tool.

2 Display the Spacing options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 Enter a Horizontal scale value as a percentage of the standard scale. A value larger than 100 widens the text; a value smaller than 100 narrows the text.

To adjust spacing between words or letters:

1 Select a text block with the Pointer tool or a range of text with the Text tool.

2 Display the Spacing options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 Under Spacing, enter minimum, maximum, and optimal values for words and letters.

Adjusting word spacing

Values are measured as a percentage of standard word spacing for the current font. For Word Spacing, 100% is standard spacing; values smaller than 100 move words closer together, and values larger than 100 move words farther apart. For Letter Spacing, 0% is standard spacing; negative values move letters closer together, and positive values move letters farther apart.

Entering minimum and maximum values allows FreeHand to apply a range of spacing. To control spacing precisely, enter the same values for the Min., Opt., and Max. text boxes.

To keep a specified number of lines together at the end of a column or linked text block:

1 Select a text block with the Pointer tool or a range of text with the Text tool.

2 Display the Spacing options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 For Keep Lines Together, enter the number of lines to be kept together. Enter a value of at least 2 to prevent the first or last line of a paragraph from being isolated at the bottom or top of a column or linked text block.

To prevent line breaks in selected text:

1 Select a range of text with the Text tool.

2 Display the Spacing options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 Select the Selected Words option.

> **Note:** You can also insert a nonbreaking space to prevent two words from breaking apart at a line break. For more information, see "Inserting special characters" on page 242.

Selecting, finding, and replacing type attributes

You can find and replace text with certain type attributes (such as fonts, font styles, and point sizes) by using the Select panel and the Find & Replace panel.

To find and replace text, you use the Find Text dialog box (see "Finding and replacing text" on page 247).

To select type attributes:

1 Do one of the following to display the Find & Replace panel:

- Select Edit > Find and Replace > Graphics.

- Click the Graphics button in the Main toolbar.

2 Click the Select tab.

3 Select Font from the Attribute pop-up menu.

4 Select an option from the Search In pop-up menu to define the scope of the search—Selection, Page, or Document.

5 If you chose Selection in step 4, select the Remove from Selection option to remove text blocks with specified attributes from a current selection. If you chose Page or Document in step 4, select the Add to Selection option to add text blocks with specified attributes to a current selection.

6 Select a font from the font menu. To select all fonts in a document, select Any Font.

7 Select a style from the style menu. To select fonts in all styles, select Any Style.

8 Enter minimum and maximum values for a range of type sizes to select. To select a specific point size, enter a minimum value only. To select all type sizes, clear the Min. and Max. text boxes.

9 Click Find.

The number of text block objects selected appears in the lower left corner of the panel.

To find and replace type attributes:

1 Do one of the following to display the Find & Replace panel:

- Select Edit > Find and Replace > Graphics.

- Click the Graphics button in the Main toolbar.

2 In the Find & Replace panel, select Font from the Attribute pop-up menu.

3 Select an option from the Change In pop-up menu to define the scope of the search—Selection, Page, or Document.

4 Select a font from the font menu in the From section. To search all fonts in a document, select Any Font.

5 Select a style from the style menu in the From section. To search fonts in all styles, select Any Style.

6 Enter minimum and maximum values to specify a range of type sizes to search. To search for a specific point size, enter a minimum value only. To search all type sizes, clear the Min and Max text boxes.

7 Select a font from the font menu in the To section to determine what the original font will be changed to. To keep the font the same and change style or type size only, select No Change.

8 Select a style from the style menu in the To section. To keep the style unchanged, select No Change.

9 Enter a value for Change to determine the type size that the original type will be changed to. To keep the type size the same, clear the Change text box.

10 Click Change.

The number of objects changed appears in the lower left corner of the panel.

Setting tabs, indents, and margins

Tabs, indents, and margins can help you to control text formatting. In addition to setting these elements, you can position text relative to left, right, top, or bottom text block edges. You can also adjust spacing between paragraphs.

To set tabs, you must display the text ruler. For more information, see "Selecting text" on page 238.

Setting tabs

You can align text by using default tabs or by adding tabs. You can also add tab leaders, which are repeating characters (such as dots) that fill the space between tabbed elements. You can create a custom leader using a character of your choosing.

Default tabs left-align at 1/2-inch intervals, regardless of the unit of measure for the document. When you place a new tab, the default tabs to the left of the new tab are deleted. You can select from five kinds of tabs on the text ruler: left-align, right-align, center-align, decimal-align, and wrapping tabs.

Left-align tab
Right-align tab
Center-align tab
Decimal-align tab
Wrapping tab

Default tab marker   Right indent marker

Left indent marker

First-line indent marker

You can track tab placement with a vertical line in the text block as you drag a tab on the ruler.

To set tabs manually:

1 Using the Text tool, click to set an insertion point where you want to apply tab settings, or drag to select text.

2 Drag a tab marker from the text ruler to its new location in the area just above the numbers:

- Drag the left-align tab to align the left edge of the text to the tab marker.

- Drag the right-align tab to align the right edge of the text to the tab marker.

- Drag the center-align tab to align text to the center of the tab marker.

- Drag the decimal-align tab to align text at the decimal point. If the text does not contain a decimal point, the tab right-aligns the text.

Decimal and right-align tabs

- Drag the wrapping tab to make multiple columns of text flow between two tab markers.

Wrapping and left-indent tabs

Tip: To define a space between two columns created with wrapping tabs, place a wrapping tab on each side of a column, and then place another one at the beginning of the next column.

3 To align text to the new tab setting, click in the text where you want to place the tab, and press Tab.

To set tabs precisely:

1 Using the Text tool, click to set an insertion point where you want to apply tab settings, or drag to select text.

2 Double-click the text ruler to display the Edit Tab dialog box.

3 In the Edit Tab dialog box, set the following options:

• For Alignment, select the type of tab: Left, Right, Center, Decimal, or Wrapping.

• For Position, enter a number in points for the tab's location, measured from the left side of the text block.

4 Click OK.

5 Repeat steps 2 through 4 to set additional tabs.

6 To align text to the new tab setting, place an insertion point in the text where you want to place the tab, and press Tab.

To add a tab leader:

1 Double-click an existing tab marker or the text ruler to display the Edit Tab dialog box.

2 In the Edit Tab dialog box, do one of the following:

• Select a tab leader from the Leader pop-up menu.

• To enter a custom leader, select the Leader text box, and enter a character.

3 Click OK.

Note: Tabs and tab leaders cannot be used in text on a path. Tab leaders cannot be used with wrapping tabs.

To delete a tab:

Drag the tab arrow off the text ruler, or back to the tab area.

To move a tab to a new position:

Drag the tab arrow along the ruler to the desired position.

To track tab placement with a vertical line in the text block:

1 Display text preferences by doing one of the following:

- In Windows, press Control+U, then click the Text tab.

- On the Macintosh, press Command+U, then click the Text category.

2 Select Track Tab Movement with Vertical Line (the default setting) to display a vertical highlight line in the text block as you move a tab on the text ruler. Deselect the option to hide the tracking line.

3 Click OK.

Setting paragraph indents, paragraph spacing, margins, and insets

You can set paragraph indents and margins using the text ruler or the Object panel. You can also apply hanging indents, and hanging punctuation marks, such as quotation marks, outside paragraph margins.

Left indent marker

Right indent marker

First-line indent marker

To set paragraph indents using the text ruler:

1 Using the Text tool, click to set an insertion point where you want to apply indent settings, or drag to select text.

2 Drag an indent marker from the text ruler to its new location in the area just above the numbers, as follows:

• Drag a first-line indent marker to set the indent of the first line independently of the rest of the paragraph.

• Drag the left indent marker to set the left paragraph margin.

• Drag the right indent marker to set the right paragraph margin.

First-line indent, left paragraph margin, and right paragraph margin

To set a hanging indent using the text ruler:

1 Using the Text tool, click to set an insertion point or drag to select a paragraph or paragraphs.

2 If the text ruler isn't visible, select View > Text Rulers to display it.

3 In the text ruler, drag the left indent marker to the right to set the paragraph indent, and drag the first-line indent to the left to set a negative first-line indent.

To apply hanging punctuation:

1 Using the Text tool, click to set an insertion point or drag to select text.

2 Display the Paragraph options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 Select Hang Punctuation to position punctuation marks outside the text block margins.

Note: Only certain punctuation marks will hang.

To set left and right or first-line paragraph indents using the Object panel:

1 Using the Text tool, click to set an insertion point where you want to apply margin settings, or drag to select text.

2 Display the Paragraph options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 To set left and right indents, enter values in points in the Left Indent and Right Indent text boxes.

Positive numbers place text inside the column or text block, and negative numbers place text outside the column or text block.

Space above

Space below

Left indent

Right indent

First line indent

4 To set a first-line indent, enter a value in points in the First Line Indent text box.

To add spacing above or below a paragraph break:

1 Using the Text tool, click to set an insertion point where you want to insert space, or drag to select text.

2 Display the Paragraph options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 Enter a value in points in the Space Above text box, the Space Below text box, or both.

A positive value moves paragraphs farther apart; a negative value moves them closer together.

To apply left, right, top, and bottom margins using the Text Block property:

1 Using the Pointer tool, select a text block.

2 From the Properties list in the Object panel, select the Text Block property if it's not already selected.

3 In the bottom half of the Object panel, under Inset, enter values for left (l), right (r), top (t), and bottom (b).

An Inset value of 0 (zero) positions text against the text block border. Positive values position text inside the text block border, and negative values position text outside the text block border.

Note: When you work with text on a path, you can set only left and right values. For more information about adjusting the position of text on a path, see "Aligning text on a path" on page 278.

Aligning paragraphs and adding paragraph rules

To control how text spreads across the width of the column, you can align paragraphs in text columns. You can also add rules between paragraphs to offset paragraphs visually.

Aligning paragraphs

To precisely control how paragraphs align and to fine-tune the length of lines of justified text, you use the Object panel. You can align text by a ragged width, spreading it over a column. Ragged width specifies the minimum distance nonjustified text spreads over a column and is expressed as a percentage of the column's width. You can also align text with a flush zone that specifies the justification of the last line of a paragraph.

To adjust a text column's ragged width:

1 Select a text block with the Pointer tool or a range of text with the Text tool.

2 Display the Character options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 Click the Edit button to display the Edit Alignment dialog box.

4 In the Edit Alignment dialog box, enter a percentage for Ragged Width to justify text, from 0 for no justification to 100 for the full column width. For example, a value of 95 expands a line to fill 95% of the column width.

5 Enter a percentage in the Flush Zone text box to specify the point at which the last line in a paragraph justifies. For example, if you enter 50%, the last line justifies only if it is at least 50% as long as the column's width.

6 Click OK.

Adding paragraph rules

To provide a stronger visual break between paragraphs, you can apply paragraph rules, or lines below paragraphs. You select the line weight, color, and style for paragraph rules using the options for the Stroke property in the Object panel.

A paragraph rule flows with its paragraph. You can center paragraph rules in the column or text block, or align paragraph rules to the preceding paragraph.

To apply paragraph rules:

1 Select a text block with the Pointer tool or select paragraphs with the Text tool.

2 Display the Paragraph options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 Select an option from the Rules pop-up menu:

Centered places a rule that is centered in the column or text block.

Paragraph applies a rule of the same alignment as the paragraph above it.

4 From the Properties list in the Object panel, select the Text Block property.

5 Click the Add Stroke button near the top of the panel.

Note: Rules won't appear until a stroke has been added to the text block.

6 Use the options in the bottom half of the panel to apply a style, stroke weight, and color to the Stroke property, which affects the appearance of paragraph rules. For more information, see "Applying attributes to strokes" on page 166.

7 (Optional) From the Properties list in the Object panel, select the Text Block property; then deselect Display Border in the bottom half of the panel. This action removes the text block border that appeared when you applied a stroke. If you want to keep the text block border, leave this option selected.

To edit paragraph rules:

1 Select a text block with the Pointer tool or select paragraphs with the Text tool.

2 Display the Paragraph options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 Select Edit from the Rules pop-up menu.

4 In the Paragraph Rule Width dialog box, enter a percentage value to change the width of the rule.

5 Select an option from the pop-up menu:

Last line sizes the rule to a percentage of the last line in a paragraph.

Column sizes the rule to a percentage of the width of the column.

6 Click OK.

Applying color to text and text blocks

You can apply stroke and fill colors to text and text blocks, using the Stroke and Fill properties in the Object panel. To show or hide strokes and fills applied to text blocks, you use the Display Border option of the Text Block property in the Object panel. You can also set preferences to determine whether colors selected in the Swatches panel are applied to text or to text blocks.

For detailed instructions on applying color, see "Working with Color" on page 147.

To apply a fill color to a range of text:

1   Using the Text tool, select the text inside the text block.

2   Select Window > Color Mixer and Window > Swatches to display those panels if they are not already displayed.

3   Drag a color from the Color Mixer or Swatches panel onto the Text Fill property's color box in the Object panel.

To apply a stroke color to a range of text:

1   Using the Text tool, select the text inside the text block.

2   Click the Add Stroke button near the top of the Object panel.

3   Select Window > Color Mixer and Window > Swatches to display those panels if they are not already displayed.

4   Drag a color from the Color Mixer or Swatches panel onto the Text Stroke property's color box in the Object panel.

To apply a stroke or fill color to a text block:

1   Using the Pointer tool, select the text block.

2   Select Window > Color Mixer and Window > Swatches to display those panels if they are not already displayed.

3   Do one of the following:

•   Click the Add Stroke button near the top of the Object panel.

•   Click the Add Fill button near the top of the Object panel.

4   In the bottom of the Object panel, select a style from the pop-up menu, and select any associated options. (For more information, see "Applying attributes to strokes" on page 166 or "Applying attributes to fills" on page 177.)

5   Do one of the following:

•   Drag a color from the Color Mixer or Swatches panel onto the color box of the Stroke or Fill property you added in the Properties list.

•   Drag a color from the Color Mixer or Swatches panel onto the text block border or the text block interior.

Note: If you can't see your text after applying a fill to the text block, you may need to reorder the properties in the Properties list.

To show or hide stroke and fill colors applied to selected text blocks:

1 From the Properties list in the Object panel, select the Text Block property.

2 In the bottom half of the Object panel, select Display Border to show strokes and fills applied to text blocks. Deselect the option to hide the strokes and fills.

To remove a stroke or fill from text:

1 Select the entire text block with the Pointer tool or a range of text with the Text tool.

2 Select the Stroke or Fill property you want to remove in the Properties list of the Object panel.

3 Click the Delete button near the top of the Object panel.

To control how the Swatches panel selectors apply color to selected text or text blocks:

1 Display color preferences by doing one of the following:

• In Windows, press Control+U, then click the Colors tab.

• On the Macintosh, press Command+U, then click the Colors category.

2 Select a Color List Shows option:

Container Color displays the stroke and fill attributes of selected text blocks and applies color to the selected text block, not the text.

Text Color displays the stroke and fill attributes of selected text and applies color to the selected text, not the text blocks.

3 Click OK.

Copying type attributes

You can copy type attributes from one text selection to another by copying and pasting. Attributes you can copy include the Character, Paragraph, and Spacing options in the Object panel, as well as tabs, indents, margins, and text fill and stroke colors.

To copy and paste type attributes between text selections:

1 Use the Pointer tool to select a text block whose attributes you want to copy, or use the Text tool to select a range of text.

2 Select Edit > Special > Copy Attributes.

3 Select the text or text block to which you want to apply the attributes.

4 Select Edit > Special > Paste Attributes.

Working with columns, rows, and tables

You can format text into columns and rows. Using columns and rows or tabs and paragraph breaks, you can create tables. You can balance text in columns to control how the text flows across a group of columns.

Creating columns and rows

You can create multiple columns and rows in text blocks.

Using columns and rows, you can create a table with cells of uniform size. To create tables with cells of varying sizes, you use tabs, paragraph breaks, and paragraph spacing.

You can add lines between rows using paragraph rules, and apply a stroke to the rules using the Stroke property in the Object panel.

Note: To create forms, you can create tables with blank cells for users to fill with data.

To create columns or rows:

1   Using the Pointer tool, select the text block in which you want to create columns or rows.

2   Display the Columns and Rows options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3   To create columns, enter the number of columns in the Columns text box.

4   Enter a value for Height (h) in points to specify the height of the columns.

5   Enter a value for Spacing in points to specify the width of the space between columns.

6   To add rules between columns, select an option from the Rules pop-up menu:

- Select Inset to create rules the length of the inset text as specified by the Text Block property in the Object panel. For more information, see "Setting paragraph indents, paragraph spacing, margins, and insets" on page 264.

- Select Full Height to create rules the height of the full column (regardless of the height of inset text).

   Note: To apply a stroke to the rules, see the procedure that follows.

7   To create rows, enter the number of rows in the Rows text box.

8   Enter a value for Width (w) in points to specify the width of the rows.

9   Enter a value for Spacing in points to specify the height of the space between rows.

10 To add rules between rows, select an option from the Rules pop-up menu:

- Select Inset to create rules the width of the inset text as specified by the Text Block property in the Object panel.

- Select Full Width to create rules the width of the full row.

   Note: To apply a stroke to the rules, see the procedure that follows.

11 To move text automatically to the top of the next column, place an insertion point with the Text tool and select Text > Special Characters > End of Column.

12 For Flow, click a button to specify how text flows across columns and rows: down all rows in the first column and then into the second column, or across all columns in the first row and then into the second row.

To apply a stroke to table rules or table borders:

1 Using the Pointer tool, select the text block.

2 From the Properties list in the Object panel, select the Text Block property.

3 Select Display Border in the bottom half of the Object panel if you want the table's outer border to display. This option is selected by default.

4 Click the Add Stroke button near the top of the Object panel.

5 In the bottom half of the panel, select a stroke style from the pop-up menu, and select options for the stroke. (For more information, see "Applying attributes to strokes" on page 166.)

6 Select Window > Color Mixer and Window > Swatches to display those panels if they are not already displayed.

7 Drag a color from the Color Mixer or Swatches panel onto the color box of the Stroke property you added to the Properties list, or drag a color onto the text block border.

To create a table with uniform cells using columns and rows:

1 Using the Pointer tool, select the text block.

2 Create columns and rows as described earlier in this section, with the following specifications:

- Set Spacing for Columns and Rows to **0**.

- For Column Rules, select Full Height, and for Row Rules, select Full Width.

To create a table with variable cells using tabs and paragraph breaks:

1 Drag with the Text tool to create a text block the size of the table.

2 Drag left-align tabs to define the left edge of each column. For more information on setting tabs, see "Setting tabs, indents, and margins" on page 261.

3 Drag wrapping tabs to define the right edges of columns that contain more than one line of text.

Flower	Number	Color
Carnation	7,688 (20% lost due to spoilage)	Yellow with blue accents
Rose	10,755	Red
Tulip	34	Yellow

4 Press Enter (Windows) or Return (Macintosh) to create rows.

5 To change the distance between rows, adjust the paragraph spacing using the Paragraph options in the Object panel. (For more information, see "Setting paragraph indents, paragraph spacing, margins, and insets" on page 264.)

Flower	Number	Color
Carnation	7,688 (20% lost due to spoilage)	Yellow with blue accents
Rose	10,755	Red
Tulip	34	Yellow

6 To add lines between rows, add paragraph rules. For more information, see "Adding paragraph rules" on page 268.

7 To apply a border to the table, see the procedure above for applying a stroke to table rules or borders.

Balancing columns of text

The Adjust Columns options in the Object panel let you copyfit text by balancing text among columns, modifying leading, or altering the text size and leading proportionally to fit the selected text block.

You can also use the Adjust Columns options to make text inside an irregular object fit that object exactly.

To insert a break in a column and force text into the next column:

1 Using the Text tool, place an insertion point in the column where you want the text to break.

2 Select Text > Special Characters > End of Column.

To balance lines of text evenly among columns:

1 Use the Text tool to place an insertion point where you want to apply text balancing, or use the Pointer tool to select a text block.

2 Display the Adjust Columns options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 Select one of the following:

Balance distributes lines of text evenly among columns. If the number of lines is not evenly distributed among columns, some columns will have more lines than others.

Modify Leading adds leading so that text fills the column from top to bottom. For Threshold, enter the percentage a column must fill before modified leading is applied. For example, with a threshold of 50% (the default setting), extra leading is applied only to those columns that are at least 50% filled with text.

4 To reduce or enlarge text size and leading to fit the column size, enter minimum and maximum values for Copyfit %, measured as a percentage of the current size. Values larger than 100% increase text and leading size; values smaller than 100% decrease text and leading size.

5 For First Line Leading, select an option to enter a value for the space above the first line in a column:

- To specify First Line Leading as a point value to be added to the current type size, select + from the pop-up menu and enter a value in points for the amount of leading you want to add to the current type size.

- To specify First Line Leading as a fixed point value, select = from the pop-up menu and enter a value in points to set leading to the exact size specified.

- To specify First Line Leading as a percentage of the current type size, select % from the pop-up menu and enter a leading value as a percentage of the current type size.

Using text styles

You can use text styles to create sets of text formatting specifications that you can save and apply to multiple paragraphs or text blocks in a document. Text styles help you maintain visual consistency and simplify formatting tasks.

Text styles let you specify settings for all the type specifications of the Character, Paragraph, and Spacing options in the Object panel (except paragraph indents), as well as text effects, text color, overprinting, and tabs and indents set with the text ruler. (For information on overprinting, see "Printing" on page 375.)

You use the Styles panel and Object panel to create and edit text styles. Text styles appear in the Styles panel, and in the Styles pop-up menu of the Object panel's Character options. You can use styles as part of a document or template. For more information on templates, see "Using templates" on page 60.

You can create styles for objects as you do for paragraphs. You can duplicate, import, and export paragraph and graphic styles. For more information on these procedures, see "Using styles" on page 301.

To display the Styles panel:

- Select Window > Styles.

Creating and editing text styles

When you create a new text style, the style's settings are based either on the currently selected style in the Styles panel or on the attributes of the text selection in the document. You use the Object panel to enter new settings for the style, or to modify an existing style. In the Styles panel, you can rename new styles and existing styles.

When modifying a style, you can exclude specified attributes to preserve them when you apply the style. For example, you can create a style that does not change the font of the text to which it is applied.

You can also base a style on another style by making it the child of a parent style. For more information about parent and child styles, see "Basing one style on another" on page 306.

To create a new text style based on another text style:

1 In the Styles panel, select a text style from the list.

2 Click the Styles panel Options menu control and select New.

A new text style is added to the list. New styles are named Style-1, Style-2, and so on. To choose specifications for the style or rename the style, see the procedures below.

To create a new text style based on the current text selection in the document:

1 Use the Pointer tool to select a text block that has the desired attributes, or use the Text tool to select a range of text.

2 Click the Styles panel Options menu control and select New.

To edit a text style:

1 In the Styles panel, select the style in the list.

2 Select the Text property in the Object panel Properties list.

3 Make changes to the style's attributes in the bottom half of the Object panel.

All new text blocks you create using this style will reflect the attribute changes, until you select a different text style or further modify the default text attributes. To update the attributes of existing text blocks that possess this style, you must redefine the style. For more information, see "Overriding and redefining text styles" on page 277 and "Changing default attributes" on page 146.

For information on selecting type formatting options, see "Setting precise type specifications" on page 250, "Setting tabs, indents, and margins" on page 261, and "Applying text effects" on page 278.

To preserve settings for specified attributes when applying a text style:

1 In the Styles panel, select the style in the list.

2 Click the Styles panel Options menu control and select Style Behavior.

3 In the Edit Style dialog box, do any of the following:

• To preserve Font, Font Style, Leading, Text Effects, or Rules settings, select No Selection from the respective pop-up menu.

   Note: Selecting None in the Rules pop-up menu removes all paragraph rules in paragraphs to which the style is applied. Selecting No Effect in the Text Effect menu removes all text effects.

• To preserve Justification, click the Blank button in the button bar.

• To preserve color, deselect the Style Affects Text Color option.

• To preserve hanging punctuation, select Hang Punctuation until a dimmed check mark (Windows) or hyphen (–) (Macintosh) appears. (An empty checkbox indicates that hanging punctuation is turned off.)

• To preserve size and spacing settings (Point Size, Paragraph Spacing, Spacing %, Range Kerning, Baseline Shift, and Horizontal Scale), clear the respective text boxes.

• To preserve Tabs and Margins, select No Selection in the text ruler.

- To change settings globally, select one of the following from the Global Settings pop-up menu:

  No Settings clears all settings.

  Restore Original Values reverts any settings you changed in the previous step to their original values.

  Restore Program Defaults changes all settings to the default FreeHand text settings (the settings for Normal Text).

4 Click OK.

To rename a text style:

- In the Styles panel, double-click the style name in the list and enter the new name.

  Note: You cannot rename the Normal Text style.

To set the text style of subsequent paragraphs:

1 Select the style in the Styles panel.

2 Click the Styles panel Options menu control and select Style Behavior.

3 Select a style from the Next pop-up menu.

4 Click OK.

Applying text styles

You can apply styles to text by selecting the style in the Styles panel, dragging the style from the Styles panel, or copying and pasting attributes from selected text.

To apply a text style, do one of the following:

- Use the Pointer tool to select a text block to which you want to apply a style, or use the Text tool to select a paragraph. In the Styles panel, click the style you want to apply.

- Drag the style preview from the Styles panel onto a paragraph.

  Note: To specify whether dragged styles are applied to selected paragraphs or entire text blocks, see the next procedure.

- From the Character options in the Object panel, select a style from the Style pop-up menu. (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

To set the behavior for dragging a text style:

1 Display text preferences by doing one of the following:

- In Windows, press Control+U, then click the Text tab.

- On the Macintosh, press Command+U, then click the Text category.

2 Select an option for Dragging a Text Style Changes:

- To apply a style to a selected paragraph only (not to the entire text block), select Single Paragraph (the default setting).

- To apply a style to an entire text block, select Entire Text Container.

3 Click OK.

To apply text style attributes by copying and pasting:

1 Select the text whose attributes you want to copy, and select Edit > Special > Copy Attributes.

2 Select the text to which you want to apply the attributes, and select Edit > Special > Paste Attributes.

Note: You can also use this method to copy attributes of text that has no text style applied.

Overriding and redefining text styles

You can override settings for individual attributes in selected text, and you can remove an override to restore the style settings in the selection. You can also use a text selection as the basis for redefining a style.

To override a text style setting:

1 Select a text block with the Pointer tool, or select a paragraph with the Text tool.

2 Change any text attribute.

When you select the modified text, the style name appears in the Styles panel (or in the Styles pop-up menu in the Character options of the Object panel) with a plus (+) sign to indicate that an attribute has been changed.

To remove a text style override:

1 Use the Pointer tool to select the text block that has a style override, or use the Text tool to select a paragraph.

2 In the Styles panel, click the style that is applied to the selection.

The original style is applied to the text, restoring any modified attributes to those of the original style.

To redefine a text style based on selected text:

1 Use the Pointer tool to select the text block with the attributes that you want to use for defining a style, or use the Text tool to select a paragraph.

2 Click the Styles panel Options menu control and select Redefine.

3 In the Redefine style dialog box, select the name of the style you are redefining, and click OK.

The style assumes the attributes of the selected text.

To specify how a selection's attributes are applied to a redefined text style:

1 Display text preferences by doing one of the following:

• In Windows, press Control+U, then click the Text tab.

• On the Macintosh, press Command+U, then click the Text category.

2 Select an option for Build Text Styles Based On:

First Paragraph bases a redefined text style on the first paragraph in a selection.

Shared Attributes bases a redefined text style on the common attributes of a range of selected paragraphs.

3 Click OK.

Applying text effects

In FreeHand, you can create many effects with text. You can attach and align text to a path, wrap text around graphics, create inline graphics, and apply built-in special text effects such as shadows and underlines.

Attaching text to paths

You can align text to a path that is open or closed, with curve or corner points. The text can be linked to other paths or text blocks. Type specifications of text attached to a path remain intact. You can apply transformations to text attached to a path as you would any other object.

You can flow two lines of text on a closed path. The characters up to the first carriage return flow along the top of the path, and the characters from there to the second carriage return flow along the bottom of the path. On an open path, only characters up to the first carriage return or tab appear. An indicator dot appears in the text's link box if the text overflows the path. Left-aligned text on a curved path is respaced automatically to avoid overlapping letters.

You can also make text flow inside a path; see "Flowing text inside a path" on page 280.

To attach text to a path:

1 Using the Pointer tool, Shift-click to select a text block and a path.

2 Select Text > Attach to Path, or click the Attach to Path button on the Text toolbar.

You can edit text directly on the path or use the Text Editor; see "Using the Text Editor" on page 241.

To place text on the top and bottom of an ellipse:

1 Position the Text tool in a text block at the point where the text should split between the top and bottom of the ellipse, and press Enter (Windows) or Return (Macintosh) to insert a carriage return.

2 Using the Pointer tool, Shift-click to select the text block and an ellipse.

3 Select Text > Attach to Path.

4 If necessary, do one of the following:

- If the text disappears, review the selected options in the Top and Bottom alignment pop-up menus in the Object panel. If None is selected for both, text will not be visible on the path.

- If the text flows in the wrong direction, Alt-click (Windows) or Option-click (Macintosh) the path to select it. (It's easiest to select the path in this manner when Keyline mode is active or if the Show Path option is selected in the Object panel.) Then select Modify > Alter Path > Reverse Direction.

Aligning text on a path

You can adjust the alignment and orientation of text on a path by using the Object panel.

Text flows in the direction of the path, from left to right (clockwise) or from right to left (counterclockwise). To reverse the direction of the text, you reverse the direction of the path. For more information, see "Attaching text to paths" on page 278.

To adjust alignment and orientation of text on a path:

1   Using the Pointer tool, select the text on a path in the workspace.

2   Select Window > Object to open the Object panel if it's not already open.

3   Select an Orientation option for the text—Rotate Around Path, Vertical, Skew Horizontal, or Skew Vertical.

Rotate Around Path, Vertical, Skew Horizontal, and Skew Vertical text orientations

4   If you want the path to be visible, select Show Path.

5   In the Alignment section, choose which part of the text aligns to the top and bottom of the path—None, Baseline, Ascent, or Descent.

From left to right: Text aligned by baseline, ascent, and descent to the top of a path

For information about altering the position of text along the path, see the following procedures.

To move text on a path manually:

1 Place an insertion point with the Text tool, or select the path with the Pointer tool.

A triangular text handle appears to the left, center, or right of the text, depending on the text alignment. To display text as it moves on the path, hold down Alt (Windows) or Option (Macintosh) as you drag the text handle.

2 Drag the triangular handle to move the text along the path.

The position of the text updates the values in the Left and Right alignment boxes in the Object panel.

To move text on a path a precise distance:

1 Place an insertion point in the text with the Text tool, or select the path with the Pointer tool.

2 In the Object panel, enter a value in the Left or Right alignment box.

Flowing text inside a path

You can make text flow inside any open or closed path. You can edit text that flows inside a path without removing it from the path, and you can transform text that flows inside a path as you would any other object.

You can also wrap text around paths and objects. For more information, see "Wrapping text around objects" on page 281.

To flow existing text inside a path and apply an inset:

1 Use the Pointer tool to select both a text block and a closed path.

2 Select Text > Flow Inside Path, or click the Flow Inside Path button in the Text toolbar.

3 To adjust the text's placement within the path, enter values in the Inset text boxes of the Object panel to define the margins between the text and the path. If necessary, select Display Border to make the path visible, or switch to Keyline mode.

When you select a path with text flowed inside it, a box is displayed below the path. A dot in the box indicates overflow text.

Detaching text from a path

To remove text to which you've applied the Attach to Path or Flow Inside Path command, you use the Detach from Path command.

To remove text from a path:

1 Using the Pointer tool, select the path.

2 Select Text > Detach from Path, or click the Detach from Path button in the Text toolbar.

The command creates two objects: the text block and the path. Any transformations are removed, and the original text block's size is modified to match the width of the path.

Wrapping text around objects

You can wrap text automatically around a single object, including imported graphics and composite paths, using the Flow Around Selection command. The command is applied to objects, not to text blocks. However, you can use this technique with text blocks to create pull quotes and other text treatments.

You cannot flow text around a group or blend. You can, however, draw a path around such objects and then wrap the text around the path.

Flow Around Selection applied

To wrap text around an object:

1 Select the object in the document, and position it so that it overlaps the text.

2 Select Modify > Arrange > Bring to Front. The object around which you want to wrap the text (whether it is a regular object, another text block, or the path you drew around an object) must be in front of the text.

3 Do one of the following:

• To wrap text around a graphic object, select the object. If the object is a group, blend, or OLE image, draw a path around it first, and then select the path and the object.

• To wrap text around another text block (to create a pull quote or other effect), apply Inset settings in the Object panel to inset the text from its text block border. Optionally, apply a stroke to display the text block border. Then select the text block around which you want to wrap the text. For more information on applying strokes and inset settings, see "Applying color to text and text blocks" on page 269 and "Insetting a path" on page 135.

4 With the object still selected, select Text > Flow Around Selection or click the Flow Around Selection button in the Text toolbar.

5 In the Flow Around Selection dialog box, click the Text Wrap button.

Flow Around Selection

Standoff
Left: 0
Right: 0
Top: 0
Bottom: 0

OK   Cancel

6 For Standoff, enter the minimum distance between the selected object and the text that wraps around it.

Positive numbers begin text flow outside the selected object. Negative numbers overlap text behind the selected object. Values are in the document's unit of measure.

7 Click OK.

To remove a text wrap from an object:

1 Using the Pointer tool, select the object with the text wrap.

2 Select Text > Flow Around Selection or click the Flow Around Selection button in the toolbar.

3 Click the Remove Text Wrap button and click OK.

Working with inline graphics

An inline graphic is an object pasted into a text block and anchored to move with the text flow. The inline graphic becomes a text character; reflowing the text also reflows the inline graphic. The point size of the inline graphic is equal to its original height.

Inline graphics retain their original graphic attributes when placed in a text block and aren't affected by changes to text strokes and fills. You cannot apply a text effect, font, or type style to an inline graphic. Inline graphics have a bounding box that acts as the border between the graphic and the text.

An inline graphic pasted into a transformed text block assumes the text's transformations. If you want the graphic to retain its assigned attributes, you need to transform the inline graphic before pasting it in the text block.

When you use the Text Editor to edit text containing an inline graphic, the inline graphic appears in the Text Editor as a black dot.

Note: If you add an inline graphic to a paragraph that has a text style applied, the Styles panel displays a plus (+) sign next to the name of the assigned text style to indicate an override. Removing the override adjusts the inline graphic proportionally to match the style's font size. For more information, see "Overriding and redefining text styles" on page 277.

To place an inline graphic in text:

1 Using the Pointer tool, select the object you plan to use for the inline graphic.

   If you're using text blocks or text attached to paths as inline graphics, group them to avoid having the text appear as individual characters when pasted.

   If desired, transform the inline graphic before pasting it so that the graphic retains the transformation.

2 Select Edit > Copy or Edit > Cut.

3 Place an insertion point in an existing text block, and select Edit > Special > Paste Special.

4 In the Paste Special dialog box, select the format for the pasted graphic.

5 Click OK.

To remove an inline graphic:

1 Using the Text tool, select the inline graphic.

   When an inline graphic is selected, the Graphic option is selected in the Effects pop-up menu in the Object panel.

2 Select Edit > Cut or press the Delete key.

Positioning inline graphics

You can edit the point size, paragraph spacing, word and letter spacing, baseline shift, alignment, leading, and horizontal scale of an inline graphic. To adjust type attributes, you use the Text menu, the Object panel, or the Text toolbar.

To position an inline graphic:

1   Using the Text tool, select the inline graphic. If you want, you can also select any surrounding text.

2   Use the Text menu, the Object panel, or the Text toolbar to adjust the following type attributes:

• Adjust leading at the insertion point to accommodate the graphic's height. By default, the bottom of an inline graphic is aligned with the text baseline.

• Use kerning to move the inline graphic and the text characters that immediately surround it closer together (with a negative value) or farther apart (with a positive value).

• Adjust baseline shift to move the inline graphic below (negative value) or above (positive value) the baseline of the surrounding text.

    For more information about adjusting leading, kerning, and baseline shift, see "Setting alignment, leading, range kerning, and baseline shift" on page 253.

3   Adjust the text wrap by entering Inset values in the Object panel when the Text Block property is selected in the Properties list.

Text wraps flush with the graphic's left edge and leaves a slight space at the right edge of the inline graphic's bounding box.

Applying text effects

FreeHand provides six text effects: highlight, inline, shadow, strikethrough, underline, and zoom. You can set options for all text effects. You can also search for occurrences of a text effect in a document.

First row: highlight, inline, and shadow effects; second row: strikethrough, underline, and zoom effects

Applying text effects can make redrawing slower as you work with documents. You can set options to avoid this problem when editing. In addition, text effects may be lost when printing to non-PostScript printers, converting to paths, or exporting to some file formats.

To apply a text effect with its default settings:

1 Select one or more text blocks with the Pointer tool or a range of text with the Text tool.

2 Display the Character options in the Object panel. For more information, see "Displaying type attributes in the Object panel" on page 248.

3 Select a text effect from the Effects pop-up menu at the bottom of the panel.

> *Note:* The Graphic effect is used for inline graphics only.

To set options for a text effect:

1 Using the Text tool, select text to which the effect has been applied.

2 Do one of the following:

- From the Character options in the Object panel, select Edit from the Effects pop-up menu. (For information on displaying Character options, see "Displaying type attributes in the Object panel" on page 248.)

- Select Text > Effect, and select the effect from the submenu.

   A dialog box appears for the effect you selected.

3 Set text effect options as described in the following procedures.

To edit the Highlight, Underline, and Strikethrough text effects, set the following options:

- For Position, enter a positive number for the effect's distance above the text baseline, or enter a negative number for the distance below the baseline.

- To apply a dash pattern, select a pattern from the Dash pop-up menu.

- For Stroke Width, enter the point size of the effect.

- To change the color of the effect, use the color pop-up menu.

- To compensate for slight misregistration when overprinting the original text, select Overprint.

To edit the Inline effect, set the following options:

- To specify the number of outlines that will surround the text, enter a number in the Count text box.

- For Stroke Width, enter the size of the stroke width.

- To change the stroke color, select from the color pop-up menu.

- For Background Width, enter the width of the background color that will appear between the stroke and the text.

- To change the background color, select from the color pop-up menu.

To edit the Shadow effect, set the following options:

- In the Offset X and Y text boxes, enter values to offset the shadow from the text.

- Select a shadow color from the Color pop-up menu, or click the color box and pick a color swatch.

- Drag the Tint slider or enter a value into the Tint box to define the tint percentage.

To edit the Zoom effect, set the following options:

- In the Zoom To text box, enter a percentage for the foreground object.

  For example, entering 50% reduces the foreground object by 50% of the original.

- In the Offset X and Y text boxes, enter the distance to move the foreground object from the original text.

- To change the color of the background object, use the From pop-up menu.

- To change the color of the foreground object, use the To pop-up menu.

To search for text effects applied in a document:

1 Do one of the following to display the Select panel:

- Select Edit > Find and Replace > Graphics.

- Click the Graphics button in the Main toolbar. Click the Select tab.

2 Select Text Effect from the Attribute pop-up menu.

3 Select an effect from the Effects menu.

4 For Search In, choose an option to define the scope of the search—Selection, Page, or Document.

5 If you chose Selection in step 5, select the Remove from Selection option to deselect text blocks with the specified effect from a current selection. If you chose Page or Document in step 5, select Add to Selection to add text blocks with the specified effect to a current selection.

6 Click Find.

  The number of objects selected appears in the lower left corner of the panel.

To increase screen redraw speed when using text effects, do one of the following:

- In Windows, press Control+U and click the Redraw tab; then deselect Display Text Effects.

- On the Macintosh, press Command+U and click the Redraw category; then deselect Display Text Effects.

- Assign text effects after typing text.

- Select View > Keyline to turn off Preview mode.

Converting text to paths

You can edit text as objects by converting the text to paths. Once the text is converted, you can edit the shape of individual characters, use converted text as a clipping path, apply complicated strokes and fills to the shape of a group of characters, and apply FreeHand and third-party Xtras that create special effects. However, you can no longer edit text converted to paths as text—for example, you can't change the spelling, type, or paragraph attributes.

Any PostScript Type 1 font, PostScript Type 3 font created with Macromedia Fontographer, or TrueType font installed on your computer can be converted to paths. Text in linked text blocks cannot be converted to paths unless you unlink the blocks.

Converting text to paths may affect the onscreen appearance of text characters, because the characters are no longer handled as type outlines by your system's type-handling utility.

Printing text converted to paths does not require that fonts be installed, but it may result in poor-quality output, especially at 12-point sizes and smaller.

You cannot convert paths back to text after you manipulate the paths. However, you can select Edit > Undo to reverse the conversion if you have not yet manipulated the paths or saved the file.

To convert text to paths:

1 Using the Pointer tool, select the text block you want to convert.

2 Select Text > Convert to Paths or click the Convert to Paths button in the Text toolbar.

   The following conversions occur:

- Text attached to a path remains in place, but the path disappears.

- The text in the text block converts to a group of objects.

- Letters with more than one component, such as the letter *i*, convert to composite paths. For more information on composite paths, see "Combining paths" on page 127.

- Letters with enclosed areas, such as *B* and *O*, convert to composite paths with transparent holes.

- All other letters, such as *L* and *Z*, convert to a single path.

3 To ungroup the converted text into individual, editable characters, select Modify > Ungroup.

4 To edit a selected word or phrase as a single object, select the characters that make up the word or phrase and select Modify > Group.

To work more efficiently in Macromedia FreeHand MX, you can use layers, symbols, and styles to organize your illustrations, automate your work, and make consistent changes.

Layers help you organize your illustrations, and styles help you maintain visual consistency and simplify formatting.

Symbols streamline the use of repetitive elements and minimize the size of files in which you use them.

Using layers

Layers separate objects in an illustration to make them easier to work with. Layers divide an illustration into discrete planes; this is similar to drawing an illustration's components on separate tracing paper overlays. By default, a new document contains three layers: Foreground, Guides, and Background. Importing and drawing occur on the active layer, which is initially the Foreground layer. When a new layer is added, it initially becomes the default drawing layer; any content you create or import appears on that layer until you move the content.

The Layers panel is divided by a horizontal separator bar. Layers above the separator bar—generically called foreground layers—are printable. Those below the separator bar—background layers—do not print.

The Guides layer contains guide lines dragged from the ruler or entered manually in the Guides Editor, as well as paths that have been converted to guides.

The Background layer appears by default below the separator bar, so it does not print. You can move other layers below the separator bar too, to make additional background layers. Objects on any background layer are dimmed onscreen. If you move a background layer above the separator bar, objects on it become fully visible onscreen and will appear when the document is printed.

Every object in an illustration resides on a layer; each layer can have multiple objects. You can edit only those objects on visible, unlocked layers.

By moving objects from one layer to another or rearranging layers, you can change how the objects overlay one another. Each layer maintains its own stacking order of objects (see "Arranging objects" on page 123). You can set preferences to control how objects can be moved between layers. For more information, see "Moving objects and reordering layers" on page 291.

Artwork and its layered components

Using the Layers panel

The Layers panel displays all layers in your document and lets you add, copy, arrange, and remove layers. You can use the Layers panel to select, create, and delete layers; hide and lock layers to avoid accidentally moving or deleting objects; merge layers; choose display and printing options for layers; and display guides to precisely align and place objects.

To display the Layers panel, do one of the following:

- Click the Layers button in the Main toolbar.

- Select Window > Layers.

To designate a layer as nonprinting, do one of the following in the Layers panel:

- Drag the layer below the separator line.

- Drag the separator line above the layer.

- Hide a layer by clicking the check mark beside it.

    Note: A hidden layer can still be printed, however, if the Include Invisible Layers option is selected in the Output Options dialog box. For more information, see "Viewing layers and layered artwork" on page 294.

Creating layers

To create new layers, you use the Layers panel. You can create all layers before creating your artwork or add individual layers as you need them. You can add new layers or duplicate existing ones.

To add a new layer:

1 Select Window > Layers to display the Layers panel if it's not already displayed.

2 Click the Layers panel Options menu control and select New.

To duplicate a layer and all objects on it:

1 Select Edit > Select > None or press Tab to deselect all objects. This prevents you from inadvertently moving selected objects to the new active layer.

Note: You can change the preference that causes selected objects to automatically move to the active layer. For more information, see "Moving objects and reordering layers" on page 291.

2 In the Layers panel, click a layer name to select it.

3 Click the Layers panel Options menu control and select Duplicate.

To rename a layer:

1 Double-click the layer name in the Layers panel.

2 Type a new name, and press Enter (Windows) or Return (Macintosh).

Selecting layers

You can use the Layers panel to select a layer, making it the active layer. In addition to selecting a layer, you can easily select all the objects on a layer.

To select a layer and make it active:

1 Select Edit > Select > None or press Tab to deselect all objects. This prevents you from inadvertently moving selected objects to the new active layer.

Note: You can change the preference that causes selected objects to automatically move to the active layer. For more information, see "Moving objects and reordering layers" on page 291.

2 Click the layer name.

A pen icon appears to the right of the active layer name. The next object you draw or import appears on this layer.

To select all objects on a single layer in a multilayer document:

Hold down Alt (Windows) or Option (Macintosh) and click the layer name.

Moving objects and reordering layers

To edit your artwork, you can change the way objects overlay one another in a document, move or copy objects from one layer to another, rearrange the order of the layers, and designate layers as nonprinting.

When copying and pasting objects on layers between FreeHand documents, you can retain the layer information.

You can group objects from different layers; all objects in the group move to the active layer. If grouped or joined objects were originally on different layers, you can also return the objects to their separate layers by ungrouping them. For more information on grouping, see "Grouping objects" on page 119.

To move an object to another layer using the Layers panel:

1 Select the object.

The object's layer name is highlighted in the Layers panel.

2 In the Layers panel, click the name of the layer to which you will move the selection.

By default, clicking a layer name moves a selected object to that layer.

> **Note:** If this procedure doesn't work correctly, check your panel preferences. See the following procedure.

To prevent selected objects from automatically moving to other layers:

1 Display panels preferences by doing one of the following:

- In Windows, press Control+H, then click the Panels tab.
- On the Macintosh, press Command+H, then click the Panels category.

2 Deselect Clicking on a Layer Name Moves Selected Objects, and click OK.

To move one or more objects to another layer by using menu commands:

1 Select Edit > Select > None or press Tab to deselect all objects in the document.

2 In the Layers panel, select the layer you want to move the object or objects to.

3 Select an object or multiple objects in the workspace. Objects can reside on different layers.

The objects' layer names are highlighted in the Layers panel.

4 Do one of the following:

- From the Layers panel Options pop-up menu, select Move Objects to Current Layer.
- (Windows only) In the Layers panel, right-click the layer that you want to move the object or objects to. Select Move Selection to This Layer from the context menu.

To move a layer in front of or behind another layer:

1 Select Edit > Select > None or press Tab to deselect all objects in the document.

2 In the Layers panel, drag the name of the layer you want to move to the new position.

Dragging the layer below another layer in the list moves it behind that layer, while dragging it above a layer in the list puts it in front of that layer.

Dragging a layer name to reposition the layer

To retain layer information when pasting selections between documents:

1 Display general preferences by doing one of the following:

- In Windows, press Control+H, then click the General tab.

- On the Macintosh, press Command+H, then click the General category.

2 Select Remember Layer Info, and click OK.

This option also returns grouped, joined, and clipped objects to their original layers if you ungroup or split the objects.

To copy layer information between documents:

1 Display general preferences by doing one of the following:

- In Windows, press Control+H, then click the General tab.

- On the Macintosh, press Command+H, then click the General category.

2 Select Remember Layer Info, and click OK.

3 Select an object in the source document and select Edit > Cut or Edit > Copy.

4 Open the destination document and select Edit > Paste.

If the layer name in the destination document is the same as the one in the original document, then FreeHand places the object on that layer. Otherwise, a new layer is created.

Merging layers

When you've finished creating your artwork, you can merge layers to streamline your document. You cannot merge the Guides layer with other layers.

To merge layers:

1 In the Layers panel, select the layers you want to merge. Select discontiguous layers by Control-clicking (Windows) or Command-clicking (Macintosh), or select a range of contiguous layers by Shift-clicking.

2 Click the Layers panel Options menu control and select Merge Selected Layers. The layers are merged onto the bottom layer in the selection. Objects on merged layers retain their stacking order relative to one another.

To merge all foreground layers:

Click the Layers panel Options menu control and select Merge Foreground Layers. The foreground layers are all the layers above the separator line except the Guides layer.

Removing layers

You can remove layers you no longer need using the Layers panel.

To remove a layer:

1 Select the layer to be removed.

2 Do one of the following:

• Click the Layers panel Options menu control and select Remove.

• In Windows, right-click the layer to be removed and select Remove.

   A warning appears if the layer is not empty.

3 Click Yes to remove the layer and its contents.

Viewing layers and layered artwork

You can hide a layer to hide its objects without removing them. Displaying a layer displays all objects on that layer. If the active layer is hidden, newly created objects are not visible until the layer is displayed again.

To show or hide a layer, do one of the following:

• In the Layers panel, click the left column to show or hide the layer; a check mark indicates that the layer is visible.

• To show or hide a range of contiguous layers, drag up or down in the left column of the Layers panel. Visible layers are indicated by a check mark.

• To show or hide all layers, Control-click (Windows) or Option-click (Macintosh) in the left column of the Layers panel.

   Note: To print all foreground layers when some or all layers are hidden, select File › Document Settings › Output Options, and select Include Invisible Layers.

Viewing layers in Preview or Keyline mode

You can view layers as they will appear when printed in Preview mode, or as outlines in Keyline mode. A filled circle to the left of the layer name in the Layers panel indicates Preview mode; a hollow circle indicates Keyline mode. Modes affect onscreen display only; they have no effect on printing and exporting.

To switch between Preview and Keyline modes, do one of the following:

• In the Layers panel, click the circle icon to the left of the layer name. The Preview mode icon is a solid circle; the Keyline mode icon is a hollow circle.

• To switch between Preview and Keyline modes for a contiguous selection of layers, drag through the circle icon column for those layers.

• To switch the view of all layers, Control-click (Windows) or Option-click (Macintosh) the circle icon to the left of any layer name.

Locking and unlocking layers

You can lock layers to protect the objects on those layers from changes while keeping them visible. A closed padlock icon next to the layer name in the Layers panel indicates that a layer is locked; an open padlock icon indicates that it's unlocked.

To lock or unlock a layer, do one of the following:

• In the Layers panel, click the padlock icon to the left of the layer name.

• To lock or unlock a range of contiguous layers, drag through the padlock column.

• To lock all layers, Control-click (Windows) or Option-click (Macintosh) a padlock icon to the left of any layer name.

Using the Guides layer and guide paths

Using the Guides layer, you can turn a simple path into a guide. Guide paths help you to trace, position, and place objects more accurately.

You can hide, lock, move, or change the color of the Guides layer, but you cannot merge, rename, or remove it.

For more information on guides, see "Using guides" on page 55.

To show or hide the Guides layer:

In the Layers panel, click in the far left column of the Guides layer.

A check mark indicates that the layer is visible.

To change the color of the Guides layer:

1 Display colors preferences by doing one of the following:

• In Windows, press Control+H, then click the Colors tab.

• On the Macintosh, press Command+H, then click the Colors category.

2 Click the Guide Color box and select a color.

3 Click OK twice.

To toggle between viewing guides in black (Keyline mode) or in color:

Click the circle icon in the Guides layer.

To position guides in front of your artwork:

In the Layers panel, drag the Guides layer above the other layers.

To turn a path into a guide:

1 Select the path.

2 In the Layers panel, click the Guides layer.

The path appears in the guide color. Any path moved to the Guides layer becomes a guide.

To turn a guide path into a normal path:

1 Double-click the guide path.

2 In the Guides dialog box, click Release and then click OK.

The path returns to its original layer.

Using layer highlight colors

To help distinguish layers and the objects contained within them, you can assign different highlight colors to layers. The highlight affects the onscreen display color of a selected object's path, its points, and its transform handles; it does not affect the actual color of the object.

To change a layer's highlight color:

1 Select Window > Layers to display the Layers panel if it isn't already showing.

2 Do one of the following:

• Drag a color from the color box in the Swatches panel or Color Mixer panel to the swatch next to the layer name in the Layers panel.

• Drag a layer color from another layer in the Layers panel onto the swatch you want to change.

• Drag a color from a stroke or fill color swatch in the Object panel Properties list onto the swatch in the Layers panel.

• Use the Eyedropper tool to drag a color from an object in the document to the swatch in the Layers panel.

To set whether the layer highlight color appears on selected paths:

1 Display general preferences by doing one of the following:

• In Windows, press Control+H, then click the General tab.

• On the Macintosh, press Command+H, then click the General category.

2 To display path segments in the highlight color, select Highlight Selected Paths. Deselecting this option causes only selection handles to appear in the layer highlight color.

3 Click OK.

Using the Library panel

The FreeHand library stores symbols and master pages for reuse throughout a document. Using the Library panel, you can do the following:

- Create a symbol from any object, text, or group

- Delete or group symbols

- Import and export symbols and master pages

Symbols help you to streamline the use of repetitive elements and minimize file size. You can create instances of a symbol; instances are children of their parent symbol. Many instances of a single symbol can appear in a document, and these instances can be transformed individually with different attributes. For more information, see "Creating and importing symbols" on page 298.

Master pages enable you to create a consistent look throughout your document by carrying graphics, text, and page attributes across some or all document pages. For more information, see "Working with master pages" on page 50.

To display the Library panel, do one of the following:

- Click the Library button in the Main toolbar.

- Select Window > Library.

Symbol preview

Toggle sorting

List view area

Remove

Swap symbol

New group

New symbol

Creating and importing symbols

A symbol is an object stored in the library for future reuse. You can create a symbol from any object, text, or group. Creating a new symbol automatically adds the symbol to the library.

You can duplicate symbols as well as preview and import them from other FreeHand documents. Duplicating a symbol copies the attributes of the symbol.

To create a symbol:

1 Select an object, group, or text that you'll make a symbol.

2 Do one of the following:

• Click the New Symbol icon at the bottom of the Library panel.

• Drag the object onto the list view area in the Library panel.

• Click the Library panel Options menu control and select New Graphic.

• Select Modify > Symbol > Convert to Symbol.

• Select Modify > Symbol > Copy to Symbol.

To duplicate a symbol:

1 Select Window > Library to display the Library panel if it isn't already open.

2 Select the symbol in the Library panel.

3 Do one of the following:

• Click the Library panel Options menu control and select Duplicate.

• Hold down Control (Windows) or Option (Macintosh) and drag a symbol in the symbol list. Select a range of contiguous symbols by Shift-clicking.

    The duplicate symbol is added to the library.

To preview a symbol:

1 Click the Library panel Options menu control and select Preview if it's not already selected.

2 Select the symbol in the list.

    The symbol is previewed in the upper window of the panel.

To import a symbol:

1 Click the Library panel Options menu control and select Import.

2 Browse to locate the document from which to import the symbol, select the file, and click Open.

3 Select the symbol from the Import Symbols dialog box, and click Import.

To remove a symbol:

1 Select the symbol in the Library panel.

2 Do one of the following:

• Click the trash can icon at the bottom of the Library panel.

• Click the Library panel Options menu control, and select Remove.

3 In the alert box that appears, click Delete.

To group symbols:

1 Do one of the following:

• Click the folder icon at the bottom of the Library panel.

• Click the Library panel Options menu control, and select New Group.

2 Name the new group folder.

3 Select and drag the symbols from the symbol list into the group folder. Shift-click to select multiple symbols.

Creating and modifying instances

An instance is linked to the symbol used to create it. If you modify the symbol, the instance is modified as well.

You can release an instance from its symbol to use the resulting unlinked object independently. You can also transform an instance using the Transform panel or associate a URL with an instance using the Navigation panel. For more information, see "Transforming objects" on page 136 and "Attaching URLs to objects and text" on page 327.

To create an instance, do one of the following:

• Drag a symbol from the Library panel to your document.

• Copy and paste or duplicate an existing instance.

To release an instance from its symbol:

1 Select the instance.

2 Select Modify > Symbol > Release Instance.

Editing symbols

Editing a symbol (the parent) automatically changes all associated instances (children).

You can easily change all instances of a symbol in the document by replacing the symbol in the library with a selected object on the canvas. You can also replace selected objects or instances on the canvas with an instance of a different symbol in the library.

To edit a symbol:

1 Double-click the symbol icon or symbol preview in the Library panel.

   The symbol opens in a separate editing window.

2 To update all instances when you edit your symbol, select Auto-Update in the upper left corner of the editing window.

   Note: The Auto-Update option is selected by default. Although Auto-Update allows for live display of changes made in the editing window, changes are not actually applied to the original document until you close the editing window or switch to another FreeHand document.

3 Edit the symbol as desired.

4 Close the editing window.

To replace a symbol and all associated instances with another object:

1 Drag the new object onto the symbol you want to replace in the Library panel.

2 At the prompt, click Replace.

   All instances associated with the original symbol are updated automatically.

To replace objects or instances in the document with a symbol from the library:

1 In the Document window, select an object or instance that you want to replace. Shift-click to select more than one object or instance.

2 Select the symbol in the Library panel.

3 Do one of the following:

• Click the Swap Symbol icon in the Library panel.

• Click the Library panel Options menu control and select Swap.

The objects or instances you selected in the document are replaced with an instance of the symbol selected in the Library panel.

Exporting symbols

You can export symbols for use in other FreeHand documents.

To export one or more symbols:

1 Click the Library panel Options menu control and select Export.

2 Select the symbol or symbols you want to export.

3 Click Export.

4 In the Export Symbols dialog box, browse to locate the folder to which to save the symbol file.

5 Enter a filename, and click Save.

Using styles

To maintain visual consistency and simplify formatting, you use styles. You can change graphic styles and text styles to quickly modify graphics and text throughout your document. You can create and save styles to use as part of a template. For more information, see "Using templates" on page 60.

Graphic styles let you format graphics with preset strokes, fills, colors, effects, and halftone attributes. These attributes are available in the Object panel and the Halftones panel.

Text styles let you format text blocks and paragraphs with preset type attributes. For more information, see "Using text styles" on page 274.

Using the Styles panel

The Styles panel displays the current graphic styles and text styles in your document. You use the Styles panel to duplicate, remove, and add new styles. You use the Styles panel and the Object panel together to edit styles. (For more information about the Object panel, see "Using the Object panel" on page 107.)

Selecting a style in the Styles panel when no objects are selected in the document causes the style to define the default attributes for all new objects. For more information, see "Changing default attributes" on page 146.

To display the Styles panel:

Select Window > Styles.

To change how styles appear in the Styles panel:

Click the Styles panel Options menu control and select one of the following:

Compact List View displays style names and small previews.

Large List View displays style names and large previews.

Previews Only displays large previews only.

From left to right: Styles panel displaying compact list view, large list view, and previews only

Applying styles

You can apply a style to a selection by using the Styles panel to select or drag a style, or by copying and pasting.

You can set preferences to control how new styles are defined and whether new graphic styles apply immediately to selected objects.

To apply a style, do one of the following:

• Select the object to which you will apply the style. In the Styles panel, click the style you want to apply.

• Drag a style preview from the Styles panel to the object.

Dragging a graphic style to apply it to an object

• Drag the style preview from the Properties list in the Object panel to the object.

To copy and paste style attributes:

1 Select the object whose attributes you want to copy, and select Edit > Special > Copy Attributes.

2 Select the object onto which you'll paste the attributes, and select Edit > Special > Paste Attributes.

To set how graphic styles are applied and defined:

1 Display object preferences by doing one of the following:

- In Windows, press Control+H, then click the Object tab.

- On the Macintosh, press Command+H, then click the Object category.

2 Under New Graphic Styles, do one of the following:

- Select Auto-Apply to Selection if you want to automatically assign new styles that you create to objects that are selected in the document at the time.

- Deselect Auto-Apply to Selection if you want objects that are selected at the time you create new styles to retain their original styles.

3 Click OK.

To specify which attributes are affected when styles are applied:

1 Select Edit > Select > None or press Tab to deselect all objects.

2 In the Styles panel, select the style.

3 Click the Styles panel Options menu control and select Style Behavior.

4 Do one of the following:

- For graphic styles, use the Style menu to select the attributes that you want the style to affect: Both Fill + Stroke, Fill Attributes, or Stroke Attributes.

- For text styles, select attributes and options. Select No Selection from the pop-up menus to prevent the style from changing those attributes in selected objects. For more information about these options, see "Creating and editing text styles" on page 274.

5 Click OK.

Adding, duplicating, and removing styles

To add new styles, copy styles, or remove styles, you use the Styles panel.

To create a new style based on the Normal graphic style:

Click the Styles panel Options menu control and select New from Normal.

To create a new style based on a selected object, do one of the following:

- Click the Styles panel Options menu control and select New.

- Drag the object from the workspace to an empty area of the Styles panel.

- Drag the preview swatch beside the object name in the Object panel Properties list to an empty area of the Styles panel.

To create a new style based on an existing style:

1 Select Edit > Select > None or press Tab to deselect your artwork.

2 In the Styles panel, select the style on which you want to base the new style.

> *Note:* Selecting a style when no objects are selected causes the style to define the default attributes for all new objects. For more information, see "Changing default attributes" on page 146.

3 Do one of the following:

• Click the Styles panel Options menu control and select New.

• Drag the preview swatch from the style in the Object panel Properties list into an empty area of the Styles panel.

To create a new style based on attributes you set in the Object panel:

1 Select Edit > Select > None or press Tab to deselect your artwork.

2 Set attributes in the Object panel.

3 Do one of the following:

• Click the Styles panel Options menu control and select New.

• Drag the style preview from the Object panel Properties list into an empty area of the Styles panel.

To duplicate a style:

1 Select Edit > Select > None or press Tab to deselect your artwork.

2 In the Styles panel, select a style.

3 Click the Styles panel Options menu control and select Duplicate.

To remove a style:

1 Select Edit > Select > None or press Tab to deselect your artwork.

2 In the Styles panel, select a style.

3 Click the Styles panel Options menu control and select Remove.

To remove all unused styles:

Click the Styles panel Options menu control and select Remove Unused.

To rename a style:

1 Click the Styles panel Options menu control and select a view that displays style names.

2 Double-click the style name in the Styles panel.

3 Type a new name, and click outside the Styles panel or press Enter (Windows) or Return (Macintosh).

Modifying styles

You can modify any style's stroke, fill, color, or effect attributes in the Object panel. Modifying a style in this manner does not automatically update previously created objects that use it. To update the style of previously created objects, you must redefine the style after making modifications. You can also override the style for an object by making changes to the object's attributes after the style has been applied to it.

If you select a style in the Styles panel when no objects are selected in the document, the style defines the default attributes for all new objects. For more information, see "Changing default attributes" on page 146.

To modify a style:

1 Select Edit > Select > None or Press Tab to deselect all objects in the workspace.

2 Click the style name in the Styles panel.

3 Select Window > Object to open the Object panel if it's not already open.

The Object panel displays properties and options for the selected style, which now defines the default attributes for all new objects you create.

4 Select attributes in the Properties list, and modify their options in the bottom half of the Object panel.

A plus (+) sign is displayed beside the style in the Styles panel, indicating that the attributes in the Object panel are now different from the style's original attributes. All new objects you create using this style will have the updated style attributes, until you select another style or further modify the default attributes.

To override an object's style:

1 Select the object, paragraph, or text block containing the style you want to override.

2 Change any stroke, fill, effect, or text attribute in the Object panel.

When you select the object or text, the overridden style appears highlighted with a plus (+) sign beside it in the Styles panel.

To remove a style override from an object:

1 Select an object, paragraph, or text block with an overridden style.

2 In the Styles panel, select the object's style to reapply the style.

To redefine a style:

1 Select Edit > Select > None or press Tab to deselect your artwork.

2 Select the style name in the Styles panel.

3 Change the desired attributes in the Object panel.

4 Do one of the following:

- In the Object panel, select the graphic style in the Properties list (the topmost level in the list), and click the Redefine button in the options section of the panel.

- Click the Styles panel Options menu control and select Redefine. In the dialog box that appears, select the style to redefine and click OK.

- Drag the style's preview swatch from the Object panel's Properties list onto the style in the Styles panel that you want to redefine. Then click Redefine in the dialog box that appears.

To redefine a style based on a selected object or text block:

1 Do one of the following:

- Drag the object from the workspace onto the style you want to redefine in the Styles panel.

- Drag the object's preview swatch from the Object panel's Properties list onto the style in the Styles panel that you want to redefine.

2 Click Redefine in the dialog box that appears.

To redefine a style with another style:

1 In the Styles panel, drag the style with the desired attributes onto the style you want to redefine.

2 Click Redefine in the dialog box that appears.

Basing one style on another

You can base one style on another. One parent style can have many different child styles based on it; for instance, the children can all have the same fill but various stroke weights. Editing a parent style changes any attributes that the child styles share. Attributes unique to each child style do not change.

If you remove a child style from the Styles panel, any object or text that was based on that style becomes based on the parent style, but the object or text retains all of its attributes.

To base one style on another:

1 Select Edit > Select > None or press Tab to deselect all objects.

2 In the Styles panel, select the style that you want to make a child style.

3 Click the Styles panel Options menu control and select Style Behavior.

4 From the Parent pop-up menu, select the style on which you want to base the child style, and click OK.

To copy style information to another document:

1 Select an object or text that uses the desired style.

2 Select Edit > Cut or Copy.

3 Open the destination document and select Edit > Paste.

The object appears in the document, and its style appears in the Styles panel. When a style in the destination document has the same name as the style you copy, the style in the destination document is unchanged. So that the pasted object will appear just as it did in the original document, it has a style override. For information on overriding a style, see "Modifying styles" on page 305.

Importing and exporting styles

You can import styles from other documents, or export styles to use them in other illustrations, to distribute them to other users, or to store for future use.

To import styles:

1 Click the Styles panel Options menu control and select Import.

2 Locate the styles library or FreeHand document containing the styles you want to import, and click Open (Windows) or Choose (Macintosh).

3 In the Import Styles dialog box, select the styles you want to import. Shift-click to select multiple styles.

4 Click Import.

To export styles:

1 Click the Styles panel Options menu control and select Export.

2 In the Export Styles dialog box, select the styles you want to export. Shift-click to select multiple styles.

3 Click Export.

4 Enter a filename for the style library, choose a location, and click Save.

CHAPTER 10
Using Imported Artwork

Macromedia FreeHand MX can import a wide variety of vector and bitmap graphic formats. FreeHand imports graphics in the following ways:

- Imported vector graphics are converted to FreeHand format and are stored in the current FreeHand document.

- EPS graphic files are linked, embedded, or parsed depending on the nature of the file and certain preference settings. For more information, see "Linking and embedding" on page 62.

- When bitmap images are opened or imported, by default they are linked to a FreeHand document, not embedded; you can change this preference. Bitmap images that are imported by copying and pasting are always embedded. For more information, see "Linking and embedding" on page 62.

- When opening Adobe Illustrator files, FreeHand treats Live Blends as grouped vector objects and converts objects with gradient mesh effects to paths with a 50% black fill.

Note: When a graphic file is imported into FreeHand and then modified and saved in its original graphics application with the same name and file location, all references to that graphic file are updated in FreeHand.

Importing a graphic

You can import graphics or text using the Import, Open, or Paste command, or by dragging and dropping. On the Macintosh, you can import and open existing FreeHand files using the FreeHand MX File Viewer.

For information about the file formats that FreeHand can import, see "Import file formats" on page 310.

Note: If you are importing or opening an HPGL (Windows), CGM (Windows), or DXF file in FreeHand, you will not be able to export or save it in its original format. To retain the information in the document, you must save it as a FreeHand document or export it to one of the other available formats.

To import a graphic into an existing document using the Import command:

1 Select File > Import.

2 Select a file and click Open.

   If the file selected for import contains a preview, the preview appears when the file is selected.

3 To set format-specific import options, select the file type and click Setup to open an additional dialog box. Select the desired options and click OK.

   Note: Import options are only available for some formats.

4 Position the import pointer where you want the graphic or text block's upper left corner to appear.

5 Place the graphic by doing one of the following:

• Click to place the graphic at its default size.

• To resize an image while importing, drag the import pointer to create a marquee. Release the mouse button when the marquee is the correct size.

For information about other ways to import graphic files, see the following sections:

• "Creating and opening documents" on page 58

• "Copying objects" on page 115

• "Importing artwork using the FreeHand MX File Viewer (Macintosh only)" on page 317

• "Working with bitmap images in FreeHand" on page 318

Import file formats

FreeHand lets you import files in many vector, bitmap, and other formats, as detailed in the table that follows. The following are the most common types of files you can import:

• Macromedia Fireworks PNG files: Fireworks vectors, text, layers, and some effects are editable in FreeHand.

• Vector-graphic files in Adobe Acrobat, Illustrator, and CorelDRAW (versions 7 and 8) file formats: vector graphics import as editable paths.

• Adobe Photoshop PSD files: these files import as flattened images and cannot be edited.

• Adobe Pagemaker EPS, Photoshop EPS, and QuarkXPress EPS files.

• Bitmap image files from Fireworks in PICT (Macintosh), TGA, TIFF, PSD, GIF, JPEG, or BMP formats: bitmap graphics import in their original format.

• Other file formats, including ASCII and RTF text.

FreeHand import file formats	File extension	Windows	Macintosh	Comments
Acrobat PDF	.pdf	X	X	Portable Document Format
Adobe Illustrator 1.1 through 9.0	.ai, .eps	X	X	Vector and bitmap

FreeHand import file formats	File extension	Windows	Macintosh	Comments
Adobe Photoshop 3.0 through 6.0	.psd	X	X	Bitmap. In Photoshop, select the Photoshop 2.5 Format Compatibility preference before saving the file for export. You can still use Photoshop to edit Photoshop PSD files that have been imported into FreeHand, either by using the External Editor to launch the application or by opening the source file in Photoshop.
AutoCAD DXF	.dxf	X	X	Vector
ASCII text		X	X	
Computer Graphics Metafile	.cgm	X	N/A	
CorelDRAW 7.0 and 8.0	.cdr	X	X	Vector and bitmap. In CorelDRAW, turn both file and bitmap compression off before saving the file.
Desktop Color Separations 2.0 (DCS2 EPS)	.dcs2	X	X	Vector and bitmap
FreeHand 8.0 through MX		X	X	Vector and bitmap
CompuServe GIF	.gif	X	X	Bitmap
HPGL2 Graphics	.plt	X	N/A	Vector, used to print to plotters. Requires special fonts created for HPGL2 graphics; TrueType and Type 1 fonts won't work. Consult the plotter manufacturer for more information.
Encapsulated PostScript, Macintosh EPS, MS-DOS EPS, EPS with TIFF Preview	.eps	X	X	Vector and bitmap
JPEG	.jpg, .jpeg	X	X	Bitmap
Macintosh PICT	.pict, .pict2	N/A	X	Bitmap
Macromedia Fireworks PNG	.png	X	X	Editable vectors, text, layers, cross-product effects, and bitmaps, depending on import options selected
Portable Network Graphic (Generic PNG)	.png	X	X	Bitmap
Macromedia Flash SWF	.swf	X	X	SWF movie. Content cannot be edited in FreeHand, but FreeHand can launch Flash to edit the movie's source FLA file.
Micrografx Designer 3.x	.drw	X	N/A	Vector
QuarkXPress EPS	.eps	X	X	Vector. Files cannot be edited in FreeHand.
RTF text	.rtf	X	X	Rich Text Format. Text with formatting is retained.
Targa	.tga	X	X	Bitmap

FreeHand import file formats	File extension	Windows	Macintosh	Comments
TIFF	.tif	X	X	Bitmap
Windows Bitmap	.bmp	X	X	Bitmap
Windows Enhanced Metafile	.emf	X	N/A	Vector and bitmap
Windows Metafile	.wmf	X	N/A	Vector and bitmap

Importing PNG files

Portable Network Graphic (PNG) is an extensible bitmap image format that features lossless, well-compressed storage of bitmap images. FreeHand can import and open PNG files, whether created in Fireworks or another application.

PNGs from Fireworks import and open differently than PNGs created by other applications. If a PNG file contains extra data appended by an application besides Fireworks, FreeHand ignores the additional data but doesn't delete it.

Depending on the options you select when importing or opening, FreeHand can import Fireworks layers, frames, vectors, text, bitmaps, and some effects that are shared by both applications. Hidden Fireworks layers are ignored and are not imported.

Whether or not the content you import or open is editable in FreeHand depends on the import options you select. These options will be used each subsequent time you import or open a Fireworks PNG, unless you specify otherwise while importing or opening the file.

To import or open a Fireworks PNG:

1 In FreeHand, do one of the following:

• Select File > Import.

• Select File > Open.

2 Locate and select the Fireworks PNG file on your hard disk, then click Open.

The Fireworks PNG Import dialog box appears.

3 Select a File Conversion option:

Open Frames as Pages imports Fireworks frames onto separate FreeHand pages. If you want, select Remember Layers to convert Fireworks layers to FreeHand layers. Deselecting this option causes the content of all Fireworks layers to be combined onto a single layer.

Open Frames as Layers imports Fireworks frames as separate layers.

4 Select a frame to import from the Frame pop-up menu. To import all frames, select All.

Note: The All option is available only if you are opening frames as layers or if you are opening a PNG (rather than importing it).

5 Select how to import objects:

Rasterize If Necessary to Maintain Appearance converts some vector objects to uneditable bitmap images. Only objects with effects, strokes, and fills not shared by FreeHand are converted.

Keep All Paths Editable lets you edit all imported vector objects. Some objects might appear slightly different in FreeHand than in Fireworks because of differences in the way the two applications interpret information. Also, some effects not shared by the two applications might be discarded.

6 Select how to import text:

Rasterize If Necessary to Maintain Appearance converts some text objects to uneditable bitmap images. Only text with effects, strokes, and fills not shared by FreeHand is rasterized.

Keep All Text Editable enables you to edit all imported text. Some text might appear slightly different in FreeHand than in Fireworks, and some effects not shared by the two applications might be discarded.

7 Select the Import as a Single Flattened Bitmap option if you want to preserve the look of the entire Fireworks document. When this option is selected, the rest of the options in the Fireworks PNG Import dialog box are dimmed. Select this option only if editability is not important to you.

8 Click OK.

9 Click in the Document window where you want the Fireworks content to appear.

To import a generic PNG:

1 Select File > Import.

2 Locate and select the PNG file on your hard disk, then click Open.

3 Click in the Document window where you want the PNG to appear.

Importing GIF files

GIF is a bitmap graphic file format that is supported by both Windows and Macintosh platforms. A GIF can be imported into or exported from FreeHand and supports up to 256 colors. However, this format is not recommended for print.

To import a GIF file:

1 Select File > Import.

2 Navigate to locate the file, and select it.

3 Click Open.

4 Click in the page to which you want to import the GIF file.

Importing DXF files

DXF is a vector graphic file exchange format used to transfer files between 3D editing applications, or between 3D editing applications and vector drawing applications. Most 3D editing applications, including AutoCAD and 3DS Max, support DXF format.

FreeHand can import DXF images saved in ASCII or binary format. FreeHand ignores DXF file information that it cannot render, such as 3D splines or other 3D-specific features.

When preparing a 3D file from another application for DXF import into FreeHand, follow these guidelines:

- Flatten the document. Remove any 3D splines or other 3D-specific features of the drawing; FreeHand ignores 3D-specific features when it opens the file.

- To retain consistent text formatting and placement, use common TrueType fonts in files to be imported into FreeHand. FreeHand converts multiline text to the default font when it imports a file.

- For best control over positioning and placement of the imported graphic, prepare the 3D file from the default document view. FreeHand renders imported DXF files in a single, two-dimensional view.

To set DXF import preferences:

1 Do one of the following:

- In Windows, select File > Import. In the Import Document dialog box, select AutoCAD.DXF (*.dxf) from the Files of Type pop-up menu. Navigate and select the filename. Click Setup.

- On the Macintosh, press Command+U and click the Import category.

2 Select one of the DXF filter preferences:

Import Invisible Block Attributes imports DXF objects with invisible stroke and fill attributes.

Convert White Strokes to Black Strokes converts stroke color from white to black.

Convert White Fills to Black Fills converts fill color from white to black.

3 Click OK.

Importing EPS and DCS EPS files

EPS (Encapsulated PostScript) files can contain vector graphics, bitmap images, or both. If clipping paths are present, the clipping path information is preserved. EPS is the best file format for preserving prepress-ready color.

By default, FreeHand imports an EPS graphic as a linked file, not an embedded file.

You can import DCS (Desktop Color Separation) EPS 1.0 or 2.0 files as linked files to increase the speed of printing high-resolution EPS files. A DCS 1.0 file actually consists of five separate files—a low-resolution, composite preview and a separate file for each process (CMYK) color—whereas a DCS 2.0 file contains the same data in a single file. When FreeHand creates process-color separations, it gathers information from the other four component files and outputs them to the appropriate plates.

When you import a DCS 2.0 EPS file, FreeHand automatically uses the low-resolution data for display and the high-resolution data for output to the appropriate plates.

Note: Import a DCS EPS file as a linked image; do not embed it. For more information on linking and embedding, see "Linking and embedding" on page 62.

To import a DCS 1.0 or 2.0 EPS file:

1 Select File > Import.

2 In the Files of Type pop-up menu, select Encapsulated PostScript (*.eps).

3 Navigate to locate the file, and select it.

4 Click Open.

5 Click in the page to which you want to import the EPS file.

Note: Importing a DCS 1.0 file outputs a low-resolution, composite preview and a separate file for each process (CMYK) color, whereas importing a DCS 2.0 file outputs the same data in a single file and adds support for spot colors.

Importing PDF files

Adobe Acrobat PDF (Portable Document Format) is a common file format for sharing documents across most computer platforms. PDF documents can be viewed or printed with Adobe Acrobat Reader. FreeHand can open and import PDF documents.

FreeHand preserves notes and links to URLs in PDF documents. By default, Acrobat notes are placed on a separate layer called the Notes layer, and URLs are placed on the URLs layer. If FreeHand cannot determine the assigned path area, it places linked notes as rectangles on the URLs layer.

FreeHand also preserves linear and radial gradient fills that were originally generated in FreeHand and exported to PDF. PostScript 3 gradient mesh fills are converted to 10% black fills.

For imported PDF text, FreeHand uses only the fonts that are installed on your system. If a font match is not found, FreeHand displays the Missing Fonts dialog box, which lets you select replacement fonts. (For more information on PDF font support, see your Adobe Acrobat documentation.)

To open a PDF document in FreeHand:

1 Select File > Open, select the desired PDF file, and click Open.

If the document you are importing is a multipage PDF, FreeHand generates a page in the document to hold the content for each PDF page. Each page has the same size and orientation as the original page in the PDF.

2 If prompted to replace fonts, see the procedure in "Replacing missing fonts" on page 66.

3 If the text in the PDF file is displayed as individual text blocks, combine these text blocks using the text tools.

Tip: If an entire page appears as a single object with the graphic elements pasted inside, select the page with the Pointer tool and select Edit > Cut Contents to release the graphic elements.

To import a PDF document into an existing FreeHand document:

1 Select File > Import, select the desired PDF file, and click Open.

2 If prompted to replace fonts, see the procedure in "Replacing missing fonts" on page 66.

3 Click in the document where you want the PDF content to appear.

If the document you imported was a multipage PDF, FreeHand imports the content from all pages but does not create separate document pages for the content; content after page 1 of the PDF is placed on the pasteboard. In addition, page size and orientation information is lost. To preserve page information, you must open the PDF rather than importing it. (See the previous procedure.)

To choose PDF import preferences:

1 Display import preferences by doing one of the following:

• In Windows, press Control+U, then click the Import tab.

• On the Macintosh, press Command+U, then click the Import category.

2 Select one or both of the following PDF Import options:

Import Notes imports notes from the PDF and places them in the Notes layer.

Import URLs imports URL links from the PDF and places them in the URLs layer.

3 Click OK.

Importing PICT files (Macintosh only)

FreeHand can import PICT patterns and convert their fills to PostScript tints to maintain the original tint's appearance.

To choose PICT import preferences (Macintosh):

1 Press Command+U and click the Import category.

2 Select Convert PICT Patterns to Grays. This option converts a pattern fill or line to a PostScript tint that approximates the darkness of the original PICT pattern.

3 Click OK.

Other file formats FreeHand can import

FreeHand can import graphics in a variety of file formats. This section contains format-specific information about import file formats not covered in other sections.

For general instructions on importing graphics of any format, see "Importing a graphic" on page 309. For detailed instructions about importing specific file formats not covered below, see the appropriate sections earlier in this chapter.

FreeHand can import graphics of the following file formats, among many others:

JPEG   The JPEG (Joint Photographic Experts Group) format is a highly compressible bitmap graphic format that can support millions of colors. JPEG images are always displayed at high resolution regardless of whether the Image Display option in redraw preferences is set to High Resolution. The more the image is compressed, the more sharpness is lost. This format is not recommended for print. You can import 8-bit JPEG images in RGB, CMYK, and grayscale color spaces; you cannot import YCC, YCCk, and 12-bit JPEG images. When working with JPEG images, follow these guidelines:

• Applying plug-in filters to a linked JPEG image converts the image to an embedded TIFF image. To extract the image and create a link to the new TIFF file, use the Extract button in the Links dialog box. For more information, see "Managing links" on page 63.

   Note: Some plug-ins don't work properly with JPEG images.

• To colorize a grayscale JPEG, apply a fill color.

Photoshop (PSD)   FreeHand can import Photoshop (PSD) files. These files are imported as bitmap images that cannot be edited. If you open a PSD file directly in FreeHand, you can still edit the file using Photoshop, either by extracting the file or by launching Photoshop as an external editor. For more information, see "Working with bitmap images in FreeHand" on page 318 and "Editing bitmap images using other external editors" on page 322.

Note: To preserve spot colors in Photoshop images, export from Photoshop as DCS2 EPS. For more information on importing EPS files, see "Importing EPS and DCS EPS files" on page 314.

CGM (Windows only)   The CGM (Computer Graphics Metafile) format can contain vector graphics, bitmap images, text, or all three. FreeHand can import CGM and ATA CGM files.

CorelDRAW 7 and 8   FreeHand can open files saved in the uncompressed CorelDRAW 7 or 8 for Windows file format on both Windows and Macintosh platforms.

Targa   Targa is a bitmap graphic format developed by Truevision, Inc. that is widely used in professional video editing. Targa can support 8-bit, 16-bit, 24-bit, and 32-bit color and can contain an alpha channel.

Importing artwork using the FreeHand MX File Viewer (Macintosh only)

The FreeHand MX File Viewer allows you to easily import or open FreeHand files. You can drag file previews directly into a FreeHand document.

To import FreeHand files using the FreeHand MX File Viewer:

1   Locate the FreeHand MX File Viewer in the FreeHand MX application folder and double-click the icon to launch the viewer.

2   Click the triangles to expand the folder views.

3   In FreeHand, open an existing document or create a new document.

4   Do one of the following:

• Drag the desired file preview from the File Viewer window to your FreeHand document.

• Double-click the preview in the File Viewer to open the artwork as a new document in FreeHand.

5   Select File > Quit to close the File Viewer.

Working with bitmap images in FreeHand

FreeHand can import TIFF, GIF, JPEG, PICT, PNG, Targa, BMP, and Photoshop (PSD) bitmap formats. In most cases, all bitmap formats behave in FreeHand exactly as TIFF images behave. You can embed, extract, or change links to these files using the Links dialog box. For information about how to embed graphics, see "Linking and embedding" on page 62.

You can set preferences to display imported bitmap files at the highest resolution available. You can also display the alpha channel of imported TIFF, PSD, PNG, BMP, and Targa images. You can hide the alpha channel by using the Object panel.

Note: If you import a bitmap image with an alpha channel, FreeHand displays the image's transparency onscreen but does not maintain upon export the true alpha channel that was saved with the original image. To export the bitmap image with an alpha channel, you must apply an alpha channel in FreeHand before exporting the image. For more information, see "Working with alpha channels" on page 353.

The Object panel also lets you set black-and-white and grayscale bitmaps to be transparent (so that any white area is clear) and edit the grayscale ramp. In addition, you can apply a color to a black-and-white or grayscale bitmap by assigning it a fill color.

FreeHand can apply some plug-ins to bitmap files. However, once a bitmap image has been modified with a plug-in, it is converted to a TIFF and is embedded in the FreeHand document. Also, the plug-in might not support alpha channels, so you could lose transparency when using plug-ins.

To extract an embedded bitmap:

1 Select File > Open.

2 Navigate to locate the FreeHand document containing the embedded graphic, and click Open.

3 Do one of the following:

• Select Edit > Links.

• Select the embedded graphic you want to extract, and click the Links button in the Object panel.

4 In the Links dialog box select the embedded file to extract. Click Extract.

5 In the Extract Import dialog box, click Save to accept the file import.

6 Click OK.

To set a grayscale or black-and-white bitmap to be transparent:

1 Select the bitmap. Ensure that it is a true grayscale or black-and-white image.

Tip: If a selection is a true grayscale or black-and-white image, its name is preceded by the word *Grayscale* in the Object panel Properties list.

2 Select Transparent in the Object panel.

Note: This option is available only for true grayscale and black-and-white images. It is not available for RGB images with bit depths of 8 bits or higher, nor is it available for CMYK images.

To edit a grayscale ramp for a bitmap:

1 Select the bitmap. Ensure that it is a true grayscale or black-and-white image.

Tip: If a selection is a true grayscale or black-and-white image, its name is preceded by the word *Grayscale* in the Object panel Properties list.

2 Click the Edit Grayscale Ramp button beside the Transparent option in the Object panel.

Note: This option is available only for true grayscale and black-and-white images. It is not available for RGB images with bit depths of 8 bits or higher, nor is it available for CMYK images.

3 In the Image dialog box, do one of the following:

- Select one of the four predefined grayscale ramps.

- Manually edit the grayscale ramp using the Lightness and Contrast arrows.

4 Do one of the following:

- Click Reset to undo grayscale editing.

- Click Apply to preview the edits.

5 Click OK to accept the edits.

To display imported TIFF files at the highest resolution available:

1 Display redraw preferences by doing one of the following:

- In Windows, press Control+U, then click the Redraw tab.

- On the Macintosh, press Command+U, then click the Redraw category.

2 Select Smart Image Preview Resolution (Windows) or Set On-Screen Image Resolution (Macintosh) if it is not already selected. Set this option to Full Resolution to display imported TIFF files at the highest resolution available.

In Windows, Image RAM Cache is selected by default and is automatically calculated to the best RAM allocation for the cache. The cache allows for faster redrawing of bitmap images.

3 Click OK.

To resize a bitmap image, do one of the following:

- Drag the corner handles of the bitmap image.

- To constrain the proportions of the image as you resize it, Shift-drag.

- To resize the image in specific increments based upon the printer resolution, Alt-drag (Windows) or Option-drag (Macintosh).

- In the Object panel, enter the scale percentage or the dimensions and press Enter (Windows) or Return (Macintosh).

To display or hide a bitmap's alpha channel:

1 Select the bitmap.

2 In the Object panel, do one of the following:

• Select Display Alpha Channel. This option is selected by default when you import an image containing an alpha channel.

• Deselect Display Alpha Channel. This causes the background of an imported image to display as opaque.

Launching Fireworks to edit imported bitmap images

You can use launch-and-edit integration to edit bitmap images placed in a FreeHand document. FreeHand automatically launches Fireworks, enabling you to use the Fireworks bitmap editing tools to modify the image. When you finish making changes, the updates you made in Fireworks are automatically applied to the placed image in FreeHand. Together, the two applications provide a streamlined workflow for editing and designing graphics.

To launch Fireworks to edit a bitmap image:

1 Select the image you want to edit in the Document window.

2 Do one of the following:

• Click the Edit in Fireworks button at the bottom of the Object panel.

• In Windows, right-click the image and select Edit Source in Fireworks from the context menu.

3 If prompted, specify whether to launch a source Fireworks file for the placed image, and select an option from the Fireworks Source Files pop-up menu:

Always Use Source PNG automatically opens the Fireworks PNG source file for the placed image. Both the source PNG and its corresponding placed image are updated.

Never Use Source PNG automatically opens the placed image in Fireworks, whether or not a source PNG file exists. Updates are made to the placed image only.

Ask When Launching lets you specify whether to open the source PNG file each time. When you edit or optimize a placed image, Fireworks displays a message prompting you to make a launch-and-edit decision.

Note: These are Fireworks preferences. Changing an option here sets the launch-and-edit preferences for all future bitmap images that you edit with the Edit in Fireworks button or the Edit Source in Fireworks command. These options are also available within Fireworks in the Preferences dialog box.

4 In Fireworks, edit the image. The Document window indicates that you are editing a Fireworks image from FreeHand.

5 When you finish making edits, click Done in the Document window.

The graphic placed in FreeHand is updated, and the PNG source file is saved if a source file was selected. If the placed graphic was linked rather than embedded in the FreeHand document, the graphic file outside the FreeHand document is also updated.

Launching Fireworks to optimize bitmap images

You can launch Fireworks from FreeHand to make quick optimization changes to a bitmap, such as resampling or changing the file type. Fireworks lets you make changes to optimization settings, the size and area of the image, and animation settings.

To launch Fireworks to optimize a bitmap image:

1 In FreeHand, select the desired image in the Document window.

2 Select Edit > Optimize in Fireworks.

3 If prompted, specify whether to launch a source Fireworks file for the placed image, and select an option from the Fireworks Source Files pop-up menu. For more information about these options, see "Launching Fireworks to edit imported bitmap images" on page 320.

4 Make edits in the dialog box that appears:

- To edit optimization settings, click the Options tab and change the desired settings.

- To edit the size and area of the exported image, click the File tab and change the desired settings.

- To edit animation settings for the image, click the Animation tab and change the desired settings.

  For more information about these options, see Fireworks Help.

5 When you finish editing the image, click Update.

  The image in FreeHand is updated, and the PNG source file is saved if a source file was selected. If the placed image was linked rather than embedded into the FreeHand document, the image file outside the FreeHand document is also updated.

Changing PNG source file information

When launching Fireworks to edit a bitmap image in FreeHand, you can choose to locate the source file from which the imported bitmap originated. Once you've launched and edited an image in Fireworks, its source file information is stored in the Links dialog box.

You can edit this information, or delete it altogether to break the link between the graphic and the original source file.

To edit a bitmap's PNG source file information:

1 Select the bitmap image in the Document window.

2 Do one of the following to open the Links dialog box:

- Select Edit > Links.

- Click the Links button in the bottom half of the Object panel.

3 Click the Info button.

  The Link Info dialog box appears.

4 Modify the information in the Source field, or click the Browse button and locate a source file.

5 Click OK to close the Link Info dialog box, and click OK again to close the Links dialog box.

Editing bitmap images using other external editors

You can use external editors other than Fireworks to modify bitmap images placed in FreeHand. You can set external editor preferences, or choose an external editor each time you select a bitmap for editing.

To set external editor options:

1 Display object preferences by doing one of the following:

- In Windows, press Control+U, then click the Object tab.

- On the Macintosh, press Command+U, then click the Object category.

2 Select Warn Before Launch and Edit (the default).

When this option is selected, a dialog box prompts you to confirm that you want to launch an external editor to edit the image.

3 For Object, select the file format from the pop-up menu: PICT, BMP, GIF, JPEG, Photoshop, PNG Image, Targa, TIFF Image, or Xres LRG Image.

4 Click the Ellipsis (...) button, navigate to select an editor, and click OK (Windows) or Open (Macintosh).

5 Click OK twice.

To use an external editor:

1 Select a bitmap image.

2 Select Edit > Edit in External Editor or press Alt (Windows) or Option (Macintosh) and double-click the image.

3 At the prompt asking if you want to open an external editor, click OK.

The application launches with the selected image opened (if enough RAM is available). An Editing in Progress dialog box appears in FreeHand when the external application opens.

By deselecting the Warn Before Launch and Edit option in object preferences, you can turn off this prompt; for more information, see the previous procedure.

4 When you have finished editing in the external editor, select File > Save to save your changes and quit the external editor application.

5 Click Done in the Editing in Progress dialog box in FreeHand.

The image is automatically updated, reflecting any changes made to it.

Tracing bitmaps

You can import bitmap artwork into FreeHand and then use the Trace tool to create paths that follow the outlines of all or part of the artwork. You can trace all of an image within the selection marquee, or you can trace just an area of contiguous color within the image. The Trace tool traces any objects, including FreeHand graphics, bitmap images, and text.

Scanning images for tracing

When you scan images to be traced in FreeHand, Macromedia recommends that you use a scan resolution between 300 and 600 dots per inch (dpi). Scanning at a resolution higher than 600 dpi results in too many points. In addition, high-resolution bitmap images require more RAM than lower-resolution images. If RAM is limited, FreeHand uses the lowest allowable resolution setting when tracing.

Setting Trace tool options

When tracing bitmap and vector graphics, the default settings for the Trace tool provide good results without using excessive system memory. Before tracing, you should confirm Trace tool settings. The Trace tool's settings are saved to the FreeHand Preferences file when you quit FreeHand.

FreeHand lets you convert color when tracing graphics. You can specify the color mode, color space, and number of colors for objects that the Trace tool creates.

To set Trace tool options:

1 Double-click the Trace tool in the Tools panel.

2 In the Trace Tool dialog box, set the color mode options.

- Select the number of colors, from 2 to 256. Excess colors in the image are converted to the nearest color.

- Select Colors or Grays to set the color mode of the trace result.

- Select RGB or CMYK to set the color space for the trace result.

  Note: To add colors from imported or traced graphics to the color list in the Swatches panel, select Xtras > Colors > Name All Colors, or use the Eyedropper tool to manually add unincluded colors.

3 Set the resolution.

- Select High to yield more details in the trace result. The trace is slower and uses more memory.

- Select Low to yield fewer details in the trace result. The trace is faster and uses less memory.

- Select Normal for a result intermediate between High and Low.

4 Select a Trace Layers option: All, Foreground, or Background. FreeHand traces all paths on the designated layers.

5 Set the Path Conversion option to determine how paths are traced:

- Select Outline to trace along the outside border of the graphics and create closed, filled paths. Then select a Path Overlap option: None to trace line art and text; Loose to trace continuous-tone images; or Tight for more precise color tracing.

- Select Centerline to trace the center of graphic strokes. Use this option to trace line-intensive graphics with few fills. Then select Uniform to trace with a consistent, 1-point stroke, or deselect Uniform to create paths with varying stroke widths.

- Select Centerline/Outline to combine the Outline and Centerline. Then enter an Open Paths Below value to leave paths with widths below that value open. Values are from 2 to 10 pixels.

- Select Outer Edge to trace only the outer contours of the graphic, providing an accurate clipping path into which the original graphic can be pasted.

6 Set the Trace Conformity value to determine how closely the traced paths follow the original. Values can range from 0 (less conformity with fewer points) to 10 (greater conformity with more points).

7 Set the Noise Tolerance value to eliminate stray pixels, or noise, in a low-quality original. Values can range from 0 (more noise retained) to 20 (more noise eliminated).

8 Set Wand Color Tolerance to control the sensitivity when selecting areas of contiguous colors. Values can range from 0 (narrower range of colors selected) to 255 (wider range of colors selected).

9 Click OK.

Tracing an image

You can trace an image by selecting an area or by selecting an area of similar color. With either method, FreeHand creates the traced paths directly above the object that you traced.

When you select by color, FreeHand selects only those colors that are adjacent to the initial selection and within the tolerance set in the Trace tool options. You can add additional areas of any color to the selection. For example, you can select all of the red roses in a picture, or you can select a red rose and its green stem.

To trace a selected area:

1 Click the Trace tool in the Tools panel.

The pointer becomes a wand.

2 Drag a selection area around the object to trace. Hold down Shift to constrain the Trace tool's selection area to a square.

To trace a contiguous area of color:

1 Click the Trace tool in the Tools panel.

2 In the document, click to select an area of color.

- To add to the current selection, Shift-click additional areas.

- To subtract from the current selection, Shift-click a selected area.

- To deselect all areas, press Tab.

3 (Optional) Click a selected area to open the Wand Options dialog box, and select one of the following options:

Trace Selection traces the selection using the settings in the Trace Tool dialog box.

Convert Selection Edge traces only the edges of the selected areas.

4 Click OK to close the Wand Options dialog box if it is open.

Converting vector graphics to bitmap images

You can directly convert, or rasterize, a vector graphic to a bitmap image in FreeHand using the Convert to Image command. The converted object becomes an embedded TIFF file residing in the FreeHand document.

Converting replaces the original vector graphic with the new bitmap image. If you want to keep the original graphic, make a copy and convert the copy.

If the graphic is too large or complex to convert directly in FreeHand, an error message appears. For more complex graphics, export the file to bitmap format. (For more information, see "Saving and Exporting Files" on page 341.)

To convert one or more selected vector objects to bitmap images:

1 Select Modify > Convert to Image.

2 In the Convert to Image dialog box, select a resolution:

   72 dpi is for artwork intended for the web.

   144 dpi is for artwork intended for draft printing.

   300 dpi is for artwork intended for final printing.

3 Set an Anti-Aliasing value to smooth lines and outer edges in the image. Higher values give a smoother result.

4 Click OK.

Cropping a bitmap image

You can use the Crop tool to hide unwanted portions of a bitmap image. The hidden portions are not deleted; you can retrieve them later if you want.

By default, the Crop tool does not appear on any toolbar. You can add it to a toolbar, or use its hot key to activate it.

To add the Crop tool to a toolbar:

1 Select Window > Toolbars > Customize.

2 In the Commands list, expand the Tools/Commands category.

3 Drag the Crop tool button to any open toolbar.

4 In the Customize dialog box, click Close.

To crop a selected bitmap image:

1 Press C or click the Crop tool button to activate the Crop tool.

2 Drag any of the crop handles to hide or reveal portions of the bitmap image. Hold down Shift while cropping to constrain the tool.

CHAPTER 11
Creating Web Graphics and Animation

You can prepare Macromedia FreeHand MX documents for display on the web in the following ways:

- Assign URL links to objects or text in a FreeHand document using the Navigation panel

- Convert a FreeHand document to an HTML document using the Publish as HTML feature

- Compress FreeHand art in GIF, JPEG, or PNG format for display in an HTML document

- Use the Animate Xtra to convert a FreeHand document for display as a Macromedia Flash animation

- Assign Flash actions in FreeHand documents, to create interactive movies for web display

- Export FreeHand art in Flash (SWF) file format to use in creating dynamic vector art for display on the web

- Preview and test Flash movies inside FreeHand using the Flash Playback window.

Attaching URLs to objects and text

To attach URLs to objects and text, you use the Link text box in the Navigation panel.

When a FreeHand document that contains URLs is exported in SWF, PDF, or HTML format, clicking an object with an attached URL jumps to the web page defined by the URL.

The Navigation panel lets you assign URLs to objects, inspect objects to see what URLs are assigned to them, update a URL for all objects linked to it, and search for objects linked to a specified URL.

The Substring text box displays words or phrases within an active text block that are linked to the URL displayed in the Link text box.

You can also use the Navigation panel to assign Flash actions to FreeHand objects. For more information, see "Assigning Flash actions" on page 332.

To assign a URL to an object:

1 In the FreeHand Document window, select the text, text object, or text block to which you want to assign a URL.

2 Select Window > Navigation to open the Navigation panel.

3 In the Link text box, enter the URL to be assigned to the text, or select a URL from the link pop-up menu.

If you selected a word or group of words from a text object in step 1, the text you selected appears in the Substring text box.

To search for objects linked to a URL:

1 In the Navigation panel, enter a URL in the Link text box or select a URL from the Link pop-up menu.

2 Click the Find button to the right of the Link text box.

Objects in the current document that are linked to the URL are selected in the Document window.

To update a URL for all the objects linked to it:

1 Deselect all objects in the current document.

2 In the Navigation panel, select the URL from the Link pop-up menu.

3 Click the Find button to the right of the Link text box.

4 Update the URL in the Link text box as needed.

The URL is updated for all objects linked to it in the current document.

About compressing artwork for the web

When preparing images for display on the web, you compress the images to reduce file size and control the display of color and other attributes. You can compress FreeHand artwork as a bitmap image in GIF, JPEG, or PNG format.

You can also export FreeHand vector artwork in Flash (SWF) format, to compress static artwork or to export a document with animation or Flash actions. For more information, see "Animating objects and text" on page 331, "Assigning Flash actions" on page 332, "Exporting FreeHand documents as Flash movies" on page 336, and "Exporting files" on page 345.

When compressing artwork in a bitmap format, you should choose a file format based on the color and tonal characteristics of the original artwork, and on the type of browser you expect your web audience to use.

In general, the GIF format is best for illustrations with flat color and sharp detail, such as text. The JPEG format is best for artwork with a wide range of colors or continuous-tone color, such as gradients or scanned photographs. The PNG format, like JPEG, preserves a wide range of colors. However, the PNG format is not as widely supported for display in browsers as the JPEG format.

For detailed information on using these file formats, see "Exporting to GIF format" on page 355, "Exporting to JPEG format" on page 357, and "Other export file formats" on page 358.

Publishing FreeHand documents as HTML

The Publish as HTML feature converts a FreeHand document to an HTML document, which can be displayed as a web page in a browser.

You can choose an HTML setting to control the HTML conversion, including the location where the HTML document will be saved, the document layout formatting, the font encoding, and file formats for vector and bitmap artwork. You can select a setting manually, or use the wizard (Windows) or assistant (Macintosh) to help you.

FreeHand has a built-in Default setting for saving the HTML document to a desktop folder titled FreeHand HTML Output. The Default setting formats the document with layers, encodes fonts with Western (Latin 1) formatting, and converts vector images to SWF files and bitmap images to JPEG files. You can edit settings (including the Default setting) and create additional settings.

To create different versions of a document that can be viewed on different browsers or with different plug-ins, you can convert a document to HTML multiple times with different settings. For example, you can create one version of a document that requires the Macromedia Flash Player and one that does not. You must give each HTML document a different name to avoid overwriting the files.

You can also choose options to control which pages in a document are converted and to preview the HTML document or HTML code in a browser or editor when the conversion is complete.

Note: If you assign a URL to a FreeHand object that has a stroke but no fill, the link in the HTML document will be active only when the user rolls over the stroke.

To publish a FreeHand document as HTML:

1 With the document displayed in the Document window, select File > Publish as HTML.

2 In the HTML Output dialog box, do one of the following to choose HTML settings:

- Select a setting from the HTML Setting pop-up menu. (If you have not previously created any HTML settings, only the built-in Default setting is available.)

- Click Setup to view the HTML Setup dialog box and select HTML settings. For information on selecting HTML settings, see the procedure that follows. When you have finished selecting settings, click OK.

- Click Wizard (Windows) or Assistant (Macintosh) and follow the onscreen instructions to select HTML settings. When you have finished selecting settings, click Finish.

3 Specify which pages to publish, all or a range.

4 To display the HTML Output Warnings dialog box when you convert the document, select Show Output Warnings.

5 To preview the converted HTML document on your system, select View in Browser or HTML Editor.

6 Select a browser or editor from the web browser pop-up menu to view the output, or click Browse and locate an HTML viewing application on your system.

7 Click Save as HTML.

If you selected View in Browser or HTML Editor in step 5, the specified HTML application launches and displays the converted document.

8 If you selected Show Output Warnings in step 4, the HTML Output Warnings dialog box appears, indicating any HTML errors in your document.

To create or edit an HTML setting:

1 Select File > Publish as HTML to view the HTML Output dialog box, if it is not already open.

2 In the HTML Output dialog box, click Setup to open the HTML Setup dialog box.

3 Do one of the following:

• To create a new HTML setting, click the Plus (+) button. In the New HTML Setting dialog box, enter a name for the new setting and click OK.

• To edit an existing HTML setting, select the setting from the HTML setting pop-up menu.

4 To choose a location to save the HTML document, click Browse and navigate to the destination folder, then click Select (Windows) or Select [*Folder Name*] (Macintosh).

5 To control how objects are positioned on the document page, select an option from the Layout pop-up menu:

• Select Positioning with Layers to place objects on layers. Layers allow precise positioning and overlapping of objects; however, layers are not supported by any version 3.0 or earlier web browsers.

• Select Positioning with Tables to place objects in table cells. Tables are supported by most browsers; however, table cells do not allow objects to overlap. Overlapping objects are sliced or combined to achieve accurate table cell positioning.

6 For Encoding, select the font encoding format that is appropriate to the language displayed in your document. For English and most western European languages, select Western (Latin 1).

7 For Vector Art, select a file format to which vector artwork files will be converted. For information on conversion file formats, see "About compressing artwork for the web" on page 328.

8 For Images, select a file format to which bitmap image files will be converted.

Note: To set export options for files in GIF, JPEG, or PNG format, you must use the Export dialog box. For more information, see "Exporting bitmap images" on page 352.

9 Do one of the following:

- Click Apply to apply your selections to the setting and continue editing other settings in the HTML Setup dialog box.

- Click OK to apply your selections to the setting and close the HTML Setup dialog box.

Animating objects and text

To animate objects for display in the Flash Player, you place the objects on layers using the Animate > Release to Layers Xtra. You can animate blends, text blocks, or groups, as well as objects attached to a path.

The Release to Layers Xtra ungroups blends, groups, text blocks, or objects attached to a path, creates a new layer for each object, and can assign each ungrouped object to a new layer in consecutive order (New Layer, New Layer-1, New Layer-2, and so on). The Xtra places the first object (or object in a group) on the current layer, and the last object on the top layer. Releasing text to layers converts each letter in the text block to paths and places each letter on a separate layer.

You will achieve the best results by designing the frames of your movie to animate upward from the bottom layer to the top layer. Any objects on the Background layer appear on every frame of the SWF movie.

You can preview or export your animation as a SWF file using the Controller or the Window > Movie commands. For more information, see "Controlling SWF files" on page 338.

You can also create your animation by placing objects on separate pages and selecting Animate Pages or Animate Pages and Layers when you export the FreeHand document as a SWF.

To prepare a text block for animation:

1 Select the text block containing the text that you want to animate, and position the text block where you want the animation to begin.

2 Select Text > Convert to Paths. (For more information on converting text to paths, see "Converting text to paths" on page 287.)

3 With the text block still selected, select Modify > Join.

4 Select Edit > Clone to create a copy of the converted text block.

5 Use the Pointer tool to drag the copy of the converted text block to the position where you want the animation to end.

6 With the Pointer tool, Shift-select the original and the copy of the converted text block.

7 Select Xtras > Create > Blend.

For information on animating the blend, see the following procedure.

To animate objects:

1 Select the objects that you want to animate. A nested object included in a group behaves as a single object.

2 Select Window > Layers to display the Layers panel.

   The Layers panel displays new layers as you create them in the following steps.

3 Select Xtras > Animate > Release to Layers.

4 For Animate, select animation effects to determine how objects are released to layers:

   Sequence releases objects in sequence to separate layers.

   Build creates a stacking effect by copying objects in sequence to subsequent layers. For example, if you have a group of two objects, the first object is placed on Layer 1, and copies of the first and second objects are placed on Layer 2.

   Drop copies objects to all layers but omits one object in sequence from each layer. For example, if you select a group of three objects, the second and third objects are placed on Layer 1, the first object and a copy of the third object are placed on Layer 2, and copies of the second and third objects are placed on Layer 3.

   Trail copies and releases objects to the number of layers you specify. Objects are copied incrementally to the specified number of layers. Enter a number for Trail By to specify the number of layers on which objects will be copied. For example, enter 4 for Trail By to copy each object in the four layers following the layer that contains the object.

5 Select Reverse Direction to release the objects in reverse stacking order and animate the sequence in the opposite direction.

6 Select Use Existing Layers to release objects to existing layers, beginning with the current layer. Deselect the option to release objects to new layers created by the Xtra.

7 If you selected Use Existing Layers in step 6, select Send to Back to release the objects to the back of the stacking order.

8 Click OK.

Assigning Flash actions

You can assign Flash actions to artwork you create in FreeHand in order to use the artwork in interactive Flash movies. You export the FreeHand document with Flash actions as a SWF file for display in the Flash Player.

In an interactive movie, your audience uses the keyboard, the mouse, or both to move objects, jump to different parts of a movie, and perform many other interactive operations.

To assign Flash actions in FreeHand, you use the Action area of the Navigation panel. The Action area lists a subset of actions from ActionScript, the Flash programming language. The following actions are available for use in FreeHand:

The Go To and Stop action jumps to a frame or scene and stops playback.

The Go To and Play action jumps to a frame or scene and continues playback.

The Get URL action retrieves the URL listed in the Link text box in the Navigation panel.

The Play and Stop actions play and stop movies.

The Print action specifies which frames in a movie users can print directly from the Flash Player.

The Full Screen action displays the movie in the Flash Player in full-screen mode, rather than normal mode.

The Start/Stop Drag action makes a specified movie clip draggable when a specified event occurs, and stops the draggable behavior when the opposite action occurs. For example, if you assign On Press as the Start Drag event, FreeHand automatically assigns On Release as the Stop Drag event.

The Load Movie and Unload Movie actions load and unload pages from a FreeHand document onto the SWF movie Stage while the current movie is playing. (The actions are available only with documents that have two or more pages.)

The Tell Target action controls other movies that were loaded into the current movie with the Load Movie action. (This action is available only with documents that have two or more pages.)

When you assign an action, you also select an event that will cause the action to run when the movie is played. A mouse click or the arrival of the movie playhead at a specified frame are events that can trigger an action during movie playback.

For some actions, including Go To, Print, Load/Unload Movie, and Tell Target, you also select parameters that define how the action is to be applied.

To assign actions to artwork in FreeHand:

1 In the Document window, select the object or objects to which you want to assign actions.

2 Select Window > Navigation.

3 Select an action from the Action pop-up menu.

4 Select the event that will trigger the action from the Event pop-up menu.

   Note: For Start/Stop Drag, the Frame Action event is disabled.

5 If you selected Go To and Play, Go To and Stop, Print, Load/Unload Movie, or Tell Target, select Parameters:

• For all actions, select an option from the list of current document pages in the first Parameter pop-up menu.

• For the Go To actions or the Print action, to specify which part of the document the playhead will move to or which part of the document will be printed when the trigger event is performed, select from the current document layers in the second Parameter pop-up menu.

• For the Tell Target action, to control playback of another movie, select an action from the second Parameter pop-up menu: Go To, Go To and Play, Go To and Stop, Play, Stop, or Print. If you selected a Go To or Print parameter, select from the current layers in the third Parameter pop-up menu to specify which part of the document the playhead will move to or which part of the document will be printed.

6 Repeat steps 3 through 5 to assign additional actions.

Using the Action tool

The Action tool lets you assign Flash actions to an object so that users can navigate from the object to a web page. For example, you might assign an action to an arrow-shaped object so that when the user clicks the object, the next page of a presentation appears. By default, FreeHand creates Go To and Stop actions and assigns them to the originating object. If an object has an action assigned to it, an action proton appears at the lower right corner of the object's bounding box.

To assign an action using the Action tool:

1 In the Tools panel, click the Action tool.

2 Drag from the source object to the target page. Until you release the mouse button, the current page highlights to indicate that it is the target page.

To remove an action from an object:

Drag the Action proton to an empty spot on the same page as the source object.

To change the default behavior of the Action tool:

1 In the Tools panel, double-click the Action tool to display the Action tool dialog box.

2 Select one of the following options:

Link to Target Page creates a link to the target page.

Print Target Page causes the target page to print.

Load Target Page as Movie causes the target page to appear as a movie in a FreeHand document.

Using Flash movies

You can import Flash movies (SWF files) into FreeHand documents to use as interactive parts of web presentations prepared in FreeHand. You can also choose a frame for a Flash movie to display when you print a FreeHand document.

To import a Flash movie:

1   Select File > Import.

2   In Windows only, select Macromedia Flash (*.swf) in the Files of Type pop-up menu.

3   Browse to the movie file you want to import, and select it.

4   Click Open.

The mouse pointer turns into a placement pointer.

5   Click in the Document window where you want the movie to appear.

Setting Flash movie attributes

You can use the Object panel to alter the size, position, scale, links, and preview frame for Flash movies you have imported into FreeHand documents.

To adjust the attributes of a selected Flash movie in the Object panel:

1   If necessary, select Window > Object to display the Object panel.

2   Set the dimensions of the movie by doing one of the following:

• Enter values in the X and Y boxes to set the coordinates of the movie within the page.

• Enter values in the W and H boxes to set the width and height of the movie as precise measurements.

• Enter values in the X and Y Scale text boxes to set the width and height of the movie as a percentage of its original size.

3   Select Show Snapshot to display one frame of the movie as a preview, then enter the frame number you want to display.

4   Click the Links button to display the Links dialog box. For more information on links, see "Managing links" on page 63.

Editing imported Flash movies

FreeHand can launch Flash to edit imported Flash movies. To launch Flash from within FreeHand, Flash must be installed on your computer.

To edit an imported Flash movie:

1 Select the movie in the Document window.

2 If necessary, select Window > Object to display the Object panel.

3 Click the Edit in Flash button to launch Flash and edit the movie.

The Locate Macromedia Flash Movie File dialog box appears.

4 Browse to the Flash FLA document that was used to create the imported Flash movie, then click Open.

The FLA document opens in Flash.

5 Edit the movie in Flash, then click the Done button when you have finished.

The movie file is automatically updated in FreeHand.

Exporting FreeHand documents as Flash movies

You can export any FreeHand document in Flash (SWF) format. You can then display the SWF file in the Flash Player plug-in in a web browser, such as Netscape Navigator or Microsoft Internet Explorer, or in a stand-alone Flash Player.

You can export still graphics in SWF format to preserve vector artwork attributes while reducing file size. You can choose to export layers, pages, or both in FreeHand documents as separate frames in a SWF file, or as separate SWF files. If you export layers as frames, all the layers below the separator bar in the Layers panel become one background layer in all frames in the SWF file.

When you export documents that contain movies, the movies are converted to movie clips. The result is a Flash movie file very similar to movie files created by Flash. If you have added Flash actions to a file, the actions are enabled in the exported SWF.

You can export a FreeHand file in SWF format using the Export command, as described in the following procedure. You can also export a file in SWF format using the Controller, or using the Window > Movie commands. For more information, see "Controlling SWF files" on page 338.

Note: To display anti-aliased artwork on the screen as it will appear when exported to Flash SWF format, test the SWF file using the Controller or the Movie commands in the Window menu. For more information, see "Controlling SWF files" on page 338.

To export a FreeHand file in SWF format:

1 Select File > Export.

2 Select Macromedia Flash (SWF) from the Save as Type (Windows) or Format (Macintosh) pop-up menu.

3 Click Setup to display the Movie Settings dialog box.

4 Select a Movie setting:

   Single translates all of the pages in a FreeHand document to a single movie. This option is automatically selected for single-page documents.

   Multiple translates each of the pages in a FreeHand document to separate movies.

5 Select a Layers setting:

   Animate translates each of the FreeHand layers (per page) to separate movie frames.

   Flatten translates all of the FreeHand layers (per page) to a single movie frame.

6 Select which pages to export with the Page Range options.

7 To begin the animation automatically at the specified frame rate in the stand-alone Flash Player, select Autoplay. If you deselect this option, the animation stops at Frame 1 in the stand-alone Flash Player, and you can start it by selecting Window > Movie > Play.

8 To play the entire animation in full-screen mode until you press Escape, select Full Screen Playback. This option does not affect Flash animations played in a web browser.

9 To specify a frame rate for the Flash movie in frames per second (fps), choose a frame rate from 0.01 fps to 120 fps, in increments of 0.01 frame. For the smoothest animations, use 12 fps.

10 To select a background color, select a color from the Background Color pop-up color palette.

11 To print each frame in the SWF animation from the Flash Player plug-in or from version 4.0 or later of the stand-alone Flash Player, select Allow Printing. When this option is deselected, the file prints using the browser's screen resolution (72 dpi).

12 To prevent a SWF file exported by FreeHand from being imported by other users, select Protect from Import.

13 To use the dimensions of the animation as the size of the SWF Stage, select Size to Match Contents. Deselect this option to use the FreeHand page size as the SWF Stage.

14 To automatically set optimization settings for producing smaller movie files, select Optimize for File Size.

15 To automatically set optimization settings for producing high-quality movie files, select Optimize for Quality.

16 To manually control optimization settings, select Advanced:

Path Compression controls how precisely to convert FreeHand paths to Flash paths—from None (no compression and the greatest number of points) to Maximum (for the most compression but lowest quality and fewest points).

Trace Dashed Strokes converts dashed lines to multiple objects. Each dash segment is converted to a separate object, increasing export time and file size.

Image Compression controls image quality and compression for converting bitmap images to JPEG format—None (highest quality, lowest compression) to Maximum (lowest quality, highest compression).

17 Select a Text option to control how to export text:

Maintain Blocks keeps all the text together in a FreeHand text block for editing in Flash 3 or later.

Convert to Paths converts text to vector paths, so the text is no longer editable as text. Text attached to a path or text flowing inside a path is automatically converted to paths and therefore is not editable in Flash. (This option yields a smaller file size than Maintain Blocks.)

None omits all text from the exported file.

18 Select Compress Movie to reduce the file size of the exported movie.

19 Click OK, and then click Save (Windows) or Export (Macintosh).

To test your movie, see the following section.

Controlling SWF files

You can use the Controller or the Window > Movie commands to test, change movie settings for, and export SWF movie files.

To test movies, you can play, stop, rewind, step forward, and step backward through frames. When you test a movie, FreeHand creates a temporary SWF file and displays it in a Flash Playback window. The temporary file is deleted when you close the window, unless you choose to export the file.

Stop

First Frame   Export Movie

Step Backward   Movie Settings

Test Movie

Last Frame

Step Forward

Play

You can drag the Controller to reposition it in FreeHand. You can also change the shortcut keys for the Controller (see "Customizing your environment" on page 35).

To display the Controller:

Select Window > Toolbars > Controller.

To test a selected Flash movie, do one of the following:

- To launch the Flash Playback window and play the movie, click the Test Movie button in the Controller, select Window > Movie > Test, or press Control+Enter (Windows) or Command+Return (Macintosh).

- To step through the frames of the movie, use the Step Forward and Step Backward buttons in the Controller, select Window > Movie > Step Forward or Window > Movie > Step Backward, or use the Right Arrow and Left Arrow keys.

- To go to the first or last frame in a movie, use the First Frame and Last Frame buttons in the Controller. To go to the first frame, you can also select Window > Movie > Rewind.

- To stop playback, click the Stop button in the Controller, select Window > Movie > Stop, or press Enter (Windows) or Return (Macintosh).

- To resume playing the movie when it has stopped, click the Play button in the Controller, select Window > Movie > Play, or press Enter or Return again.

To change movie settings:

1 Click the Movie Settings button in the Controller, or select Window > Movie > Settings.

2 In the Movie Settings dialog box, select options to format the movie, as described in "Exporting FreeHand documents as Flash movies" on page 336.

To export a movie:

1 Launch the Flash Playback window and begin creating a SWF file of the FreeHand document by clicking the Test Movie button in the Controller.

2 Select Window > Movie > Test, or press Control+Enter (Windows) or Command+Return (Macintosh).

3 Click the Export button in the Controller, or select Window > Movie > Export.

4 In the Export Movie dialog box, enter a name for the movie and select a location where it will be saved.

5 Click Save.

The movie is saved with the current settings specified in the Movie Settings dialog box.

CHAPTER 12
Saving and Exporting Files

You can save files in Macromedia FreeHand MX in various formats, including FreeHand Document, FreeHand Template, and Encapsulated PostScript (EPS).

You can export FreeHand files in a variety of vector and bitmap formats (including PDF and optimized web formats). For a complete list of export file formats supported by FreeHand MX, see "About export file formats" on page 342.

You can add information to files you plan to export, including copyright, caption, creation date, and other data, using the File Info Xtra.

You can also publish a FreeHand file as an HTML document for display on the web. For information, see "Publishing FreeHand documents as HTML" on page 329.

For information on importing graphics, see "Using Imported Artwork" on page 309.

Saving files

You can save FreeHand files as FreeHand documents, FreeHand templates, or Editable EPS files. To achieve design consistency, use FreeHand templates to create multiple pages with the same layout. For more information, see "Using templates" on page 60.

Editable EPS files can be reopened and edited in FreeHand and then saved in EPS format without reexporting. The Editable EPS format can only be used for single-page documents. On the Macintosh, the Editable EPS format is always saved with a preview.

If a document has been modified since the last save, an asterisk (*) appears in the title bar following the filename.

To save a file:

1   Select File > Save.

2   Name the file and specify a location where it will be saved.

3   Select a file format in which to save the file: FreeHand Document, FreeHand Template, or Editable EPS.

4   Click Save.

To save a file as an alternate version with a different name, location, or file format:

1   Select File > Save As.

2   Repeat steps 2–3 in the previous procedure to give the file a new name, new location, or new file format.

3   Click Save.

Adding IPTC file information

You can use the File Info Xtra to include information, such as author, copyright, creation date, headline, caption, and other data, with files you export from FreeHand. You add the file information in FreeHand using the File Info dialog box. The information is preserved with the file and can be viewed when the file is opened in an application that supports International Press Telecommunications Council (IPTC) data.

To add file information using the File Info Xtra:

1   With a file open in FreeHand, select Xtras > Other > File Info.

2   In the File Info dialog box, enter information in the Origin, Credits, Caption, and Categories and Keywords sections.

> **Note:** The IPTC determines data restrictions, including character limits, for the data text box in the File Info dialog box. For detailed information, see IPTC documentation at www.iptc.org.

3   Click OK.

About export file formats

You can export graphics or text files in the most popular formats, including the following:

- As an ASCII or RTF text file

- As bitmap images in the BMP, GIF, JPEG, TIFF, Targa, or PNG formats

- As bitmap images with layer information in Photoshop 5 (PSD) format

- As vector graphics in a variety of Encapsulated PostScript (EPS) formats, including DCS, for export to other graphics applications or page layout applications

- As vector graphics in Windows Metafile (WMF) or Enhanced Metafile (EMF) format (Windows only)

- As Macromedia Flash movies in SWF format, for display in a browser or in the Macromedia Flash Player

- As FreeHand files, version 8, 9, or 10

- As Adobe Illustrator files, versions 1.1, 88, 3, 4, 5.x, and 7.x

- As PICT files (Macintosh only)

- As PDF (Portable Document Format) documents that can be displayed or printed with Adobe Acrobat

- As RTF text (compatible with Microsoft Word, WordPerfect, PageMaker, QuarkXpress, and other word processing applications)

Most formats are compatible across the Windows and Macintosh platforms. Refer to the table that follows for the supported export file formats.

URLs in a FreeHand document export correctly to SWF and PDF formats. For more information on how to assign URLs to FreeHand objects, see "Attaching URLs to objects and text" on page 327. URLs also export to HTML format (see "Publishing FreeHand documents as HTML" on page 329).

FreeHand export file Format	File extension	Windows	Macintosh	Benefit/usage
Acrobat PDF	.pdf	X	X	Distributes electronic files
Adobe Illustrator 1.1 through 7.x	.ai	X	X	Edits in Illustrator
ASCII text	.txt	X	X	Creates editable text without formatting
Bitmap	.bmp	X	X (selected applications)	Creates bitmap graphics
CMYK EPS	.eps	X	Not applicable	Preserves prepress-ready color
Desktop Color Separations 2.0 (DCS2 EPS)	.eps	X	X	Creates a color-separated EPS for use through OPI or other client-server software
Enhanced Metafile	.emf	X	Not applicable	Creates vector graphic which preserves strokes, fills, and text
FreeHand 8 through 10		X	X	Exports file in previous FreeHand version
GIF	.gif	X	X	Creates graphics for reduced-color and prebuilt custom palettes
JPEG	.jpg	X	X	Creates bitmap graphics that support 24-bit color, for photos or continuous-tone images
Encapsulated PostScript (EPS)	.eps	X	X	Creates generic Encapsulated PostScript without preview
Macintosh EPS	.eps	Not applicable	X	Creates Encapsulated PostScript with PICT preview
MS-DOS EPS	.eps	Not applicable	X	Creates Encapsulated PostScript with TIFF preview
EPS with TIFF Preview	.eps	X	Not applicable	Creates vector graphics
Photoshop 3, 4/5 EPS	.eps	X	X	Creates vector graphics that are rasterized in Photoshop
Photoshop 5 PSD	.psd	X	X	Creates bitmap graphics that can be edited in Photoshop
Portable Network Graphic (PNG)	.png	X	X	Creates bitmap graphics
QuarkXPress EPS	.eps	X	X	Creates an EPS file with a TIFF preview (Windows)
Rich Text Format	.rtf	X	X	Creates editable text with formatting
Macromedia Flash (SWF)	.swf	X	X	Creates SWF movie

FreeHand export file Format	File extension	Windows	Macintosh	Benefit/usage
TIFF (Tagged Image File Format)	.tif	X	X	Creates bitmap graphics
Targa	.tga	X	X	Creates bitmap graphics
Windows Metafile (WMF)	.wmf	X	Not applicable	Creates vector graphics

Choosing an export format

The export format you choose is determined by the intended use for the exported file, and particularly the output device that will be used to produce or display the file. To choose an export format based on the output device, see the following table.

Output device	Suggested export format
Low-resolution PostScript printer	Any compatible file format. An EPS or TIFF image prints most consistently, however.
Non-PostScript printer	Any compatible file format except EPS and DCS. Avoid effects that require a PostScript printer, such as Textured or Custom strokes and fills.
High-resolution printer or imagesetter	EPS and DCS EPS for vector graphics, or CMYK TIFF for color bitmaps. Avoid device-dependent pattern fills and strokes, because results probably won't match expectations.
Slide recorder	EPS format if your slide recorder supports PostScript. Bitmap image format for non-PostScript effects.
Plotter, vinyl cutter, or sign-making machine	Graphic saved in a compatible vector graphics format. See your device documentation to determine compatible formats.
World Wide Web	Flash (SWF) to display FreeHand illustrations as a Flash vector graphic, animation, or interactive movie. A compressible bitmap format such as GIF, JPEG, or PNG created at screen resolution. HTML using Publish as HTML.
Multimedia	Bitmap format such as PICT, BMP, TIFF, GIF, or JPEG at screen resolution for still images; Flash (SWF) format for vector graphic, animation, or interactive movie.

About web formats

GIF, JPEG, and PNG bitmap graphic file formats are commonly used for the World Wide Web because they can be highly compressed for faster transfer across the Internet and because they are supported by most browsers. (Note that the GIF and JPEG formats are more widely supported than the PNG format.)

When preparing graphics for the web, it is a good idea to optimize them first. Optimizing web graphics involves selecting a file format with the best color and compression for your image while maintaining as much quality as possible. After optimizing images, it's also important to preview them in a browser to ensure that they will appear as intended.

You can launch Macromedia Fireworks from within FreeHand to help you prepare your graphics for use on the web. For more information, see "Launching Fireworks to optimize bitmap images" on page 321.

If you plan to export graphics for use on the web, use the following table to choose the best export file format for each:

Feature	GIF	JPEG	PNG
Color depth	8-bit maximum	Up to 24-bit	Up to 32-bit
Compression	Lossless; compresses solid areas of color	Lossy; compresses subtle color transitions	Lossless
Transparency support	Yes	No	Yes
Advantages	Lossless compression Transparency	Ability to control quality loss in compression Excellent compression of photographic images	Lossless compression Alpha transparency High-color support
Disadvantages	Maximum of 256 colors Does not compress gradient colors well	No transparency Loss of quality when compressed	Not completely supported by common browsers without using plug-ins
Typical uses	Cartoon images Logos Animated banners	Scanned photographs Images with complex textures Images with complex radiant colors	Images with high numbers of colors Complex, live transparency

Exporting files

The Export command lets you save your document in a file format other than FreeHand. When you use the Export command, the options that appear in the Export dialog box depend on the selected file format; not all options are available for all formats. See descriptions of the individual file formats for more information. You can export entire files, or selected objects and areas in a file.

You can select export preferences to determine export options for bitmap and vector file formats. You can specify whether to save a preview with exported files, as well as set the file format, dimensions, and quality of the file preview. On the Macintosh, you can include an Extensis Portfolio preview in the exported document, for use in cataloging graphics in a database.

When exporting a file to another application on your system, you can automatically launch the application and open the file in it.

If you update a FreeHand file you have previously exported, you can select Export Again to export the updated file to the same location as the previously exported version.

To export a document:

1 Select File > Export.

2 In the Export Document dialog box (Windows) or the Export dialog box (Macintosh), enter a name for the file and select a location where it will be saved.

Export dialog box: Windows and Macintosh

3 Select the file format from the Save as Type menu (Windows) or the Format menu (Macintosh).

Select the Area option if you've previously defined an export area with the Output Area tool. For more information, see "Exporting an area of a document" on page 348.

4 Select Page Boundary to display page boundaries in the exported file.

5 Select Selected Objects Only to export only selected objects in the FreeHand document.

> *Note:* The Selected Objects Only option is not available when exporting to a FreeHand file format.

6 Click Setup to select options for the export file format. For information on selecting options for the format you have selected, see "Exporting vector artwork" on page 350 or "Exporting bitmap images" on page 352.

7 To launch another application to open the exported file, select Open in External Application. In the dialog box that appears, navigate to the application that will open the image and click OK.

For example, you can open an exported Flash SWF file using Flash or a web browser. You can link each export format to a specific external application; these settings are saved for future exporting.

8 Click Save (Windows) or Export (Macintosh).

Note: If the document being exported contains Hexachrome colors, an alert message states that Hexachrome colors will export as CMYK process colors.

To reexport and update the most recent exported document:

Select File > Export Again.

If the document you are updating is not the most recently exported version, the Export dialog box appears so you can set options before exporting.

To include a thumbnail or preview with files saved or exported in FreeHand format:

1 Display export preferences by doing one of the following:

- In Windows, press Control+U, then click the Export tab.
- On the Macintosh, press Command+U, then click the Export category.

2 Select FreeHand File Preview.

3 Select the file format for file previews: JPEG or BMP.

4 Enter the dimensions for file previews.

5 Set the quality for file previews (JPEG only).

6 Click OK.

To include a color thumbnail or preview with exported EPS files:

1 Display export preferences by doing one of the following:

- In Windows, press Control+U, then click the Export tab.

- On the Macintosh, press Command+U, then click the Export category.

2 Do one of the following:

- In Windows, select Export EPS with Color Previews.

- On the Macintosh, select Bitmap PICT Previews.

3 Click OK.

Exporting an area of a document

You can use the Output Area tool to define a single export area within the workspace for a document. The export area can incorporate selected areas of existing pages, as well as selected areas of the pasteboard. After you define the export area, you can resize or delete it, or view its dimensions in the Object panel. When you save a document, the export area is saved as part of the document attributes.

Note: You can also use the Output Area tool to define a print area. For more information, see "Defining an output area" on page 382.

To define and export an export area in a document:

1 With the document displayed in the Document window, click the Output Area button in the Tools panel or on the Main toolbar.

The pointer becomes the Output Area pointer when you roll over the pasteboard.

2 Drag the pointer in the Document window to define the export area. To view and select multiple pages in the document, reduce the document magnification so that the pages are visible onscreen (see "Magnifying and reducing the view" on page 31).

Release the mouse and drag again if you need to redefine the export area.

3 Select File > Export.

The Export Document dialog box appears.

4 Select Area to export the area you defined.

5 Select additional exporting options as needed (see "Exporting files" on page 345).

6 Click Save.

The defined output area is exported.

To resize an export area:

Place the Output Area pointer on a corner or side handle and drag to resize the export area.

To move the export area on the pasteboard, do one of the following:

- Place the Output Area pointer on the area boundary (not on a corner or side handle). The pointer turns into a Hand pointer. Drag to reposition the export area.

- Use the arrow keys to nudge the export area in the appropriate direction.

To delete an export area definition, do one of the following:

- Press Delete.

- Drag to define a new export area.

About color conversion during export

To maintain color consistency when exporting a file in PDF, EPS, or Illustrator format, or when dragging into another application, you can choose how to convert colors using the Convert Colors To option in the Setup dialog box, which is accessible from the Export dialog box. Converting colors before exporting a document typically is more precise than relying on the import conversion features of other applications. For information on converting RGB colors to CMYK using output options, see "Printing" on page 375.

Using Extensis Portfolio (Macintosh)

FreeHand supports Extensis Portfolio, a program that can catalog thousands of graphics in a single database and provide instant visual access to the cataloged items. You can add keywords to your document for use in cataloging graphics.

To prepare a FreeHand document for Extensis Portfolio catalog, you add keywords and descriptive text to the document using the Portfolio Info command. Then you select the Include a Portfolio Preview option in the Export dialog box on exporting the document; for instructions, see "Exporting files" on page 345.

An Extensis Portfolio preview is created as a PICT file by default. You can also can use a bitmap preview, and specify the preview size, in the Preferences dialog box.

To include a bitmap thumbnail preview for use by Extensis Portfolio:

1 Press Command+U and click the Export category.

2 Select Include Portfolio Preview to include a thumbnail bitmap preview used by Extensis Portfolio for browsing and selecting art from a Portfolio catalog.

3 Click OK.

To add or edit document keywords for use by Extensis Portfolio:

1 Select View > Portfolio Info.

2 In the Keywords text box, assign keywords of up to 31 characters, separated by commas. You can assign up to 200 keywords to a document. For the greatest usefulness, follow these guidelines:

- Use well-defined keywords and apply them consistently throughout an Extensis Portfolio catalog.

- Use multiple keywords for each document.

- Use general and specific keywords for each document.

3 In the Description text box, enter information about the document, up to 254 characters long.

4 Click OK.

To set the size of the Portfolio preview:

1 Press Command+U and click the Export category.

2 Select Include Portfolio Preview.

3 Enter a value or use the slider to set a Bitmap Portfolio Preview size.

4 Click OK.

Exporting vector artwork

You can export vector artwork in EPS format using one of the various Encapsulated PostScript (EPS) formats, a FreeHand document format, or an Illustrator format. Files in each of these formats are EPS files (though FreeHand and Illustrator files have different file extensions and attributes).

You can also export vector artwork in PDF or Flash SWF format (see "Exporting PDF files" on page 358 or "Exporting FreeHand documents as Flash movies" on page 336).

For a complete list of EPS formats supported in FreeHand, see "About export file formats" on page 342.

You can specify options for an EPS file, including the pages in the document to be exported, the color model to be used for exporting colors (CMYK, RGB, or both), whether to include the original FreeHand format file with the exported file (for future editing in FreeHand), and whether to include fonts in the EPS file.

Note: You can also use the vector export option settings to set color space preferences when copying Illustrator and EPS format files to the Clipboard. For more information, see "Setting copy and paste preferences" on page 115.

Exporting to EPS format

Use an EPS file format, including any of the EPS formats, FreeHand formats, or Illustrator formats, to export scalable vector artwork and preserve prepress-ready color.

To export a document in a vector format:

1 Select File > Export.

2 For Save As Type (Windows) or Format (Macintosh), select an EPS format, a FreeHand format, or an Illustrator format.

3 Enter a name for the file and select a location where it will be saved.

4 In Windows, specify the pages to export. Each page exports to a separate EPS file.

5 Click Setup to view secondary options. Some EPS file types don't have secondary options, so skip to step 11 if the Setup button is not available for the EPS file type you selected.

The dialog box appears with secondary options. Setup options vary depending on the type of EPS file you selected as the file format. If you are exporting to QuarkXPress EPS, skip to step 8. If you are exporting to Illustrator 7, skip to step 9.

6 On the Macintosh, specify the pages to export. Each page exports to a separate EPS file.

7 Select Include FreeHand Document to preserve the original FreeHand file with the EPS file. Preserving the FreeHand file lets you reopen the exported file in FreeHand for future editing.

8 Select Include Fonts in EPS to export fonts with the file.

9 Select a Convert Colors To option to maintain color consistency among applications:

CMYK creates standard CMYK output and color separations.

RGB ensures that the exported file's colors will be displayed correctly in image-editing applications such as Fireworks or Photoshop.

CMYK and RGB ensures that the exported file's colors will be displayed correctly in print applications that use PostScript Raster Image Processors (RIPs) such as Illustrator or Photoshop 4 or later.

For more information on converting colors when exporting a document, see "About color conversion during export" on page 349.

10 Click OK to close the secondary options dialog box.

11 Click Save (Windows) or Export (Macintosh) to export the file.

Exporting to Photoshop EPS format

You can export FreeHand artwork to Photoshop as vector artwork using the Photoshop EPS format.

To preserve colors in CMYK mode when exporting to Photoshop, use Photoshop 3 EPS format, or EPS with TIFF (Windows) or Macintosh EPS (Macintosh). Photoshop 4 or later EPS format rasterizes files, and all colors are converted to RGB.

Note: You can export FreeHand files or a portion of a file by copying and pasting or dragging; for more information, see "Copying objects" on page 115. You can also export FreeHand documents to Photoshop as bitmap files, using the Photoshop PSD format (see "Exporting to Photoshop PSD format" on page 357).

To export invisible layers to a Photoshop EPS file:

1 Select File > Document Settings > Output Options.

2 For Objects, select Include Invisible Layers, and click OK.

Exporting to EMF format (Windows)

The Enhanced Metafile (EMF) format is an updated version of the Windows Metafile (WMF) format. EMF offers support for preserving strokes and fills, converting type to paths, and including a file description.

To select options for the EMF format:

1 With the file that you want to export in EMF format displayed in the Document window, select File > Export.

2 In the Export Document dialog box, select Windows Enhanced Metafile (EMF) from the Save As Type pop-up menu.

3 Select Setup.

4 In the Enhanced Metafile Export dialog box, select Include FreeHand Document to include the native FreeHand document in the exported file.

5 Select Convert Type to Paths to convert all text to paths on export.

6 Enter a description in the Description text box to include image or file information with the exported file.

7 Click OK to close the Enhanced Metafile Export dialog box.

Exporting bitmap images

You can export bitmap images in BMP, GIF, JPEG, PNG, Photoshop PSD, Targa, or TIFF format. You can choose the image resolution and specify an anti-aliasing level to smooth jagged edges. In Windows, you can set bitmap export preferences to specify the default resolution and anti-aliasing settings for exported bitmaps.

You can apply an alpha channel to bitmap images in BMP, PNG, Targa, or TIFF format, to create masking and transparency. For information about exporting a bitmap image with an alpha channel, see "Working with alpha channels" on page 353.

Note: If you import a bitmap image with an alpha channel, FreeHand displays the image's transparency onscreen but does not maintain upon export the true alpha channel that was saved with the original image. For more information about imported bitmap graphics, see "Working with bitmap images in FreeHand" on page 318. To export the bitmap image with an alpha channel, you must apply an alpha channel in FreeHand before exporting the image.

To export bitmap images:

1 Select File > Export.

2 For Save As Type (Windows) or Format (Macintosh), select a bitmap format—BMP, GIF, JPEG, PNG, PSD, Targa, or TIFF.

3 Click Setup to specify format options.

4 Select a value from the Resolution pop-up menu, or enter a value in the text box.

5 Select an option from the Anti-Aliasing pop-up menu, or enter a value in the text box.

6 Set format-specific options. For more information, see the appropriate section for the export format you have chosen:

- "Exporting to BMP format" on page 355
- "Exporting to GIF format" on page 355
- "Exporting to JPEG format" on page 357
- "Other export file formats" on page 358
- "Exporting to Photoshop PSD format" on page 357
- "Other export file formats" on page 358
- "Other export file formats" on page 358

7 Click Save (Windows) or Export (Macintosh) to export the image.

To set default resolution and anti-aliasing levels (Windows only):

1 Press Control+U and click the Export tab.

2 Click Bitmap Export to display the Bitmap Export Defaults dialog box.

3 Set the default resolution: 72, 144, or 300 dpi.

4 Set the default anti-aliasing level: None, 2, 3, or 4.

Note: Higher resolution and anti-aliasing settings require larger amounts of memory to rasterize vector images. The same is true for images with bitmap effects applied. If your system has insufficient memory for the settings or effects you have selected, try removing the effects or lowering the resolution or anti-aliasing settings and then reexporting the image.

5 Click OK twice.

Working with alpha channels

Using alpha channels, you can export bitmap images with complex masking and transparency for use in web page graphics, multimedia, video images, and image-editing applications. An alpha channel is a graphic layer that displays transparent areas, opaque areas, and the outline or edge of an object.

An alpha channel masks, or outlines, all objects on a page, and reveals a background graphic through an image. FreeHand can export an alpha channel in the BMP, PNG, Targa, and TIFF formats.

Note: If you import a bitmap image with an alpha channel, FreeHand displays the image's transparency onscreen but does not maintain upon export the true alpha channel that was saved with the original image. For more information about imported bitmap graphics, see "Working with bitmap images in FreeHand" on page 318. To export the bitmap image with an alpha channel, you must apply an alpha channel in FreeHand before exporting the image.

GIF images can also be exported with transparency, but they don't truly contain an alpha channel. For more information, see "Exporting to GIF format" on page 355.

When the image is opened in an application that supports alpha channels, the edges of objects in the image can be easily defined.

Original (left) and exported alpha channel (right)

Note: When FreeHand exports a file, it does not preserve the transparency of objects that have effects applied.

To include an alpha channel for transparency:

1 Select File > Export.

2 Select the TIFF, Targa, PNG, or BMP bitmap file type, and click Setup.

3 Select Include Alpha Channel to create an alpha channel automatically on export.

4 If you want to use a background layer as the alpha channel, select Alpha Includes Background. For more information, see "Defining transparency using a background layer" on page 354.

5 Do one of the following:

- In Windows, click More. For Color Depth, select the 32-bit With Alpha (for PNG, select 32-bit or 64-bit With Alpha). Click OK.

- On the Macintosh, for Color Depth, select the 32-bit With Alpha (for PNG, select 32-bit or 64-bit With Alpha).

6 Click OK to return to the Export dialog box.

7 Click Save (Windows) or Export (Macintosh) to export the document.

Defining transparency using a background layer

You can use a background layer to define custom areas of transparency on graphics exported as bitmap images with alpha channels.

To define a custom transparency using a background layer:

1 Create a graphic.

2 On a background layer, draw the desired mask.

Use only black, white, or grays for masking. White areas in the background layer appear opaque in the resulting bitmap, while black areas appear transparent. Grays or Gradient fills appear transparent with lighter grays appearing more opaque and darker grays appearing more transparent. Because a background layer does not print, defining an alpha channel this way does not affect printing of the document.

3 To export the transparency as an alpha channel, see "Working with alpha channels" on page 353.

Exporting to BMP format

BMP is the Windows standard format for bitmap graphics.

To choose options for the BMP format:

1 With the file that you want to export displayed in the Document window, select File > Export.

2 In the Export dialog box, select BMP from the Save As Type (Windows) or Format (Macintosh) pop-up menu.

3 Click Setup to view secondary options.

4 In Windows, click More.

5 Select a color depth option:

8-bit Uncompressed exports BMP images in 256 colors without any compression.

8-bit Compressed exports BMP images in 256 colors and compresses the BMP on export.

16-bit exports BMP images in thousands of colors.

24-bit exports BMP images in more than 16 million colors.

32-bit with Alpha exports BMP images in more than 16 million colors and includes an alpha channel.

6 Click OK.

Note: For information about the bitmap export options not discussed here, see "Exporting bitmap images" on page 352.

Exporting to GIF format

Graphics Interchange Format (GIF) is a bitmap format developed by CompuServe to easily transfer graphic files online. GIF is an 8-bit (256-color) format that uses lossless LZW compression to reduce image file size by as much as half the original size.

The GIF export format is the best choice for images with large areas of solid color, such as cartoon-like graphics, logos, graphics with transparent areas, or animation. Its small size, high quality, and ability to include transparency makes GIF an ideal format for web pages.

You can dither colors in a GIF to simulate colors that aren't in the 256-color web palette. Dithering simulates colors through the placement of adjacent pixels of different colors. For example, a red color and a yellow color may dither to create an orange color. Dithering creates the appearance of a greater range of colors, but also increases file size.

A GIF image can have one color defined as transparent so that placing the GIF over another image in a web browser reveals the bottom image through the transparency. The GIF format supports full transparency; you cannot have partial transparency.

To create smaller GIF files when exporting, choose a reduced color palette (such as 16 colors, 32 colors, or 64 colors) and select the Optimized Palette option. For higher quality images and files from which you want to remove unnecessary colors, use the WebSnap Adaptive 256 or 128 palettes.

To set GIF format options:

1 Select File > Export and select GIF from the Format menu.

2 Click Setup to view secondary options. For information about these options, see "Exporting bitmap images" on page 352.

3 Click More.

4 Select the Interlaced option to create an image that is displayed in intermittent bands while the full image is downloading.

5 Select an option from the Dither pop-up menu to simulate colors that are not in the current palette. A higher dither setting simulates more colors but can increase file size.

6 Select an option from the Palette pop-up menu:

Exact Palette creates a color palette for the exported GIF with only the colors used in the selected object.

Note: The Exact and WebSnap Adaptive palettes do not support Transparency.

WebSafe 216 includes the standard, 216 Web-safe colors common to Windows and the Macintosh and used by web browsers.

WebSnap Adaptive 256, 128, or 16 creates an adaptive palette of colors that are converted (adapted) to the closest Web-safe color equivalent. WebSnap Adaptive 256 is the default palette.

64 colors, 32 colors, or 16 colors selects a preset color palette to quickly export smaller GIFs by constraining the number of colors to a minimum. If the original colors differ from those in the preset palettes, FreeHand approximates the colors and may produce inconsistent results.

3-3-2 uses the palette of the original FreeHand GIF Import Export Xtra.

Other lets you use a Photoshop palette if you have installed one in your copy of FreeHand MX. Navigate to the installed palette to select it.

Tip: To install a Photoshop palette file (with the extension .aco), place the file in the Palettes folder, which is in the Macromedia/FreeHand/11/English/Settings folder inside your user-specific Application Data (Windows) or Application Support (Macintosh) folder. Because the location of your user-specific Application Data or Application Support folder varies depending on your operating system, refer to your operating system's documentation for information on how to locate it.

7 Select Optimized Palette to create the smallest file with the least number of colors, and remove unused colors from the image's palette.

8 Select Transparent Background to create transparency in a GIF based on objects' outlines.

If you chose a palette other than Exact or WebSnap, the selected color for transparency is highlighted in the palette, and its index number is displayed in the Index box. Boxes with *X*'s indicate unused colors.

9 Define the transparency color by clicking a color swatch in the palette or entering its index number.

10 Click OK.

11 If you selected Transparent Background in step 8, select Include Alpha Channel in the Bitmap Export Defaults (Windows) or GIF Setup (Macintosh) dialog box.

12 Click OK, then click Save (Windows) or Export (Macintosh) to export the GIF image.

Exporting to JPEG format

JPEG (.jpg) is an alternative to GIF developed by the Joint Photographic Experts Group specifically for photographic images. JPEG supports millions of colors (24-bit). The JPEG format is best for scanned photographs, images using textures, images with gradient color transitions, or any images that require more than 256 colors.

JPEG is a lossy format, which means that some image data is discarded when the image is compressed, reducing the quality of the final file. However, image data can often be discarded with little or no noticeable difference in quality. The amount of data discarded during compression is determined by the Image Quality setting you specify for the file.

The following JPEG export options are available:

Image Quality lets you set the percentage of quality to maintain when exporting as JPEG. A higher quality setting preserves more image data but yields a higher file size. A lower quality setting discards more image data but yields a smaller file size.

Progressive JPEG creates an image that downloads as a series of overlays in a browser, enabling a viewer to see a low-resolution version of the image before it is fully downloaded.

For information about the other options available when exporting JPEGs, see "Exporting bitmap images" on page 352.

Exporting to Photoshop PSD format

You can export FreeHand artwork to Photoshop in either the bitmap PSD or vector EPS format. For more information about exporting to Photoshop EPS format, see "Exporting to Photoshop EPS format" on page 351.

When exporting to PSD, a multipage FreeHand document exports as one PSD file, but you can choose to retain FreeHand layers. Retaining layers exports each layer as a flattened bitmap image.

To retain FreeHand layers:

1 Display general preferences by doing one of the following:

• In Windows, press Control+U, then click the General tab.

• On the Macintosh, press Command+U, then click the General category.

2 Select Remember Layer Info and click OK.

3 Select File > Export.

4 In the Export dialog box, select Photoshop 5 for Save As Type (Windows) or Format (Macintosh).

5 Click Setup.

6 In the Photoshop Export dialog box (Windows) or the PSD Export dialog box (Macintosh), select Include Layers.

7 Click OK.

8 Click Save (Windows) or Export (Macintosh) to export the file.

FreeHand rasterizes each layer and exports it to individual layers within Photoshop.

To export invisible layers:

1 Select File > Document Settings > Output Options.

2 For Objects, select Include Invisible Layers and click OK.

For information about the other options available when exporting PSDs, see "Exporting bitmap images" on page 352.

Other export file formats

FreeHand can export graphics in a variety of file formats. This section contains format-specific information about export file formats not covered in other sections.

For general instructions on exporting to any of the following formats, see "Exporting bitmap images" on page 352. For detailed instructions about exporting to specific file formats not covered below, see the appropriate sections earlier in this chapter.

FreeHand can export graphics in the following file formats, among many others:

PNG (.png)   When exporting PNG images, you can select the color depth and compression, as follows:

* Select a color depth of 8-bit, 16-bit, 24-bit, 32-bit with an alpha channel, 48-bit for millions of colors, or 64-bit with an alpha channel.

* Interlaced PNG redraws the image progressively by drawing every other line of pixels and then filling the gaps.

Targa (.tga)   Targa is a bitmap graphic format developed by Truevision, Inc. and is widely used in professional video editing. When exporting Targa images, you can choose color depth and compression, as follows:

* Color depth of 8-bit, 16-bit, 24-bit, or 32-bit with an alpha channel.

* The Compression option compresses Targa images upon export.

TIFF (.tif)   When you export an object or document as a TIFF image, FreeHand rasterizes the document. You can choose color depth options when exporting a TIFF image: 8-bit (256 colors), 24-bit, or 32-bit with alpha.

Exporting PDF files

You can export FreeHand documents to the Adobe Acrobat Portable Document Format (PDF).

The PDF format supports RGB, grayscale, and monochrome bitmaps. The PDF format supports most objects or formatting that can be created or placed in FreeHand, with some exceptions. An alert message appears when you export any incompatible objects.

You cannot export the following effects to PDF format:

* Custom and PostScript fills and strokes, arrowheads, and textured fills.

* Alpha channel transparency.

* EPS images. If an EPS image has a TIFF preview, FreeHand exports the preview instead of the EPS file.

* Text effects.

* Overprinting. Overprinting applied to objects is turned off when exporting to PDF.

In addition, the maximum page size maximum for a PDF document is 3240 x 3240 pixels (about 45 x 45 inches). A larger page is clipped to fit the maximum PDF page size.

To export a PDF file:

1 Select File > Export.

2 In the Export dialog box, select PDF for the file format, and click Setup (Windows) or Options (Macintosh) to display the PDF Export dialog box.

3 In the PDF Export dialog box, select All to export all pages, or select From and enter a page range.

4 Select Color or Grayscale Image Compression options to compress images in JPEG format and reduce file size. A higher compression setting yields a smaller file size, but may reduce image quality.

For print, choose little or no compression. For onscreen display, choose higher levels of compression for small files that are easier to transmit and download.

5 Select an option for Convert Colors To to maintain color consistency among applications: CMYK for standard CMYK output and color separations, RGB for use in Fireworks or Photoshop, or CMYK and RGB for print applications with a PostScript RIP such as Illustrator or Photoshop 4 or later.

6 For Compatibility, select an Acrobat version to determine which additional options are available:

Acrobat 4 converts gradients to PostScript 3 linear and radial gradients and envelopes as flattened vector graphics.

Acrobat 3 and 4 support compressed text and graphics, the ASCII text format, notes, URLs, and the Editable text format.

Acrobat 2 supports ASCII format and Editable text format.

Acrobat 1 supports only the ASCII format.

7 Select additional options, depending on the Acrobat version you selected in step 6:

Compress Text and Graphics compresses text and graphic elements in the PDF document (using the PostScript language imaging model). If you selected a Color or Grayscale Image Compression option in step 4, bitmap images are compressed in JPEG format.

ASCII Format exports documents as 7-bit, to prevent problems when PDF files are shared on older networks and e-mail systems. Deselect this option to export ASCII documents as 8-bit.

Editable Text Format exports editable text with the PDF file. Select this option only if you plan to edit the document in FreeHand or Illustrator; or to prevent FreeHand text blocks from breaking into several text blocks during export. When selected, this option produces a larger document. Deselect this option if your goal is screen and print output.

Export Notes exports notes you added in the Note text box in the Navigation panel as PDF annotations (see "Adding names and notes to objects" on page 124).

Export URLs exports URLs as rectangular, hyperlinked annotations.

Embed Fonts embeds TrueType and Type 1 fonts in the document.

8 Click OK.

9 Name the file and click Save (Windows) or Export (Macintosh) in the Export dialog box.

Exporting text

You can drag text to export it if the destination application supports the drag-and-drop text feature. You can also export text by using the Copy and Paste commands or by using the Export dialog box. You can export rich text format (RTF) text with formatting intact; however, the Outline, Subscript, and Superscript effects are not maintained on export.

You can export text with inline graphics for use with other applications, including FreeHand versions 8 and later, and in the EPS export format (except Photoshop 3 EPS format), or in any bitmap format (BMP, GIF, JPEG, PNG, PSD, Targa, and TIFF). You can also export text with inline graphics in PDF or SWF format.

To export a text file with inline graphics to Illustrator or Photoshop 3 EPS export format, convert the text with inline graphics to paths.

If you export a file containing text with inline graphics to a file format that does not support graphics, bullets replace the inline graphics in the exported file.

To export text files:

1 Select File > Export.

2 In the Export dialog box, name the text file and select a location for it.

3 Select RTF text or ASCII text from the Save As Type (Windows) or Format (Macintosh) menu, and click Save (Windows) or Export. (Macintosh).

Only text (no graphics) is included in the exported document. Linked text blocks export in the order that they are linked. Unlinked text blocks export in their stacking order from back to front, first page to last page.

CHAPTER 13
Color Management

You can use color management strategies in Macromedia FreeHand MX to adjust the appearance of artwork on your monitor or in printed proofs, to match as closely as possible the appearance the artwork will have in final output (whether print or online). Color management is intended to provide you with the most accurate preview of the final output that can be achieved.

If your final output will be online (on the web or in another multimedia format), the appearance of your FreeHand artwork will be affected by the viewers' computer system, software, and color settings. If your final output will be in print, the appearance will be affected by the type of output device used to create the printed document.

Whether you are preparing artwork for print or online use, you will want to ensure the closest possible match between the colors that appear onscreen on your system and the colors produced by a printer or another computer system used to display the artwork.

Differences between onscreen colors and those in the final output are inherent. Monitors display colors using additive RGB color, while printing presses re-create colors using subtractive CMYK color. Because the RGB gamut, or range of colors, is much larger than the CMYK gamut, some colors displayed on a monitor can only be approximated in print.

Illustrations typically pass through one or more electronic devices or software applications on the way to final output. Printing a FreeHand document to a local printer, for example, involves FreeHand, your computer's monitor and operating system, and the printer. Color interpretation from one device or application to another can vary. Even colors in artwork created strictly for the Internet can vary from monitor to monitor.

Furthermore, some elements of a FreeHand illustration may come from another electronic device or another software application. One device or application's interpretation of colors can differ from that of another device or application. Even between devices or applications of the same type—or the same brand—color interpretation can vary depending on age, wear, current settings, and other factors.

Color management strategy

A color management system (CMS) interprets and translates color accurately between devices. A CMS compares the color space (the gamut of colors a device can display) in which a color was created to that in which the same color will be output, and adjusts the color as needed to match the color on preview devices as closely as possible to the color that will be produced in the final output (either print or online).

The FreeHand color management workflow

To manage color effectively in FreeHand, you can perform some or all of the following procedures:

- Calibrate your monitor to adjust monitor colors to match colors in the output device profile. To adjust the monitor colors by matching them to printed samples or swatches, see "Calibrating monitor colors visually" on page 365.

- Build or specify profiles for each device in the workflow to characterize the device's color space. See your device's documentation to learn how to calibrate it. For more information, see "About color profiles" on page 364.

- Select the Kodak Digital Science or Apple ColorSync color management system and then select options, or use the Color Tables option for limited color management. For more information, see "Using Kodak Digital Science and Apple ColorSync CMS" on page 367 or "Using color tables" on page 372.

- When printing four-color separations using Kodak Digital Science or Apple ColorSync, choose a Separations Printer profile. To print composite proofs of color separations, choose a Composite Printer profile. For more information, see "Choosing printer profiles" on page 369.

About color profiles

Each device in the workflow must be calibrated to its profile for effective color management.

A profile describes a device's color space mathematically, by mapping the color gamut and other characteristics of each device. The profile is created by measuring the output range of a particular color device under controlled conditions with spectrophotometers, colorimeters, or other measuring devices, and using special software to build the profile.

Custom profiles are more accurate than vendor-supplied profiles. Building custom profiles requires a thorough knowledge of color management and its tools.

The Kodak Digital Science and Apple ColorSync color systems use standard profiles approved by the International Color Consortium (ICC) to help you manage color in FreeHand. These model-specific, ICC-compatible profiles supplied by the manufacturers appear in the FreeHand Color Management dialog box, along with custom profiles.

FreeHand reads all ICC version 2-compatible profiles. Additional manufacturer profiles are available on the Internet at www.colorsync.com. Device manufacturers' websites may also include profiles.

To use color profiles between Windows and Macintosh platforms, you should adhere to the following naming conventions:

- Add a period and the three-letter extension ICM to the profile name.

- Avoid special characters such as slashes (/) and parentheses.

- Use names of no more than 27 characters in length, followed by a period and the ICM extension. (For example, my_printer.icm.)

- In Windows, store profiles in the FreeHand ICM folder or in the Color folder within the Windows/System (or System 32) folder.

- In Mac OS 9, store profiles in the FreeHand ICM folder or in the Color folder within the ColorSync Profiles folder in the System folder.

- In Mac OS X, store profiles in the FreeHand ICM folder, in the Library/ColorSync folder, or in the Library/Color folder within your user-specific folder. For information on how to locate this folder, refer to your operating system's documentation.

Calibrating monitor colors visually

You can use the Adjust Display Color option to calibrate monitor colors visually to match sample output colors, or numerically to match specific color values.

To match monitor colors with a printer's output, you can print sample colors on the printer and compare the printed output with the monitor colors. This color management option is simpler than using the Kodak Digital Science or Apple ColorSync CMS, but it may be less accurate.

To calibrate your monitor using the Adjust Display Colors option:

1 Choose a set of test colors to which you want to calibrate your monitor. Use a color swatch book, or print sample colors from the target printer.

2 To display colors preferences, do one of the following:

- In Windows, press Control+U, then click the Colors tab.

- On the Macintosh, press Command+U, then click the Colors category.

3 Select Adjust Display Colors from the color management type pop-up menu.

4 Click Calibrate.

The Display Color Setup dialog box appears.

Click to open the Display Color Setup dialog box.

Click a color to adjust the color's values.

5 Click any color in the Display Color Setup dialog box to display the Color dialog box (Windows) or Apple Color Picker (Macintosh).

Windows Color dialog box

Apple Color Picker

6 Hold color samples from the output device or color swatch book next to the color on the screen to compare them, and use the system color picker to adjust the onscreen color to match the sample.

Using Kodak Digital Science and Apple ColorSync CMS

FreeHand includes the Kodak Digital Science (KDS) color management system (CMS) for use with Windows or Macintosh operating systems. In addition, if you are working on a Macintosh system with the Apple ColorSync engine installed, FreeHand enables you to use the Apple ColorSync color management system.

If the Kodak Digital Science CMS does not appear in your installed copy of FreeHand, see "Verifying installation of the Kodak Digital Science CMS in Windows" on page 368.

Setting CMS options

For both the Kodak Digital Science and the Apple ColorSync CMS, you can choose options to control how colors appear onscreen or in printed previews.

Note: System-level color-related features, such as Gamma Control, may conflict with the FreeHand color management systems.

To set CMS options:

1 Display colors preferences by doing one of the following:

• In Windows, press Control+U, then click the Colors tab.

• On the Macintosh, press Command+U, then click the Colors category.

2 Select Kodak Digital Science or Apple ColorSync from the color management type pop-up menu.

3 Choose whether to manage spot colors electronically:

• Select Color Manage Spot Colors to use the color management system to adjust the screen display of spot colors for different devices in the workflow.

• Deselect Color Manage Spot Colors to turn off color management for the screen display of spot colors and adjust spot colors manually. Use the appropriate swatch book (for example, PANTONE) to check spot colors for color accuracy.

4 Choose whether to rebuild color tables if you switch between KDS and Apple ColorSync or change any of the profile settings:

• Select Rebuild Color Tables for FreeHand to automatically rebuild color tables each time you switch between KDS and Apple ColorSync.

• Deselect Rebuild Color Tables for FreeHand to retain the same color tables when switching between KDS and Apple ColorSync. Deselecting this option lets you try different color management settings without affecting the color tables.

Color tables are used only when you select the Color Tables option under Color Management Type in colors preferences. For more information, see "Using color tables" on page 372.

5 Click Setup to open the Color Management Setup dialog box.

6 In the Color Management Setup dialog box, select an ICC-compatible monitor profile from the Monitor pop-up menu.

7 For Monitor Simulates, choose how to set your monitor to simulate the color gamut displayed by the final output device:

None displays RGB colors according to the monitor profile and CMYK colors as RGB according to the printer profile. This option leaves the monitor display and printer profiles unchanged. Select this option when the final output will be displayed online (for example, on the web).

Composite Printer simulates the appearance of a composite printout in which all colors are printed on a single plate (instead of each color being printed to a separate plate).

Separations Printer simulates the appearance of printed color separations, in which each color is printed to a separate plate.

8 For Separations Printer, select a printer profile that describes the separations printer you intend to use. Perform this step if you selected Separations Printer for Monitor Simulates in step 7, or if you will print simulated separations on a composite printer (see step 10).

9 For Intent, select a method for translating colors between color spaces in different devices in the workflow. For more information, see "About rendering intent" on page 370.

10 If you are printing proofs of four-color separations on a composite printer, select Composite Simulates Separations to print simulated color separations.

Note: Do not select this option if you are using the composite printer for final output, or if your files will be processed on a pre-press raster image processor (RIP) that requires composite files. Select this option only to produce simulated four-color separations for proofing purposes.

11 If you selected Composite Simulates Separations in step 10, select a printer profile for Composite Printer to be used for printing simulated color separations. For more information, see "Choosing printer profiles" on page 369.

12 For Default RGB Image Source, select a device profile based on how the image was created, to improve the display and output of RGB images.

You can also select profiles for individual RGB images. For more information, see "Managing RGB image color for selected images" on page 370.

13 Click OK to close the Color Management Setup dialog box, and click OK again to close the Preferences dialog box.

Verifying installation of the Kodak Digital Science CMS in Windows

If the Kodak Digital Science CMS is correctly installed, it will appear in the Color Management section of the Colors Preferences dialog box, in the Type pop-up menu. If the KDS option does not appear, you can verify that it is installed on your system.

To verify installation of the Kodak Digital Science CMS:

Verify that the CMSCP folder is in the Macromedia\FreeHand\11\CMSCP folder exists within your All Users\Application Data folder.

Note: The location of the All Users\Application Data or Application Support folder can vary depending upon your operating system. For information on how to locate this folder, refer to your operating system's documentation.

If this method is unsuccessful, you may need to uninstall and reinstall FreeHand.

Choosing printer profiles

You can choose a printer profile to specify the type of printer that will be used to print four-color separations. The Separations Printer options include ICC-compatible CMYK printer profiles.

A generic Hexachrome printer profile is also available for six-color (CMYKOG) output when a more suitable profile for your separations printer is not available. A Hexachrome profile separates documents to six-color output but displays RGB colors according to the monitor profile and CMYK colors according to the default (CMYK) printer profile. Colors print as follows:

- Hexachrome process colors print using the defined Hexachrome values. RGB process colors and RGB TIFFs separate into Hexachrome colors.

- CMYK process colors and CMYK TIFFs remain unchanged when printing as Hexachrome. CMYK colors do not appear on the orange plate or the green plate.

- Spot colors (CMYK or RGB) print on their separate plates. If Print Spot Colors as Process is selected (in the Separations panel of the Print Setup dialog box), the colors separate to CMYK values.

If you are printing proofs of simulated four-color separations on a composite printer, you can also choose a printer profile to specify the type of printer that will be used to print the proofs. The Composite Printer options include ICC-compatible CMYK and RGB printer profiles.

For either the Separations Printer or the Composite Printer profile, the Default (CMYK) option provides acceptable results for most printers. However, for more precise color management, you should choose a device-specific profile.

To choose a Separations Printer profile:

1 Display colors preferences by doing one of the following:

- In Windows, press Control+U, then click the Colors tab.

- On the Macintosh, press Command+U, then click the Colors category.

2 Select Kodak Digital Science or Apply ColorSync from the color management type pop-up menu.

3 Click Setup.

4 Select an option from the Separations Printer pop-up menu:

- Select Default (CMYK) to achieve reasonable results with most printers.

- Select one of the ICC-compatible printer profiles for the most accurate color management.

- Select a Hexachrome profile to separate to six-color output but display RGB colors according to the monitor profile and CMYK colors according to the default (CMYK) printer profile.

5 Click OK to close the Color Management Setup dialog box.

6 Click OK to close the Preferences dialog box.

To choose a Composite Printer profile for simulated four-color separations:

1 Display colors preferences by doing one of the following:

• In Windows, press Control+U, then click the Colors tab.

• On the Macintosh, press Command+U, then click the Colors category.

2 Select Kodak Digital Science or Apply ColorSync from the color management type pop-up menu.

3 Click Setup.

4 In the Color Management Setup dialog box, verify that Composite Simulates Separations is selected.

5 Select an option from the Composite Printer pop-up menu:

• Select Default (CMYK) to achieve reasonable results with most printers.

• Select one of the ICC-compatible printer profiles for the most accurate color management.

6 Click OK to close the Color Management Setup dialog box.

7 Click OK to close the Preferences dialog box.

About rendering intent

Translating colors to a different color space may require adjusting the colors to accommodate the gamut of the destination color space. You can choose from different translation rules—called rendering intents—to determine how the source colors are adjusted and optimized for the intended use of the graphic.

Rendering intent results depend on the graphical content of documents and on the profiles used to specify color spaces.

You can choose from the following options:

Perceptual is the best choice for photographic images; this option preserves the visual relationship between colors as what's natural to the human eye, even if color values change.

Saturation is the best choice for colorful artwork such as graphs, charts, and presentation graphics. This option creates vivid color at the expense of accuracy.

Absolute Colorimetric is the best choice for matching logo colors. This option preserves colors that fall inside the destination gamut and maintains color accuracy at the expense of relationships between colors. For example, two colors that are distinct in the source space may be mapped to the same color in the destination space.

Relative Colorimetric is the best choice for illustrations. This option is identical to Absolute Colorimetric except that it compares the white point (extreme highlight) of the source color space to that of the destination color space and shifts all colors accordingly.

Managing RGB image color for selected images

To improve the display and output of a selected RGB image, you can assign a device profile to the image based on how the image was created. The profile determines the colors that the image displays and prints within that profile's color gamut. Setting profiles for individual images does not change the default RGB image profile.

When you open an RGB image with an assigned device profile on another computer system, you can preserve the assigned device profile if the profile is installed on that system.

Note: Some RGB image formats can contain embedded color profiles. If you import an image with an embedded color profile while CMS is active, FreeHand uses the embedded profile by default.

Setting profiles for selected RGB images

You can use the Object panel to set profiles for individual images. For example, you can assign one profile to an image adjusted to the monitor in Photoshop, and another profile to a scanned image.

To assign a profile to a selected RGB image:

1 Import or select the RGB image in the document.

2 Select Window > Object.

The Object panel displays the RGB file type and image source.

3 Select a device profile from the Image Source pop-up menu.

Note: Selecting the Changing Object Changes Defaults option in object preferences does not change the Image Source menu.

About preserving RGB device profiles

For device profiles for RGB images to be preserved when the images are opened on another computer system, the profiles must be installed on that system. If the profiles have not been installed or are not available, the Missing Image Sources dialog box lists the missing device profiles.

If you install the original profiles and then reopen the image, the profile assignments of the RGB images remain intact. If you do not install the original device profiles, the default device profile for RGB images is temporarily assigned to the image. If you reopen the image without replacing the original device profile and then choose a new device profile, the new profile is assigned to RGB images.

Using color tables

You can use color tables to apply limited color management strategies in your workflow. The Color Tables option manages only CMYK display and RGB conversion.

The prebuilt color tables that ship with FreeHand are based on a set of default device profiles that will provide acceptable results with most output devices.

When you use the Color Tables option, you can choose whether to manage spot colors electronically, and you can choose how your monitor will simulate the color space of the final output device.

You can choose to rebuild the default color tables in FreeHand using the Kodak Digital Science or Apple ColorSync CMS. You can also choose a device profile for your monitor or separations printer.

Note: You cannot apply a profile to an RGB or bitmap image when the Color Management option is set to Color Tables, Adjust Display Colors, or None in colors preferences.

To use color tables:

1 Display colors preferences by doing one of the following:

• In Windows, press Control+U, then click the Colors tab.

• On the Macintosh, press Command+U, then click the Colors category.

2 Select Color Tables from the color management type pop-up menu.

3 Choose whether to manage spot colors electronically:

• Select Color Manage Spot Colors to use the color management system to adjust spot colors for different devices in the workflow.

• Deselect Color Manage Spot Colors to turn off color management for the screen display of spot colors and adjust spot colors manually. Use the appropriate swatch book (for example, PANTONE) to check spot colors for color accuracy.

4 For Monitor Simulates, choose how to set your monitor to simulate the color gamut displayed by the final output device:

None displays RGB colors according to the monitor profile and CMYK colors as RGB according to the printer profile. This option leaves the monitor display and printer profiles unchanged.

For example, an artist designing graphics for onscreen display might select None for Monitor Simulates in order to create a brighter RGB display.

Separations Printer simulates the appearance of printed color separations, in which each color is printed to a separate plate.

5 Click OK.

To rebuild color tables using specific monitor or separations printer profiles:

1 Display colors preferences by doing one of the following:

- In Windows, press Control+U, then click the Colors tab.

- On the Macintosh, press Command+U, then click the Colors category.

2 Select Kodak Digital Science or Apple ColorSync from the color management type pop-up menu.

3 Select Rebuild Color Tables to automatically rebuild the default color tables according to the Color Management System you selected in step 2.

4 Click Setup.

5 In the Color Management Setup dialog box, for Monitor select an ICC-compatible monitor profile to be used for managing color on your monitor.

6 For Separations Printer, select a printer profile to be used for printing color separations.

7 Click OK to close the Color Management Setup dialog box.

8 Click OK to close the Preferences dialog box and rebuild the color tables.

9 Redisplay colors preferences by doing one of the following:

- In Windows, press Control+U, then click the Colors tab.

- On the Macintosh, press Command+U, then click the Colors category.

10 In the Preferences dialog box, under Color Management, select Color Tables from the color management type pop-up menu.

Note: The monitor and separations printer profiles you selected in steps 5 and 6 do not appear under the Color Management options for Color Tables. However, FreeHand will use the profiles you selected in performing color adjustments.

11 Click OK to close the Preferences dialog box.

Printing from Macromedia FreeHand MX is straightforward whether you want to output your document to a desktop printer or engage professional prepress services for color-separated high-resolution output.

You can select a variety of printing options, depending on the output device that you will use. You can preview print settings onscreen, apply prepress options for color separations, print only specified objects or layers in a document, generate a document report for use by a prepress service bureau, and set other options.

Printing a document

In the Print dialog box, you can select general options such as page range, number of copies, and image scaling.

To print a document in Windows:

1 Select File > Print to display the Print dialog box.

2 Select a printer from the Printer pop-up menu.

3 Select the print range: All, the current page, or a specific page range.

4 To print only the currently selected objects, select Selected Objects.

5 For Copies, enter the number of copies to print.

6 To print all colors to a single page, select Composite.

7 To print color separations according to your printer setup, select Separations.

8 To assign predefined prepress settings for color separations and other options, select an option from the Print Setting pop-up menu.

9 To choose a PostScript Printer Description (PPD) file, select Use PPD; then double-click a PPD in the Select PPD dialog box.

10 To select color management preferences, click Color Management. (For more information on color management, see Chapter 13, "Color Management," on page 363.)

11 For Scale Percentage, select one of the following options to scale the printed document horizontally or vertically, without affecting the original document:

• Select Uniform and enter a value to print an illustration larger or smaller than actual size.

• Select Variable and enter separate horizontal (x) and vertical (y) dimensions to print an illustration larger or smaller than actual size.

• Select Fit on Paper to scale each page to fit into the printable area.

12 Select Tile to print a large document on separate sheets, or a number of small pages on a large sheet. Select manual or automatic tiling. If you select automatic tiling, enter a value for overlap.

13 Click OK to print.

To print a document in Mac OS 9:

1 Select File > Print to display the Print dialog box.

2 Select a printer from the Printer pop-up menu.

3 For Copies, enter the number of copies to print.

4 Select Collated to print multiple copies sequentially. Select Composite to print multiple copies of each page together.

5 For Pages, select All, or enter a specific page range.

6 Select FreeHand MX from the print options pop-up menu.

7 To print color separations according to your printer setup, select Separations. Deselect it to print all colors to a single page.

8 To print only the currently selected objects, select Selected Objects Only.

9 For Scale Percentage, select one of the following options to scale the printed document horizontally or vertically, without affecting the original document:

• Select Uniform and enter a value to print an illustration larger or smaller than actual size.

• Select Variable and enter separate horizontal (x) and vertical (y) dimensions to print an illustration larger or smaller than actual size.

• Select Fit on Paper to scale each page to fit into the printable area.

10 To print a large document on separate sheets, or a number of small pages on a large sheet, select Tile. Select manual or automatic tiling. If you select automatic tiling, enter a value for overlap.

11 To choose color management preferences, click Color Management. (For more information on color management, see Chapter 13, "Color Management," on page 363.)

12 To assign predefined prepress settings or to choose a PostScript Printer Description (PPD) file, click Advanced, then do one of the following:

- To assign prepress settings for color separations and other options, select an option from the Print Setting pop-up menu.

- To use a PPD, select Use PPD, double-click a PPD in the Open dialog box, and then click Open.

13 If necessary, click OK to close the Print Setup dialog box.

14 Click Print.

To print a document in Mac OS X:

1 Select File > Print to display the Print dialog box.

Print	

Printer: HP 8100 5W

Saved Settings: Standard

Copies & Pages

Copies: 1 ☑ Collated

Pages: ○ All
⊙ From: 1 to: 999

(?) Preview Cancel **Print**

2 Select a printer from the Printer pop-up menu.

3 For Copies, enter the number of copies to print.

4 Select Collated to print multiple copies sequentially. Deselect the option to print multiple copies of each page together.

5 For Pages, select All, or enter a specific page range.

6 Select FreeHand MX from the print options pop-up menu.

Print

Printer: HP 8100 5W

Saved Settings: Standard

FreeHand MX

Normal   Advanced...

☐ Separations   ☐ Print output area

☐ Selected objects only   ☐ Print page boundary

Scale %: Uniform

100

☐ Tile Manual   Overlap: 18 points

(?) Preview Cancel **Print**

7 To print color separations according to your printer setup, select Separations. Deselect it to print all colors to a single page.

8 To print only the currently selected objects, select Selected Objects Only.

9 For Scale Percentage, select one of the following options to scale the printed document horizontally or vertically, without affecting the original document:

• Select Uniform and enter a value to print an illustration larger or smaller than actual size.

• Select Variable and enter separate horizontal (x) and vertical (y) dimensions to print an illustration larger or smaller than actual size.

• Select Fit on Paper to scale each page to fit into the printable area.

10 To print a large document on separate sheets, or a number of small pages on a large sheet, select Tile. Select manual or automatic tiling. If you select automatic tiling, enter a value for overlap.

11 To assign predefined prepress settings or to choose a PostScript Printer Description (PPD) file, click Advanced, then do one of the following:

• To assign prepress settings for color separations and other options, select an option from the Print Setting pop-up menu.

• To use a PPD, select Use PPD.

12 If necessary, click OK to close the Print Setup dialog box.

13 Click Print.

Using print preview

A print preview lets you view and adjust how your document will print with the current print settings on the selected paper. You can adjust objects within the print area to control where they'll print on the paper; the saved image is not affected.

The print preview matches your output choices. For example, if you chose Fit on Paper from the Scale Percentage menu in the main Print dialog box, the print preview scales the selected page and displays it onscreen at the correct size.

The print preview displays a nonprinting bounding box of what will print on the selected paper (called the print area) as a dotted rectangle. The bounding box size varies according to the selected printer paper size, indicated by the gray outline. The area that prints is defined in the selected printer driver or PPD and is limited by the document page. You can also define a custom print area (see "Defining an output area" on page 382).

A bleed area appears if the bleed is greater than 0.

To preview printing:

1 Select File > Print to display the Print dialog box.

2 On the Macintosh, select FreeHand MX from the print options pop-up menu.

3 Do one of the following:

• In Windows: For PostScript printers, click Advanced. For non-PostScript printers, click Preview.

Print area

Crop marks (PostScript printers only)

Bleed area only appears if bleed is greater than zero

Registration marks (PostScript printers only)

• On the Macintosh: For PostScript or non-PostScript printers, click Preview.

4 Select a print preview mode from the pop-up menu at the bottom of the preview window:

X-Box displays the page with an X and the bleed. Select this option to make the Print dialog box open more quickly.

Keyline displays the objects on the page in keyline view.

Preview displays the objects on your page as they will print.

To reposition objects in the print preview for printing:

1 Position the mouse pointer in the print preview area; the pointer becomes a Hand pointer.

2 Use the Hand pointer to reposition objects on the paper for printing.

Note: Repositioning objects in the print preview area repositions the objects for the current output only. The objects in the document file are not affected.

To restore the original location of objects:

1 Move the pointer to the gray area of the print preview pasteboard to display the Reset arrow.

2 Click with the Reset arrow to restore the original location.

Defining an output area

You can use the Output Area tool to define a single print and export area within the workspace for a document. The output area can incorporate selected areas of existing pages, as well as selected areas of the pasteboard. After you define the output area, you can resize or delete it, or view its dimensions in the Object panel. When you save a document, the output area is saved as part of the document attributes.

You can use the Output Area tool to print multiple pages, such as business cards, on a single sheet.

To define an output area in a document:

1 With the document displayed in the Document window, click the Output Area button in the Tools panel.

The mouse pointer becomes an Output Area pointer when you roll over the pasteboard.

2 Drag in the Document window to define the output area. To view and select multiple pages in the document, reduce the document magnification so that the pages are visible onscreen (see "Magnifying and reducing the view" on page 31).

Release the mouse and drag again to redefine the output area.

To resize an output area:

Place the Output Area pointer on a corner or side handle, and drag to resize the output area.

To reposition the output area on the pasteboard, do one of the following:

• Place the Output Area pointer on the area boundary (not on a corner or side handle). The pointer turns into a Hand pointer. Drag to reposition the output area.

• Use the arrow keys to nudge the output area in the appropriate direction.

To delete an output area definition, do one of the following:

• Click outside the defined output area.

• Press Delete.

• Drag to define a new output area.

To print an output area:

1 Select File > Print, then select Area.

2 Select Print Page Boundary to print page boundaries. Deselect this option to print objects on pages, but not page boundaries.

3 Click OK (Windows) or Print (Macintosh).

The defined output area is saved with the document.

About printing fonts

To ensure that the text on your pages displays and prints correctly, it's important to choose the correct type of font, PostScript or TrueType, for your output and to use that type of font exclusively for production work.

In general, use PostScript fonts for output to PostScript printers or for exporting a document as an EPS file, and use TrueType fonts for output to desktop or non-PostScript printers. If you are working with a prepress service provider or service bureau, ask for a recommendation on font formats before beginning your FreeHand artwork.

You can use a type manager to improve onscreen text display and font management. Adobe Type Manager (ATM) supports all of the text effects available in FreeHand. ATM requires PostScript (Type 1) fonts, but does not require output to a PostScript printer.

If you open or import a document that contains fonts not installed on your system, you will be prompted to replace missing fonts.

About printing PostScript fonts

PostScript fonts are the best choice if your final output device is a PostScript printer or imagesetter, or if you want to export your document as an EPS file. All text effects and transformations are available for PostScript fonts.

PostScript fonts have three components:

• The screen or bitmap font for a specific point size (Macintosh)

• The printer or outline font

• Font metrics—the information used to compose the font—including kerning and spacing data

In Windows, a PostScript font is available for output if the font is listed in the printer driver for the selected target printer; if the font metrics filename appears in the target printer's section in the Win.ini file; or if the font was installed with a font management utility such as ATM (Windows 98 or NT 4) or with the Windows Control Panel.

On the Macintosh, a PostScript font is available for output when the screen font is properly installed in the system. The Macintosh does not require a separate font metrics file because font metric information is stored in the screen font. Store PostScript screen and printer fonts in the Fonts folder within the System folder. Drag a font file to the System folder to store the file in the appropriate location automatically. Alternatively, use a font management utility such as ATM.

For more information on installing PostScript fonts in FreeHand, see the related TechNotes available at www.macromedia.com.

About printing TrueType fonts

TrueType fonts are best if your final output device is a desktop printer, especially a non-PostScript printer. TrueType fonts retain quality when scaled, but text effects and transformations may not display or print to a PostScript printer as effectively as a PostScript font with ATM.

Bitmap fonts such as PCL (Windows) are often included with non-PostScript printers. PCL fonts generally provide a limited, nonscalable set of sizes, cannot be transformed, and do not support special text effects.

In Windows, you install TrueType fonts using the Control Panel, and they normally reside in the Windows folder.

On the Macintosh, TrueType fonts are located in the Fonts folder within the System folder.

Applying halftone settings to selected objects

If you've included screened objects in your artwork, you can use a PostScript printer to print those objects at halftone settings that differ from those applied to the document as a whole.

You can override object-level halftone settings when choosing separations options in the Print Setup dialog box.

To apply halftone settings to selected objects:

1   Select an object or objects in the document.

2   Select Window > Halftones.

3   For Screen, select a halftone dot shape. Select Default to use the shape specified in the Separations tab in the Print Setup dialog box.

4   Enter a screen angle in degrees or drag the dial to specify the Angle setting.

5   Enter a screen frequency or drag the slider to specify Frequency.

About choosing an output device

If you are working with a limited budget, or want to first print black-and-white or color proofs of your illustration, use a desktop printer. For these tasks, you can usually use output devices available at your workplace.

If you require accurate, high-quality color reproduction, use a high-resolution PostScript output device available through a service bureau, commercial printer, or other service provider. Be sure to check with the provider to determine what files and prepress options are needed to create the output you have in mind. Also, keep in mind that using an external service provider requires additional time in your production schedule.

You can output your document to a PostScript file that contains all of the print options you have applied. In some cases a service provider will use the PostScript file (rather than the FreeHand file) to create the printed document.

A service provider can output your document in a variety of forms. For example, an imagesetter prints high-resolution, camera-ready art or color separations on either paper or film. A dye sublimation or high-resolution proofing device (such as the 3M Matchprint system) prints high-resolution color proofs. A film recorder can create 35-mm slides of your illustrations.

Guidelines for faster printing

For fastest printing and smaller file size, use efficient drawing techniques. Techniques that reduce print times also help speed screen redrawing and make editing easier.

To reduce memory requirements for processing objects, specify a paper size no larger than the illustration actually covers.

You can speed printing and reduce file size by following these guidelines when you create your artwork:

- Avoid unnecessary complexity. Delete any object not visible in Preview mode. FreeHand processes all objects drawn on foreground layers when you print, even if they are hidden behind other objects. You can also use the Delete Xtras to delete empty text blocks and unused named colors.

- When possible, use straight paths instead of curves to reduce printer time and memory slightly. For curves, use the fewest points possible, and shape curves using point handles instead of adding more points.

- Use a higher flatness value.

- Reduce the number of subpaths in a composite path.

- Apply special effects conservatively—for example, do not use numerous multicolor radial fills. Use a basic fill when possible. Use special fills—such as lenses and gradient fills—and text effects sparingly.

- Clean up paths created with the Trace tool or the Pencil tool by choosing Modify > Alter Path > Simplify or Xtras > Cleanup > Simplify.

- Simplify clipping paths and their contents.

- Use options from the Halftones panel sparingly.

- Modify and crop imported graphics in their original application.

Do the following to minimize the printing time for imported graphics:

- Bitmap images: scale, crop, or rotate EPS, TIFF, and other bitmap images in an image-editing application before you place them.

- Vector graphics: select imported PICT or CGM graphics, then select Modify > Alter Path > Simplify or Xtras > Cleanup > Simplify.

- On the Macintosh, print images in the binary data format to create a smaller file than ASCII encoding, thus reducing print time. (Select Binary from the Images pop-up menu in the Output Options dialog box.)

    Note: Windows networks do not support binary image data.

To print text faster, follow these guidelines:

- Use text on a path sparingly.

- Limit the number of typefaces used in the document.

- Use the Zoom effect sparingly—it prints slower than the other effects.

- Deselect Unlimited Downloadable Fonts in the Print Setup dialog box to prevent FreeHand from sending a font to the printer each time it is encountered in a document.

To reduce memory overhead and speed printing, FreeHand downloads to a PostScript printer only the fonts necessary to print the specified pages and does not download fonts that appear only on the pasteboard.

INDEX

w

Wand Color Tolerance setting 325
Warn Before Launch and Edit option 322
warping objects 222
web file formats, defined 344
WebSafe option 356
WebSnap option 356
widows 256
Windows
    installing and starting FreeHand in 8
    system requirements for 7
    uninstalling FreeHand in 8
    using wizards in 68
word spacing 256
wrapping tab 262

x

Xtras
    Animate 331
    Cleanup 386
    Color Control 162
    Convert to Grayscale 162
    Correct Direction 128
    Crop 132
    Darken 162
    Delete 386
    Delete Empty Text Blocks 235
    Delete Unused Named Colors 161
    Desaturate 162
    Divide 130
    Expand Stroke 135
    File Info 342
    Inset Path 136
    installing 27
    Intersect 130
    Lighten 162
    managing 27
    Name All Colors 156
    Punch 131
    Randomize Named Colors 163
    Release to Layers 331
    removing 27
    Saturate 162
    Union 129
    Xtra Operations toolbar 22, 27
    Xtra Tools toolbar 22, 27

z

zero point, changing 53
Zoom effect 286
Zoom tool 31, 32